

Emprise JavaScript Charts

Developer's Guide

© 2008 Emprise Corporation. All Rights Reserved.

Table of Contents

Part I Getting Started	1
1 Overview	1
2 Implementation Instructions	2
3 Creating Your First Chart	5
4 Customizing Your Chart	12
Y Axis	15
X Axis	15
Hint	16
Chart Body	16
Legend	17
5 Version 1.x Compatibility	17
Version 1.x Compatibility	17
Deprecated Properties, Methods and Events	17
Part II Deployment	19
Part III Changes	19
1 Changes in version 2.0	19
2 Changes in version 1.3.1	20
3 Changes in version 1.3	20
4 Changes in version 1.2.1	21
5 Changes in version 1.2	21
6 Changes in version 1.1	23
7 Changes in version 1.0.1	24
8 Changes in version 1.0	25
Part IV Data Formats	26
1 XML - Full	27
2 XML - Short	28
3 XML - Compact	29
Part V API Reference	29
1 EJSC	29
Properties	29
DefaultImagePath	29
DefaultColors	29
DefaultBarColors	30
DefaultPieColors	31
STRINGS	31
2 EJSC.Chart	32

Properties	32
allow_interactivity	32
allow_mouse_wheel_zoom	33
allow_move	33
allow_zoom	34
allow_hide_error	34
auto_find_point_by_x	34
auto_resize	35
auto_zoom	35
axis_bottom	36
axis_left	37
axis_right	38
axis_top	38
background	39
building_message	39
drawing_message	40
legend_title	40
max_zoom_message	40
message_timeouts	40
proximity_snap	40
show_hints	41
show_legend	41
show_messages	42
show_titlebar	42
title	42
Methods	43
acquireSeries	43
addSeries	43
clearSelectedPoint	44
exportSVG	44
exportSVGLegend	45
findClosestPoint	47
getMinMaxYInXRange	47
getZoomBoxPixelCoordinates	48
hideTitlebar	48
hideZoomBox	48
redraw	48
remove	49
removeSeries	49
selectPoint	49
setAutoResize	49
setLegendTitle	49
setTitle	50
showTitlebar	50
showZoomBox	50
Events	51
onAfterBuild	51
onAfterDraw	51
onAfterMove	51
onAfterSelectPoint	51
onAfterUnselectPoint	52
onAfterZoom	52
onBeforeBuild	52
onBeforeDoubleClick	52

onBeforeDraw.....	52
onBeforeSelectPoint.....	53
onBeforeUnselectPoint.....	53
onDoubleClickPoint.....	53
onShowHint.....	53
onShowMessage.....	54
onUserBeginZoom.....	54
onUserEndZoom.....	54
Deprecated	55
Properties	55
force_static_points.....	55
force_static_points_x.....	55
force_static_points_y.....	55
legendTitle	55
show_crosshairs.....	55
show_grid	55
show_mouse_position.....	55
show_x_axis	55
show_y_axis	55
x_axis_caption	55
x_axis_className.....	55
x_axis_extremes_ticks.....	55
x_axis_formatter.....	55
x_axis_max_tick_interval.....	56
x_axis_min_tick_interval.....	56
x_axis_minor_ticks	56
x_axis_size	56
x_axis_stagger_ticks.....	56
x_axis_tick_className.....	56
x_axis_tick_count.....	56
x_cursor_position_caption	56
x_cursor_position_formatter.....	56
x_max	56
x_min	56
x_value_hint_caption	56
x_zero_plane	56
y_axis_caption	56
y_axis_className.....	56
y_axis_extremes_ticks.....	56
y_axis_formatter.....	57
y_axis_max_tick_interval.....	57
y_axis_min_tick_interval.....	57
y_axis_minor_ticks	57
y_axis_size	57
y_axis_tick_className.....	57
y_axis_tick_count.....	57
y_cursor_position_caption	57
y_cursor_position_formatter.....	57
y_max	57
y_min	57
y_value_hint_caption	57
y_zero_plane	57
Methods	57
addXAxisBin	57

addYAxisBin	57
convertPixelToPoint.....	58
convertPointToPoint.....	58
findClosestPointInSeries	58
hideGrid	58
hideXAxis	58
hideYAxis	58
getXExtremes	58
getYExtremes	58
getZoom	58
removeXAxisBin	58
removeYAxisBin	58
selectClosestPoint.....	58
setCrosshairs	58
setXAxisCaption	58
setXExtremes	58
setYAxisCaption	58
setYExtremes	59
setZoom	59
showGrid	59
showXAxis	59
showYAxis	59
Events	59
onAfterShowCrosshairs	59
onBeforeBeginZoom	59
onBeforeEndZoom.....	59
onShowCrosshairs.....	59
onXAxisNeedsTicks.....	59
onYAxisNeedsTicks	59
3 Axes Types	59
LinearAxis	59
Properties	60
background (inherited).....	60
border (inherited).....	60
caption (inherited).....	61
caption_class (inherited)	61
color (inherited)	62
crosshair (inherited).....	62
cursor_position (inherited).....	63
extremes_ticks (inherited)	64
force_static_points (inherited).....	64
formatter (inherited)	64
grid (inherited)	65
hint_caption (inherited)	66
label_class (inherited).....	66
major_ticks (inherited).....	67
max_extreme (inherited).....	67
min_extreme (inherited)	68
minor_ticks (inherited).....	68
size (inherited)	69
stagger_ticks (inherited).....	69
visible (inherited).....	70
zero_plane (inherited).....	70
Methods	71

addBin (inherited).....	71
getExtremes (inherited).....	72
getZoom (inherited).....	72
getZoomBoxCoordinates (inherited).....	72
hide (inherited)	72
hideGrid (inherited)	73
pixelToPoint (inherited).....	73
pointToPixel (inherited).....	73
removeBin (inherited).....	73
resetZoom (inherited).....	74
setCaption (inherited).....	74
setCrosshair (inherited).....	74
setExtremes (inherited).....	74
setZoom (inherited).....	75
show (inherited)	75
showGrid (inherited).....	75
Events	75
onHideCrosshair (inherited).....	75
onHideCursorPosition (inherited).....	76
onNeedsTicks (inherited).....	76
onShowCrosshair (inherited).....	77
onShowCursorPosition (inherited).....	77
LogarithmicAxis	77
Properties	78
background (inherited).....	78
base	78
border (inherited).....	79
caption (inherited).....	79
caption_class (inherited).....	80
color (inherited)	80
crosshair (inherited).....	81
cursor_position (inherited).....	81
extremes_ticks (inherited).....	82
force_static_points (inherited).....	82
formatter (inherited)	83
grid (inherited)	83
hint_caption	84
label_class (inherited).....	84
major_ticks (inherited).....	85
max_extreme (inherited).....	86
min_extreme (inherited).....	86
minor_ticks (inherited).....	87
size (inherited)	87
stagger_ticks (inherited).....	88
visible (inherited).....	88
zero_plane (inherited).....	89
Methods	89
addBin (inherited).....	89
getExtremes (inherited).....	90
getZoom (inherited).....	90
getZoomBoxCoordinates (inherited).....	90
hide (inherited)	91
hideGrid (inherited)	91
pixelToPoint (inherited).....	91

pointToPixel (inherited).....	91
removeBin (inherited).....	92
resetZoom (inherited).....	92
setCaption (inherited).....	92
setCrosshair (inherited).....	93
setExtremes (inherited).....	93
setZoom (inherited).....	93
show (inherited).....	93
showGrid (inherited).....	94
Events	94
onHideCrosshair (inherited).....	94
onHideCursorPosition (inherited).....	94
onNeedsTicks (inherited).....	94
onShowCrosshair (inherited).....	95
onShowCursorPosition (inherited).....	95
4 Series Types	96
EJSC.AnalogGaugeSeries	96
Properties	97
anchor	97
axis	97
delayLoad (inherited).....	98
fillColor	98
fillOpacity	98
height	98
label	99
legendIsVisible (inherited).....	99
lock	99
marker_position.....	100
max	100
min	100
minorTick	101
needle	101
position	102
range	102
range_degrees	103
ranges	103
start_degree	103
tick	103
tickCount	104
title (inherited)	104
visible (inherited).....	104
width	105
x_axis_formatter (inherited).....	105
Methods	105
getDataHandler (inherited)	105
getVisibility (inherited).....	105
hide (inherited)	106
hideLegend (inherited).....	106
reload (inherited).....	106
setDataHandler (inherited)	106
setTitle (inherited)	106
show (inherited).....	107
showLegend (inherited)	107
Events	107

onAfterDataAvailable (inherited).....	107
onAfterVisibilityChange (inherited).....	107
onBeforeVisibilityChange (inherited).....	108
Data Formats	108
EJSC.AreaSeries	109
Properties	110
autosort (inherited).....	110
closeLine	110
color (inherited).....	110
coloredLegend (inherited).....	111
delayLoad (inherited).....	111
drawPoints (inherited).....	111
hint_string (inherited).....	111
legendIsVisible (inherited).....	112
lineOpacity (inherited).....	112
lineWidth (inherited)	112
opacity (inherited).....	112
pointBorderColor (inherited).....	113
pointBorderSize (inherited)	113
pointColor (inherited).....	113
pointSize (inherited).....	113
title (inherited)	114
visible (inherited).....	114
x_axis (inherited)	114
x_axis_formatter (inherited).....	114
y_axis	115
y_axis_formatter (inherited).....	115
Methods	115
getDataHandler (inherited)	115
getVisibility (inherited).....	115
hide (inherited)	115
hideLegend (inherited).....	116
reload (inherited).....	116
setColor (inherited)	116
setColoredLegend (inherited).....	116
setDataHandler (inherited)	117
setLineWidth (inherited).....	117
setOpacity (inherited)	117
setTitle (inherited)	117
show (inherited)	117
showLegend (inherited).....	118
Events	118
onAfterDataAvailable (inherited).....	118
onAfterVisibilityChange (inherited).....	118
onBeforeVisibilityChange (inherited).....	118
onShowHint (inherited)	119
Data Formats	119
Text Replacement Options.....	120
EJSC.BarSeries	120
Properties	121
autosort (inherited).....	121
color (inherited).....	121
coloredLegend (inherited).....	122
defaultColors	122

delayLoad (inherited).....	122
groupedBars	122
hint_string (inherited).....	123
intervalOffset	123
legendIsVisible (inherited).....	124
lineOpacity (inherited).....	124
lineWidth (inherited)	124
opacity (inherited).....	124
orientation	125
ranges	125
title (inherited)	126
treeLegend	126
useColorArray	126
visible (inherited).....	127
x_axis (inherited)	127
x_axis_formatter (inherited).....	127
y_axis (inherited)	127
y_axis_formatter (inherited).....	127
Methods	128
addRange	128
clearRanges	128
deleteRange	128
getBarSize	128
getDataHandler (inherited)	129
getPoints	129
getVisibility (inherited).....	129
hide (inherited)	129
hideLegend (inherited).....	129
reload (inherited).....	130
setColor (inherited)	130
setColoredLegend (inherited).....	130
setDataHandler (inherited)	130
setDefaultColors	131
setGroupedBars	131
setIntervalOffset.....	131
setLineWidth (inherited)	131
setOpacity (inherited)	132
setTitle (inherited)	132
show (inherited)	132
showLegend (inherited)	132
Events	133
onAfterDataAvailable (inherited).....	133
onAfterVisibilityChange (inherited).....	133
onBarNeedsColor.....	133
onBeforeVisibilityChange (inherited).....	134
onShowHint (inherited)	134
Data Formats	134
Text Replacement Options.....	136
EJSC.CandlestickSeries	136
Properties	137
autosort (inherited)	137
color (inherited).....	137
coloredLegend (inherited).....	138
delayLoad (inherited)	138

gain	138
hint_string (inherited)	139
intervalOffset	139
legendIsVisible (inherited)	140
lineOpacity (inherited)	140
lineWidth (inherited)	140
loss	141
opacity (inherited)	141
title (inherited)	142
visible (inherited)	142
x_axis (inherited)	142
x_axis_formatter (inherited)	142
y_axis (inherited)	143
y_axis_formatter (inherited)	143
Methods	143
findClosestPoint (inherited)	143
getDataHandler (inherited)	143
getVisibility (inherited)	144
hide (inherited)	144
hideLegend (inherited)	144
reload (inherited)	144
setColor (inherited)	144
setColoredLegend (inherited)	145
setDataHandler (inherited)	145
setLineOpacity (inherited)	145
setLineWidth (inherited)	145
setOpacity (inherited)	145
setTitle (inherited)	146
show (inherited)	146
showLegend (inherited)	146
Events	146
onAfterDataAvailable (inherited)	146
onAfterVisibilityChange (inherited)	147
onBeforeVisibilityChange (inherited)	147
onShowHint (inherited)	147
Data Formats	147
Text Replacement Options	149
EJSC.FloatingBarSeries	149
Properties	150
autosort (inherited)	150
color (inherited)	150
coloredLegend (inherited)	150
defaultColors (inherited)	150
delayLoad (inherited)	151
groupedBars (inherited)	151
hint_string (inherited)	151
intervalOffset (inherited)	152
legendIsVisible (inherited)	152
lineOpacity (inherited)	153
lineWidth (inherited)	153
opacity (inherited)	153
orientation (inherited)	153
ranges (inherited)	154
title (inherited)	154

treeLegend (inherited).....	155
useColorArray (inherited).....	155
visible (inherited).....	155
x_axis (inherited).....	155
x_axis_formatter (inherited).....	156
y_axis (inherited).....	156
y_axis_formatter (inherited).....	156
Methods	156
addRange (inherited)	156
clearRanges (inherited)	157
deleteRange (inherited)	157
getBarSize (inherited)	157
getDataHandler (inherited)	157
getPoints (inherited)	157
getVisibility (inherited)	158
hide (inherited)	158
hideLegend (inherited)	158
reload (inherited)	158
setColor (inherited)	158
setColoredLegend (inherited)	159
setDataHandler (inherited)	159
setDefaultColors (inherited)	159
getGroupedBars (inherited)	160
setIntervalOffset (inherited)	160
setLineWidth (inherited)	160
setOpacity (inherited)	160
setTitle (inherited)	160
show (inherited)	160
showLegend (inherited)	161
Events	161
onAfterDataAvailable (inherited)	161
onAfterVisibilityChange (inherited)	161
onBarNeedsColor (inherited)	161
onBeforeVisibilityChange (inherited)	162
onShowHint (inherited)	163
Data Formats	163
Text Replacement Options.....	165
EJSC.FunctionSeries	165
Properties	166
color (inherited).....	166
coloredLegend (inherited).....	166
hint_string (inherited).....	166
legendIsVisible (inherited)	167
lineOpacity (inherited)	167
lineWidth (inherited)	167
title (inherited)	167
visible (inherited)	168
x_axis (inherited)	168
x_axis_formatter (inherited)	168
y_axis (inherited)	168
y_axis_formatter (inherited)	168
Methods	169
getVisibility (inherited)	169
hide (inherited)	169

hideLegend (inherited).....	169
reload (inherited).....	169
setColor (inherited)	170
setColoredLegend (inherited).....	170
setLineWidth (inherited).....	170
setTitle (inherited)	170
show (inherited)	171
showLegend (inherited)	171
Events	171
onAfterVisibilityChange (inherited)	171
onBeforeVisibilityChange (inherited).....	171
onShowHint (inherited)	172
Text Replacement Options.....	172
EJSC.LineSeries	172
Properties	173
autosort (inherited)	173
color (inherited).....	173
coloredLegend (inherited).....	173
drawPoints	174
hint_string (inherited).....	174
legendIsVisible (inherited).....	174
lineOpacity (inherited).....	174
lineWidth (inherited)	175
pointBorderColor.....	175
pointBorderSize	175
pointColor	175
pointSize	176
title (inherited)	176
visible (inherited).....	176
x_axis (inherited)	176
x_axis_formatter (inherited).....	177
y_axis (inherited)	177
y_axis_formatter (inherited).....	177
Methods	177
getDataHandler (inherited)	177
getVisibility (inherited).....	178
hide (inherited)	178
hideLegend (inherited).....	178
reload (inherited).....	178
setColor (inherited)	179
setColoredLegend (inherited).....	179
setDataHandler (inherited)	179
setLineWidth (inherited)	179
setTitle (inherited)	179
show (inherited)	180
showLegend (inherited)	180
Events	180
onAfterDataAvailable (inherited).....	180
onAfterVisibilityChange (inherited)	180
onBeforeVisibilityChange (inherited).....	181
onShowHint (inherited)	181
Data Formats	181
Text Replacement Options.....	182
EJSC.OpenHighLowCloseSeries	183

Properties	184
autosort (inherited)	184
color (inherited)	184
coloredLegend (inherited)	184
delayLoad (inherited)	185
gain	185
hint_string (inherited)	186
intervalOffset	186
legendIsVisible (inherited)	187
lineOpacity (inherited)	187
lineWidth (inherited)	187
loss	188
opacity (inherited)	188
title (inherited)	189
visible (inherited)	189
x_axis (inherited)	189
x_axis_formatter (inherited)	189
y_axis (inherited)	190
y_axis_formatter (inherited)	190
Methods	190
findClosestPoint (inherited)	190
getDataHandler (inherited)	190
getVisibility (inherited)	190
hide (inherited)	191
hideLegend (inherited)	191
reload (inherited)	191
setColor (inherited)	191
setColoredLegend (inherited)	192
setDataHandler (inherited)	192
setLineOpacity (inherited)	192
setLineWidth (inherited)	192
setOpacity (inherited)	192
setTitle (inherited)	193
show (inherited)	193
showLegend (inherited)	193
Events	193
onAfterDataAvailable (inherited)	193
onAfterVisibilityChange (inherited)	194
onBeforeVisibilityChange (inherited)	194
onShowHint (inherited)	194
Data Formats	194
Text Replacement Options (COPY)	196
EJSC.PieSeries	196
Properties	197
defaultColors	197
delayLoad (inherited)	197
height	197
hint_string (inherited)	197
legendIsVisible (inherited)	198
lineOpacity (inherited)	198
lineWidth (inherited)	198
opacity (inherited)	198
position	199
title (inherited)	199

total_value	199
treeLegend	200
visible (inherited).....	200
width	200
x_axis_formatter (inherited).....	200
Methods	200
findCenter	200
findCenterOfCurve.....	201
getDataHandler (inherited)	201
getPoints	201
getTotalValue	202
getVisibility (inherited).....	202
hide (inherited)	202
hideLegend (inherited).....	202
reload (inherited).....	202
resetTotalValue.....	203
setDataHandler (inherited)	203
setDefaultColors	203
setLineWidth (inherited).....	204
setOpacity (inherited)	204
setTitle (inherited)	204
setTotalValue	204
show (inherited)	205
showLegend (inherited)	205
Events	205
onAfterDataAvailable (inherited).....	205
onAfterVisibilityChange (inherited).....	205
onBeforeVisibilityChange (inherited).....	206
onPieceNeedsColor.....	206
onShowHint (inherited)	206
Data Formats	206
Text Replacement Options.....	208
EJSC.ScatterSeries	208
Properties	209
autosort (inherited).....	209
color (inherited).....	209
coloredLegend (inherited).....	209
delayLoad (inherited).....	209
hint_string (inherited).....	210
legendIsVisible (inherited).....	210
lineOpacity (inherited).....	210
lineWidth (inherited)	210
opacity (inherited).....	211
pointSize	211
pointStyle	211
title (inherited)	211
visible (inherited).....	212
x_axis (inherited)	212
x_axis_formatter (inherited).....	212
y_axis (inherited)	212
y_axis_formatter (inherited).....	213
Methods	213
getDataHandler (inherited)	213
getVisibility (inherited)	213

hide (inherited)	213
hideLegend (inherited)	214
reload (inherited)	214
setColor (inherited)	214
setColoredLegend (inherited)	214
setDataHandler (inherited)	214
setLineWidth (inherited)	215
setOpacity (inherited)	215
setPointStyle	215
setTitle (inherited)	215
show (inherited)	216
showLegend (inherited)	216
Events	216
onAfterDataAvailable (inherited)	216
onAfterVisibilityChange (inherited)	216
onBeforeVisibilityChange (inherited)	217
onShowHint (inherited)	217
Data Formats	217
Text Replacement Options	219
EJSC.StackedBarSeries	219
Properties	219
groupedBars (inherited)	219
hint_string (inherited)	219
intervalOffset (inherited)	220
legendIsVisible (inherited)	220
title (inherited)	220
orientation (inherited)	221
visible (inherited)	221
x_axis (inherited)	221
y_axis (inherited)	221
Methods	222
getBarSize (inherited)	222
addSeries	222
getVisibility (inherited)	222
hide (inherited)	223
hideLegend (inherited)	223
reload (inherited)	223
removeSeries	223
setGroupedBars (inherited)	224
setIntervalOffset (inherited)	224
setTitle (inherited)	224
show (inherited)	224
showLegend (inherited)	225
Events	225
onAfterVisibilityChange (inherited)	225
onBeforeVisibilityChange (inherited)	225
onShowHint (inherited)	225
Text Replacement Options (COPY)	226
EJSC.TrendSeries	226
Properties	227
color (inherited)	227
coloredLegend (inherited)	227
hint_string (inherited)	227
legendIsVisible (inherited)	228

lineOpacity (inherited).....	228
lineWidth (inherited)	228
title (inherited)	228
visible (inherited).....	228
x_axis (inherited).....	229
x_axis_formatter (inherited).....	229
y_axis (inherited).....	229
y_axis_formatter (inherited).....	229
Methods	230
getVisibility (inherited).....	230
hide (inherited)	230
hideLegend (inherited).....	230
reload (inherited).....	230
setColor (inherited)	231
setColoredLegend (inherited).....	231
setLineWidth (inherited).....	231
setTitle (inherited)	231
show (inherited)	231
showLegend (inherited)	232
Events	232
onAfterVisibilityChange (inherited)	232
onBeforeVisibilityChange (inherited).....	232
onShowHint (inherited)	232
Text Replacement Options.....	233
5 Data Handlers	233
EJSC.XMLDataHandler	233
Properties	233
requestType (inherited)	233
url (inherited)	234
urlData (inherited)	234
Methods	234
getUrl (inherited)	234
loadData (inherited)	235
setRequestType (inherited).....	235
setUrl (inherited)	235
setUrlData (inherited)	235
setXMLData (inherited)	236
Events	236
onDataAvailable (inherited)	236
onDataReady (inherited)	236
onNeedsData (inherited)	236
EJSC.XMLStringDataHandler	237
Methods	238
getXML	238
loadData (inherited)	238
setXML	238
Events	238
onDataAvailable (inherited)	238
EJSC.ArrayDataHandler	239
Methods	239
getArray	239
loadData (inherited)	239
setArray	239
Events	240

onDataAvailable (inherited).....	240
EJSC.CSVFileDataHandler	240
Properties	240
requestType (inherited)	240
url (inherited)	240
urlData (inherited)	241
Methods	241
getUrl (inherited)	241
loadData (inherited).....	241
setRequestType (inherited).....	242
setUrl (inherited)	242
setUrlData (inherited)	242
setXMLData (inherited)	242
Events	243
onDataAvailable (inherited).....	243
onDataReady (inherited)	243
onNeedsData (inherited)	243
EJSC.CSVStringDataHandler	244
Methods	244
getCSV	244
loadData (inherited).....	244
setCSV	245
Events	245
onDataAvailable (inherited).....	245
EJSC.JSONFileDataHandler	245
Properties	245
requestType (inherited)	245
url (inherited)	246
urlData (inherited)	246
Methods	246
getUrl (inherited)	246
loadData (inherited).....	247
setRequestType (inherited).....	247
setUrl (inherited)	247
setUrlData (inherited)	247
setXMLData (inherited)	248
Events	248
onDataAvailable (inherited).....	248
onDataReady (inherited)	248
onNeedsData (inherited)	249
EJSC.JSONStringDataHandler	249
Methods	249
getJSON	249
loadData (inherited).....	250
setJSON	250
Events	250
onDataAvailable (inherited).....	250
6 Label Formatters	250
EJSC.NumberFormatter	250
Properties	251
currency_align	251
currency_position.....	251
currency_symbol.....	251
decimal_separator	251

forced_decimals	252
negative_symbol	252
thousand_separator	252
variable_decimals	252
Methods	253
format (inherited)	253
EJSC.DateFormatter	253
Properties	253
format_string	253
timezoneOffset	254
useUTC	255
Methods	255
format (inherited)	255
EJSC.StringFormatter	255
Properties	255
append	255
prefix	256
Methods	256
format (inherited)	256
Events	256
onNeedsFormat.....	256
7 Base Classes	257
EJSC.Inheritable	257
EJSC.AjaxDataHandler	257
Properties	257
requestType	257
url	257
urlData	257
Methods	258
getUrl	258
loadData (inherited).....	258
setRequestType.....	258
setUrl	259
setUrlData	259
setXMLData	259
Events	260
onDataAvailable (inherited).....	260
onDataReady	260
onNeedsData	260
EJSC.Axis	261
Properties	261
background	261
border	261
caption	262
caption_class	262
color	263
crosshair	263
cursor_position	264
extremes_ticks	264
force_static_points	265
formatter	265
grid	266
hint_caption	266
label_class	267

major_ticks	267
max_extreme	268
minor_ticks	268
min_extreme	269
size	270
stagger_ticks	270
visible	271
zero_plane	271
Methods	272
addBin	272
getExtremes	272
getZoom	273
getZoomBoxCoordinates	273
hide	273
hideGrid	273
resetZoom	274
pixelToPoint	274
pointToPixel	274
removeBin	274
setCaption	275
setCrosshair	275
setExtremes	275
setZoom	275
show	276
showGrid	276
Events	276
onHideCrosshair	276
onHideCursorPosition	276
onNeedsTicks	277
onShowCrosshair	278
onShowCursorPosition	278
EJSC.DataHandler	278
Methods	278
loadData	278
Events	278
onDataAvailable	278
EJSC.GaugeSeries	279
Properties	279
color (inherited)	279
coloredLegend (inherited)	279
delayLoad (inherited)	279
legendIsVisible (inherited)	280
lineOpacity (inherited)	280
lineWidth (inherited)	280
opacity (inherited)	280
title (inherited)	281
visible (inherited)	281
x_axis_formatter (inherited)	281
Methods	281
getDataHandler (inherited)	281
getVisibility (inherited)	282
hide (inherited)	282
hideLegend (inherited)	282
reload (inherited)	282

setColor (inherited)	282
setColoredLegend (inherited)	283
setDataHandler (inherited)	283
setLineOpacity (inherited)	283
setLineWidth (inherited)	283
setOpacity (inherited)	283
setTitle (inherited)	284
show (inherited)	284
showLegend (inherited)	284
Events	284
onAfterDataAvailable (inherited)	284
onAfterVisibilityChange (inherited)	285
onBeforeVisibilityChange (inherited)	285
EJSC.Formatter	285
Properties	285
format_string	285
Methods	286
format	286
EJSC.Point	286
Properties	286
label	286
userdata	286
x	287
y	287
EJSC.Series	287
Properties	287
autosort	287
color	287
coloredLegend	288
delayLoad	288
hint_string	288
legendIsVisible	289
lineOpacity	289
lineWidth	289
opacity	289
title	290
visible	290
x_axis	290
x_axis_formatter	290
y_axis	291
y_axis_formatter	291
Methods	291
findClosestPoint	291
getDataHandler	291
getVisibility	291
hide	292
hideLegend	292
reload	292
setColor	292
setColoredLegend	293
setDataHandler	293
setLineOpacity	293
setLineWidth	293
setOpacity	293

setTitle	294
show	294
showLegend	294
Events	294
onAfterDataAvailable.....	294
onAfterVisibilityChange	295
onBeforeVisibilityChange.....	295
onShowHint	295
8 Other Classes	295
EJSC.BarPoint	295
Properties	296
label (inherited)	296
userdata (inherited)	296
x (inherited)	296
y (inherited)	296
EJSC.FloatingBarPoint	296
Properties	297
label (inherited)	297
max	297
min	297
userdata (inherited)	297
x (inherited)	298
y (inherited)	298
EJSC.GaugePoint	298
Properties	298
label (inherited)	298
userdata (inherited)	299
x (inherited)	299
EJSC.PiePoint	299
Properties	299
label (inherited)	299
userdata (inherited)	300
x (inherited)	300
EJSC.StockPoint	300
Properties	300
close	300
high	300
label (inherited)	300
low	301
open	301
userdata (inherited)	301
x (inherited)	301
EJSC.XYPoint	301
Properties	302
label (inherited)	302
userdata (inherited)	302
x (inherited)	302
y (inherited)	302
9 Using Colors	302
10 Text Replacement Options	303
11 Exporting To SVG	303

Part VI Getting Support**304**

1 Getting Started

1.1 Overview

Welcome to Emprise JavaScript Charts. Constructed entirely in JavaScript the days of annoying plugin downloads and browser security warnings are gone. With genuine ease of use and complete customization Emprise JavaScript Charts provides you with the tools you need to publish your data quickly and in a variety of formats. With its wide range of interactive features, simple and straightforward implementation, and unparalleled functionality, Emprise JavaScript Charts is the clear first choice for all your charting needs.

Here's a quick sampling of just some of the features included:

- **Interactive:** Features such as Hints, Mouse Tracking, Mouse Events, Key Tracking and Events, Zooming, Scrolling, and Crosshairs raise interactivity and user experience in web charting to a new level.
- **Axis Scaling:** There's no need to determine your data range before hand. EJSChart will calculate and scale automatically to fit whatever data it is presented with.
- **Auto Zooming, Scrolling:** Too much data and not enough screen real estate? Show it all. Let your end users zoom in on the pieces they're most interested in. Axis locking for single axis zoom, scrolling and automatic axis scaling are all included.
- **Stackable Series:** Multiple chart series can be stacked and combined to fit many charting needs.
- **Multiple Series Types:** Line, Area, Scatter, Pie, Bar and Function series are just the beginning. New series are just a few lines of JavaScript code away.
- **Ajax-Driven Data:** EJSChart supports XML-formatted data and loads data on the fly. New

series can be added and data updated in real time without page reloads.

- **Compatible:** Built with compatibility in mind and tested on all major browsers, you can be assured your charts will function consistently for the broadest range of end users. See the full list of compatible browsers on our System Requirements page.
- **Plugin Free:** 100% Pure JavaScript Charting Solution. No more worries of incompatible plugin versions or confusing security warnings. EJSChart is pure JavaScript and requires no client installation.
- **Customizable:** Every aspect of the charting display can be configured and customized through well-documented properties and methods. Want to do more than just change the color of the background? Need a series type which doesn't already exist? EJSChart is fully customizable and extendable to provide the greatest flexibility and integration for existing site designs and needs.

1.2 Implementation Instructions

Ease of implementation was an important factor considered in the development of EJSChart. The process from purchase to user “wow” takes just a matter of minutes and can be completed following the few easy to follow steps detailed below. Designed for all users, no previous JavaScript knowledge is required to implement EJSChart or take advantage of its many features. The steps below will guide you through the installation and testing of the EJSChart library.

1. Create a new directory in the home directory of your webpage and name it EJSChart.
2. Copy the contents (all files and directories) of the `/dist/` folder provided in your EJSChart download package into your newly created EJSChart folder on your web server.
3. Open the webpage that you wish to place an example chart on. If you do not currently have one or wish to use a test page for this purpose one has been provided for you in the How To directory included with your download. This file is named `mydemochart.html` and can be edited in your preferred html editor or even notepad.
4. Copy `<script type="text/javascript">`

`src="/EJSChart/EJSChart.js"></script>` into the head section of your webpage.

*This path can be modified as necessary to correctly point to EJSChart.js.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="EJSChart Demo Chart HTML Page">

    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>

  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart
into.</p>
  </body>
</html>
```

5. Create a div on your page where you would like the chart to be displayed. The size of the chart can be specified within the div properties if desired. The div is created by pasting `<div id="myChart" style="width:450px; height:330px;"></div>` where desired in the body of your webpage. The style width and height properties can be adjusted as desired.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="EJSChart Demo Chart HTML Page">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart
into.</p>

    <div id="myChart" style="width:450px; height:330px;"></div>

  </body>
</html>
```

6. To turn the div into a chart paste the following sample code at the end of your webpage.

```
<script type="text/javascript">
  var chart = new EJSC.Chart("myChart");
  chart.addSeries(new EJSC.AreaSeries(
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,2],[5,3]]))
);
</script>
```


```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="EJSChart Demo Chart HTML Page">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart
    into.</p>

    <div id="myChart" style="width:450px; height:330px;"></div>

    <script type="text/javascript">
      var chart = new EJSC.Chart("myChart");
      chart.addSeries(new EJSC.AreaSeries(
        new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,2],[5,3]]))
      );
    </script>
  </body>
</html>
```

7. Upload your edited webpage to your web server. Visit your webpage and view the demo

chart located on the page where the div was placed.



1.3 Creating Your First Chart

Now that you have created and tested your first demonstration chart on your web server it is time to create your own chart. This demonstration will guide you through creating your first chart and introduce you to some of the many available features and methods of customization available to you in Emprise JavaScript Charts. If you have not yet completed the [Implementation Instructions](#) it is recommended that you do so before continuing with this section as they guide you through uploading the necessary files to your web server.

1. Open the webpage that you wish to place your first custom chart on. If you do not currently have one or wish to use a test page for this purpose one has been provided for you in the

HowTo directory included with your download. This file is named myfirstchart.html and can be edited in your preferred html editor or even notepad.

2. Copy `<script type="text/javascript"`
`src="/EJSChart/EJSChart.js"></script>` into the head section of your webpage.
- *This path can be modified as necessary to correctly point to EJSChart.js.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">

    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>

  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart into.</p>
  </body>
</html>
```

3. Create a div on your page where you would like the chart to be displayed by pasting `<div id="myFirstChart" style="width:600px; height:400px;"></div>` where desired in the body of your webpage.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart into.</p>

    <div id="myFirstChart" style="width:600px; height:400px;"></div>

  </body>
</html>
```

4. The next step is to create the chart object. This is done at the end of your html file, directly before the closing body tag;`</body>`. To begin define the text as JavaScript with `<script type="text/javascript">` and create a chart object on the next line using `var chart = new EJSC.Chart("myFirstChart");` Be sure that the div id as identified within the

body of your webpage matches the title you place within the parenthesis when creating your chart. In this example it is ‘myFirstChart’. Failure to create the appropriate div’s for the chart to be placed in will result in errors and prevent your chart from being displayed.

The properties of your chart including its visual appearance and interactivity are highly customizable by adjusting its properties. Instructions on how to accomplish this can be found on the [Customizing Your Chart](#) page of this guide.

In this example code the chart has been customized to remove the legend and set a custom title by adding:

```
<script type="text/javascript">
    var chart = new EJSC.Chart(
        "myFirstChart",
        {
            show_legend: false,
            title: "My First Custom Chart"
        }
    );

<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
    <head>
        <title>My Demo Chart</title>
        <meta name="Author" content="Emprise Corporation">
        <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">
        <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
    </head>
    <body>
        <p>This is a sample page that is used to copy and paste a demo chart into.</p>

        <div id="myFirstChart" style="width:600px; height:400px;"></div>

        <script type="text/javascript">
            var chart = new EJSC.Chart(
                "myFirstChart",
                {
                    show_legend: false,
                    title: "My First Custom Chart"
                }
            );
        </script>
    </body>
</html>
```

5. Now that the chart has been created the series must be created. The series defines how

your data will be displayed in the chart you are creating. The types of series that are available may vary by license; more details on this can be found on the LICENSE.txt file.

When creating the chart you can also choose which format you will be providing the data in. This is accomplished with the use of different Data Handlers. The formats currently supported by EJSChart are XML file, JavaScript Array, CSV file, and CSV string data. Details on the implementation of each of these data handlers as well as sample code can be found on their respective pages in the Developer Guide help file.

The properties of your series, including its visual appearance and interactivity, are customized by adjusting its properties. Instructions on how to accomplish this can be found on the [Customizing Your Chart](#) page.

In this example code a bar chart was created using the Bar Series, the color was set to green, and the bar border width was set to five pixels. The data to be graphed was specified using the EJSC.ArrayDataHandler. To accomplish this the following code was added:

```
var myChartSeries = new EJSC.BarSeries(
    new EJSC.ArrayDataHandler(
        [
            [ "Month 1",1],
            [ "Month 2",2],
            [ "Month 3",3],
            [ "Month 4",4],
            [ "Month 5",5]
        ]
    )
);
myChartSeries.color = 'rgb(50,210,50)';
myChartSeries.lineWidth = 5;
```

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart into.</p>

    <div id="myFirstChart" style="width:600px; height:400px;"></div>

    <script type="text/javascript">

      var chart = new EJSC.Chart(
        "myFirstChart",
        {
          show_legend: false,
          title: "My First Custom Chart"
        }
      );

      var myChartSeries = new EJSC.BarSeries(
        new EJSC.ArrayDataHandler(
          [
            ["Month 1",1],
            ["Month 2",2],
            ["Month 3",3],
            ["Month 4",4],
            ["Month 5",5]
          ]
        )
      );
      myChartSeries.color = 'rgb(50,210,50)';
      myChartSeries.lineWidth = 5;

    </body>
  </html>
```

6. Once created the series must then be added to the chart using the [addSeries](#) method in the chart class.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart into.</p>

    <div id="myFirstChart" style="width:600px; height:400px;"></div>

    <script type="text/javascript">

      var chart = new EJSC.Chart(
        "myFirstChart",
        {
          show_legend: false,
          title: "My First Custom Chart"
        }
      );

      var myChartSeries = new EJSC.BarSeries(
        new EJSC.ArrayDataHandler(
          [
            ["Month 1",1],
            ["Month 2",2],
            ["Month 3",3],
            ["Month 4",4],
            ["Month 5",5]
          ]
        )
      );
      myChartSeries.color = 'rgb(50,210,50)';
      myChartSeries.lineWidth = 5;

      chart.addSeries(myChartSeries);

    </script>
  </body>
</html>
```

7. Close the JavaScript by inserting </script> at the end.

```
<!doctype html public "-//W3C//DTD HTML 4.0 Transitional//EN">
<html>
  <head>
    <title>My Demo Chart</title>
    <meta name="Author" content="Emprise Corporation">
    <meta name="Description" content="Emprise JavaScript Charts :: Customization Example">
    <script type="text/javascript" src="/EJSChart/EJSChart.js"> </script>
  </head>
  <body>
    <p>This is a sample page that is used to copy and paste a demo chart into.</p>

    <div id="myFirstChart" style="width:600px; height:400px;"></div>

    <script type="text/javascript">

      var chart = new EJSC.Chart(
        "myFirstChart",
        {
          show_legend: false,
          title: "My First Custom Chart"
        }
      );


      var myChartSeries = new EJSC.BarSeries(
        new EJSC.ArrayDataHandler(
          [
            [
              ["Month 1",1],
              ["Month 2",2],
              ["Month 3",3],
              ["Month 4",4],
              ["Month 5",5]
            ]
          ]
        )
      );
      myChartSeries.color = 'rgb(50,210,50)';
      myChartSeries.lineWidth = 5;

      chart.addSeries(myChartSeries);

    </script>

  </body>
</html>
```

8. That's it! Upload the webpage to your web server and you're done.



1.4 Customizing Your Chart

With Emprise JavaScript Charts, the customization options of your chart are endless. This includes visual appearance, which can be modified to integrate fully with any theme or design, as well as chart interactivity, which can range from including user capabilities such as auto zooming and custom hint captions to hidden-axis view only chart displays. Your chart can be customized on the chart and series level via the modification of the chart and series properties.

The first customization options available to you are at the chart level. They can be specified when creating the chart or alternatively after the chart object has been established. The properties available for editing and their syntax can be found in the [Chart Properties](#) section of the help documentation. In addition, examples of their implementation with sample code and the resulting effect on chart display or interactivity are available on the in the /examples/ directory of the distribution package. There are also additional examples available online at

<http://www.ejschart.com/examples/>

The following are a few quick examples of modifying commonly used properties both at and after chart creation:

- Modification of the bottom x and left y axis labels during chart creation:

```
var chart = new EJSC.Chart("myChart", {
    axis_bottom: {
        caption: "Month"
    },
    axis_left: {
        caption: "Temperature"
    }
});
```

- Modification of the bottom x and left y axis labels after chart creation:

```
var chart = new EJSC.Chart("myChart");
chart.axis_bottom.setCaption("Month");
chart.axis_left.setCaption("Temperature");
```

The properties of each series on a chart may also be customized. This is accomplished with the editing of properties in the same way as was done to customize chart properties; either at the time of series creation or following creation. The properties available for editing and their syntax can be found on the [Properties](#) page of each of the different series help sections. In addition, examples of their implementation with sample code and the resulting effect on chart display or interactivity are available on the in the /examples/ directory of the distribution package. There are also additional examples available online at <http://www.ejschart.com/examples/>

The following are a few quick examples of modifying commonly used properties both at and after chart creation:

- Modification of the series lineWidth property during creation:


```
var myChartSeries = new EJSC.FunctionSeries(Math.sin, {lineWidth:  
4});
```

- Modification of the lineWidth property after creation:


```
var myChartSeries = new EJSC.FunctionSeries(Math.sin);  
myChartSeries.setLineWidth(4);
```

In order to fully understand the power of the properties available for customizing it is important to become familiar with the various components of the chart. The following diagram identify many of these components:


Anatomy of a Chart




1.4.1 Y Axis




1.4.2 X Axis




1.4.3 Hint



1.4.4 Chart Body



1.4.5 Legend



1.5 Version 1.x Compatibility

1.5.1 Version 1.x Compatibility

We have moved a significant number of properties and methods into separate classes to support multiple axes and new series types. You may find that properties used in charts you have already developed no longer have the effect expected on your charts. To help with the transition to the new code base we have included a version 1 compatibility JavaScript file.

To have this code included automatically into your page, simply put the following tag in the page header BEFORE you include EJSChart.js:

```
<head>
    <meta name="ejsc-v1-compatibility" content="true"/>
    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>
</head>
```

This utility script will automatically convert the deprecated properties to their version 2 counterparts.

In addition, if you are using a browser, browser extension, or other JavaScript package which implements window.console, the script will log the deprecated properties being converted in order to aide you in upgrading your code.

1.5.2 Deprecated Properties, Methods and Events

The following lists all properties, methods and events which have been deprecated in version 2.0 and are no longer available unless the [v1 Compatibility Script](#) is included.

Properties

[force_static_points](#)
[force_static_points_x](#)
[force_static_points_y](#)
[legendTitle](#)
[show_crosshairs](#)
[show_grid](#)
[show_mouse_position](#)
[show_x_axis](#)
[show_y_axis](#)
[x_axis_caption](#)
[x_axis_className](#)
[x_axis_extremes_ticks](#)
[x_axis_formatter](#)
[x_axis_max_tick_interval](#)
[x_axis_min_tick_interval](#)
[x_axis_minor_ticks](#)
[x_axis_size](#)
[x_axis_stagger_ticks](#)
[x_axis_tick_className](#)
[x_axis_tick_count](#)
[x_cursor_position_caption](#)
[x_cursor_position_formatter](#)
[x_max](#)
[x_min](#)
[x_value_hint_caption](#)
[x_zero_plane](#)
[y_axis_caption](#)
[y_axis_className](#)
[y_axis_extremes_ticks](#)
[y_axis_formatter](#)
[y_axis_max_tick_interval](#)
[y_axis_min_tick_interval](#)
[y_axis_minor_ticks](#)
[y_axis_size](#)
[y_axis_tick_className](#)
[y_axis_tick_count](#)
[y_cursor_position_caption](#)
[y_cursor_position_formatter](#)
[y_max](#)
[y_min](#)
[y_value_hint_caption](#)
[y_zero_plane](#)

Methods

[addXAxisBin](#)
[addYAxisBin](#)
[convertPixelToPoint](#)
[convertPointToPixel](#)
[findClosestPointInSeries](#)
[hideGrid](#)

[hideXAxis](#)
[hideYAxis](#)
[getXExtremes](#)
[getYExtremes](#)
[getZoom](#)
[removeXAxisBin](#)
[removeYAxisBin](#)
[selectClosestPoint](#)
[setCrosshairs](#)
[setXAxisCaption](#)
[setXExtremes](#)
[setYAxisCaption](#)
[setYExtremes](#)
[setZoom](#)
[showGrid](#)
[showXAxis](#)
[showYAxis](#)

Events

[onAfterShowCrosshairs](#)
[onBeforeBeginZoom](#)
[onBeforeEndZoom](#)
[onShowCrosshairs](#)
[onXAxisNeedsTicks](#)
[onYAxisNeedsTicks](#)

2 Deployment

The Emprise JavaScript Charts distribution package includes a compressed and obfuscated version of the source code for easy deployment. The entire /dist/ directory is meant to be placed on a web site, as is, with no modification necessary.

If you have access to the source code (Developer and Enterprise editions) and have made modifications, there is a utility web page located in the /packer/ directory which hosts a compression script powered by Dean Edward's Packer (original source: <http://dean.edwards.name/packer/>)

This utility must be used to compress and obfuscate the JavaScript source code before making it live or distributing it within your own application.

3 Changes

3.1 Changes in version 2.0

Additions

- Multiple X and Y Axes
- Logarithmic Axis
- JSON String and File Data Handlers
- Stacked Bar Series
- Floating Bar Series
- String Formatter for prefixing and appending to labels

- OpenHighLowClose Series
- Candlestick Series
- Filled Scatter Series Points in IE
- Much optimized rendering of axis labels and ticks
- Cleaner and smaller HTML generation of chart objects
- Faster chart rendering and much better support for many charts in a single page
- Removed the need for EJSChartIE.css and EJSChartIE6.css
- Better control over styling of major tick marks
- More styling options for grid lines and axis borders
- Easier customization of cursor position elements
- Background coloring with opacity of the chart area and axes

3.2 Changes in version 1.3.1

Additions

- Added Chart.y_axis_min_tick_interval, y_axis_max_tick_interval, x_axis_min_tick_interval and x_axis_max_tick_interval for finer tick control
- Added tick enhancements when using date values so that the tick interval cannot be less than one millisecond
- Added support for point specific labels in Line/Area/Scatter/Bar series

Bug Fixes

- Fixes issues with onXAxisNeedsTicks and onYAxisNeedsTicks not positioning correctly
- Added check to ensure the selected point is valid before firing onDblClickPoint event
- Updated CSV data handlers to account for pie/gauge series and correctly map labels
- Fixed issues with text bins for Y when using XML data handlers
- Updated array data handler to account for pie/gauge series and correctly map labels
- Fixed issue with gauge border default value
- Fixed issues with gauge drawing when added to a chart but not immediately drawn

3.3 Changes in version 1.3

Additions

- Added AreaSeries.closePath property which determines if the line should return to the zero plane and draw as a closed shape.
- Added PieSeries.findCenterOfCurve(point) method
- Added support for SVG exporting

Modifications

- Modified axis to write out ticks and labels less often
- Line and scatter series are now split into smaller draws in order to support larger data sets in IE
- BarSeries point selection now accounts for proximity_snap setting and the bar's line width
- Added support for text labels (bins) to TrendSeries

Bug Fixes

- Updated color conversion routine to fix issues in IE
- Added additional logic to ajax data handlers to prevent double loading
- Corrected resize issue in IE which could cause an 'Invalid Argument' error
- Updated extremes calculations to correct issues with negative numbers
- getYExtremes() now correctly returns the y axis extremes
- Added additional offset checks in point location routines to account for quirks mode in various browsers
- Fixed issues with xml data handler and processing string values
- PieSeries data points now correctly save and display their labels if defined
- Corrected drawing issues in BarSeries with negative numbers
- Fixed BarSeries drawing in IE with a large number of points
- Corrected BarSeries draw in IE to close the bar line
- Updated PieSeries to reset its available colors correctly when reloading

3.4 Changes in version 1.2.1

Additions

- Added selectPoint and clearSelectedPoint methods to the chart.

Modifications

- Enhanced support for chart with large numbers of series.
- Enabled initial implementation of Series.delayLoad (default true) which controls when a series triggers its data handler to begin data retrieval
- Updated PiePoint and PieSeries to correctly render float values for pie pieces
- Updated PieSeries to handle more 100% piece drawing cases

Bug Fixes

- Fixed issues with series reloading where auto calculated extremes were not reset with new data (affected all series)
- Fixed print rendering issues in all browsers except Opera. The chart now renders as show on screen when printing.
- Fixed XYPoint class to properly recognize the Y value as a number as opposed to a string.
- Fixed inheritance issue with ArrayDataHandler
- Fixed issues with clearing the chart when all loaded series are set invisible
- Fixed PieSeries reload method to reset available colors
- Fixed BarSeries treeLegend property to function properly when useColorArray is false
- Fixed BarSeries reload method to reset available colors
- Fixed range drawing in AnalogGaugeSeries to correctly connect arcs before filling
- Fixed issue with x axis labels not aligning correctly when allow_interactivity was false

3.5 Changes in version 1.2

Additions

- Added classes to better control and track axis bins (text labels)
- Added support for y axis bins
- Added support for shared bins between series (unused bins)
- Added coordinate property to [Chart.y_zero_plane](#) and [Chart.x_zero_plane](#) to allow zero plane to

fall somewhere other than 0

- Added [Chart.force_static_points_x](#) and [Chart.force_static_points_y](#) ([force_static_points](#) works as before, for x only) to force bins when data is numeric
- Implemented [Chart.y_axis_extremes_ticks](#)
- Added support for drawing minor tick marks on the [Y_axis](#) and [Y_axis](#)
- Added [Chart.onXAxisNeedsTicks](#) and [onYAxisNeedsTicks](#) to allow for custom tick configurations
- Added support for [auto sort](#) in all applicable series / data handlers. This is now set by default and may be turned off if data is correctly sorted prior to being handed to the data handler.
- Added support for [color specifications](#) as rgb(0,0,0), rgba(0,0,0,100) and hex (#000000) everywhere colors may be specified
- Added support for mouse wheel to zoom (controlled by [allow_interactivity](#), [allow_zoom](#), [allow_mouse_wheel_zoom](#))
- Added [Chart.addYAxisBin](#), [Chart.addXAxisBin](#), [Chart.removeYAxisBin](#), [Chart.removeXAxisBin](#) methods to support manual definition (and order) of axis bins
- Added [EJSC.XMLStringDataHandler](#) class
- Added [drawPoints](#), [pointSize](#), [pointColor](#), [pointBorderSize](#), [pointBorderColor](#) properties to EJSC.LineSeries and EJSC.AreaSeries
- Added support for new zero plane coordinate property to AreaSeries and BarSeries
- Added [tree-style legend](#) for PieSeries
- Added [tree-style legend](#) option for BarSeries (default true when [useColorArray](#) is true and treeLegend is left undefined)
- Added [position](#) and [height/width](#) properties to PieSeries to support multiple pie series per chart
- Added [findCenter](#) method to PieSeries to find the center point of a given piece

- Added [getPoints](#) method to PieSeries (to allow findCenter calls to provide a valid piece object)
- Added [orientation](#) property to BarSeries and support for horizontal bar charts
- Added [total_value](#) property and [getTotalValue](#), [setTotalValue](#), [resetTotalValue](#) methods to PieSeries
- Added [\[total\]](#) and [\[percent\]](#) as hint text replacement options for PieSeries
- Added [x_cursor_position_formatter](#) and [y_cursor_position_formatter](#) properties to chart to allow for a different formatter for mouse position display

Modifications

- Consolidated and cleaned up xml parsing routines
- Consolidated and cleaned up csv parsing routines
- Cached many often used math methods for performance
- Modified extremes to account for manually added bins with no associated data in series
- Rewrote data handlers to better support text labels (bins)
- Modified pie series to correctly use lineOpacity
- Updated pie piece drawing to one path creation per piece
- Added check in AnalogGaugeSeries to avoid resetting innerHTML unless the label has actually changed.
- Added check of show_hints before triggering onShowHint event

Bug Fixes

- Added media attribute to link tag to fix printing issues in firefox/netscape
- Added correct headers when sending an xml request as POST
- Fixed case when last tick is missing while using [x_axis_tick_count](#)
- Fixed spelling - [getZoomBoxCoordinates](#)
- Updated lineOpacity to 100 (from 1) in PieSeries so lines draw correctly
- Added check for single 100% piece to remove line when drawn (fixed full circle drawing)

- Reversed __intercept/__slope properties in TrendSeries so they represent the correct values
- Updated number formatter to check for -0 as final output and remove - sign
- onDbClickPoint and onAfterSelectPoint both now function correctly when show_hints is false
- Fixed unterminated string error in TrendSeries
- Updated style to remove border when axes are not visible (ie, pie or gauge only charts)
- Fixed constant resize issue with pie charts (and anything with x axis hidden) in IE6/opera
- Fixed issue with series drawing multiple times when added and redraw is false

3.6 Changes in version 1.1

Additions

- Added new series type AnalogGaugeSeries
- Added onBeforeBeginZoom, onBeforeEndZoom and onAfterShowCrosshairs events to Chart
- Added support for local loading of chart code in IE 7 and IE6 with certain versions of the XMLHttpRequest ActiveX control.
- Added new axis styling properties to Chart: x_axis_size, x_axis_className, x_axis_tick_className, x_axis_stagger_ticks, x_axis_tick_count, y_axis_size, y_axis_className, y_axis_tick_className, y_axis_tick_count.
- Added Chart.setZoom and getZoom methods to in order to get the current zoom and set zoom to a particular range
- Added Chart.getMinMaxYInXRange method to programmatically find the min and max Y values in a given X range
- Added Chart.findClosestPointInSeries method to programmatically find the closest point to the coordinates (x,y) in a particular series
- Added Chart.getZoomBoxCoordinates method to get the current zoom box coordinates
- Added Chart.displayZoomBox method to programmatically display the zoom box
- Added BarPoint class to support additional BarSeries functionality
- Added the ability to draw bars with different colors based on ranges
- Added the ability to adjust the spacing between bars using the new intervalOffset property.
- Added the ability to switch between grouped and overlayed bars with BarSeries
- Added a color pool to BarSeries for individually colored bars (similar to PieSeries)
- Added onBarNeedsColor to BarSeries for more advanced bar coloring options
- Added setDefaultColors, addRange, deleteRange, clearRanges, setIntervalOffset and setGroupedBars methods to BarSeries
- Added support for 'exponential' and 'logarithmic' types in TrendSeries
- Added showGrid/hideGrid methods with an optional redraw parameter to prevent immediate redrawing
- Optimized trend series calculation routines
- Blank X or Y axis captions now trigger the axis to be resized giving the chart additional space
- Added the ability to specify only changed members of child objects via the options property
- Added Chart.convertPointToPixel method to calculate document pixel top/left of a point in chart units
- Added Chart.convertPixelToPoint method to calculate chart point from a document pixels
- Added base AjaxDataHandler class, XMLDataHandler and CSVFileData handler now descend from this class.
- Added requestType property and setRequestType method to AjaxDataHandler for changing between GET and POST.
- Added urlData property and setUrlData method to AjaxDataHandler to allow assignment of POST data and GET url parameters
- Added onNeedsData event and setXMLData method to AjaxDataHandler to support 3rd party Ajax libraries for data retrieval
- Added reload flag to setUrl method (default = false) in AjaxDataHandler to allow for immediate

data retrieval / series reload.

- Added Chart.allow_hide_error property (default = false) which allows error messages to be hidden and overwritten with non-error messages
- Added additional error checking and reporting into xmlrequestpool, errors occurring during series data retrieval via XML or CSVFile data handlers will be displayed on the chart.
- Added EJSC.utility.XMLRequestPool.fatalErrors property to define which HTTP codes cause a XMLHttpRequest to fail.
- Added redraw flag to Chart.addSeries in order to postpone full redraw until all series have been added.
- Added Chart.remove() method which completely deletes a chart from the page.

Modifications

- Moved a number of private properties into the EJSC namespace for easier patching.
- Modified load/unload events to use utility.attachEvent method so that the methods are detached automatically
- Changed non-IE browser load of stylesheet to insert link tag instead of force load stylesheet via ajax
- Reduced minimum height to 60 px
- Tick container now positioned absolute in order to support additional styling options.
- Added chart parameter to onShowCrosshairs event
- Removed case sensitivity requirement for locating support files.

Bug Fixes

- Consolidate references to html and head tags, clear references on unload to fix IE leak
- Fixed issue with attachEvent in Opera causing errors
- Added cleanup routine to series in order to remove references to legend items and fix IE leaks
- Fixed canvas cover positioning
- x_axis container left coordinate is now set to fix issues with table/float layouts causing odd shifts in IE
- doRecalcExtremes now called in resize method in order to re-adjust padding appropriately to the new chart size
- Fixed issues with drawing first series added when extreme values are static
- Fixed issues in recalculation of extreme values when no series data is available
- Fixed offset issues with hints and point selection
- Fixed issues with point selection routine when no point is selected
- Fixed onBeforeDblClick event to send correct reference to chart
- Fixed issue with array data handler loading when array is empty
- Fixed scatter series to not draw line through center of circle
- Fixed and optimized several issues with drawing and point selection within BarSeries with many bars
- Fixed issues with calculating spacing and widths with multiple bar series in a single chart
- Fixed issues with drawing and point selection in bar series when bar is only partially in view
- Fixed style issues with legend header and legend captions in IE

3.7 Changes in version 1.0.1

Additions

- Added series.opacity property
- Added series.setOpacity method

- Added series.lineOpacity property
- Added series.setLineOpacity property
- Added useUTC property to DateFormatter (default value == true)
- Added timezoneOffset property to DateFormatter (default value == undefined) Only applicable when useUTC is true
- Added series.legendIsVisible property (default value == true)
- Added series.showLegend and series.hideLegend methods
- Added chart.legendTitle property and chart.setLegendTitle method

Modifications

- Modified to remove all code inside target div
- Attach events to chart container to prevent selection
- Moved lineWidth property and setLineWidth method into base Series class
- Modified LineSeries to use lineOpacity properties
- Modified AreaSeries to use opacity and lineOpacity properties
- Modified ScatterSeries to use lineWidth, opacity and lineOpacity properties
- Modified PieSeries to use lineWidth, opacity and lineOpacity properties
- Modified BarSeries to use opacity and lineOpacity properties
- Modified FunctionSeries and TrendSeries to use lineOpacity property
- Text selection is now cancelled when drag/selection originates in the chart (except Opera)

Bug Fixes

- Fixed hint and point selection issues when the chart is inside a scrollable container
- Added check and alert if attachEvent fails
- Setting y_min/max, x_min/max during chart creation now correctly assign extremes
- Fixed scaling errors when only a single Y or X value has been specified
- Added call to onBeforeZoom when double clicking to allow canceling of zoom out
- Added call to onAfterZoom when double clicking to zoom out
- Fixed BarSeries line drawing on Internet Explorer
- Fixed automatic resizing of y axis caption in IE when using setYAxisCaption()
- Fixed style sheets to completely hide axis when turned off
- Fixed style sheets to hide key grabber element and remove border and background from cursor position elements.
- Fixed issues with long series titles wrapping legend items
- Added additional exception handling to unload methods and storage and clearing of auto-resize interval
- Fixed errors when attempting to load empty data sets (applicable to all data handlers)
- Fixed error when loading BarSeries with a single point

3.8 Changes in version 1.0

Additions

- Added an optional redraw flag into Chart.removeSeries in order to allow for multiple removes between chart redraws.
- Added support for user-defined data associated with a point
- Added support for reading user-defined data from full and short xml formats
- Added the setTitle method to the base Series class.
- Added getDataHandler method to base Series class.
- Added getUrl and setUrl methods to XMLDataHandler and CSVFileDataHandler classes.

- Added getArray and setArray methods to ArrayDataHandler class.
- Added getCSV and setCSV methods to CSVStringDataHandler class.
- Added coloredLegend property to Series to specify whether the series legend text should inherit the series color
- Added setColoredLegend method to Series in order to update the coloredLegend property after series creation

Modifications

- Updated chart resize methods to monitor the chart container and update whenever necessary, this adds greater compatibility with other 3rd party packages such as Dojo when the chart is placed inside a window class.
- Chart.removeSeries() now deletes the series object which was removed.
- Modified series legend items to have their text color match the series color.
- Modified series legend captions to not wrap and display full text with a hint.

Bug Fixes

- Fixed event attachments to global objects such as document.onmouseup to use attachEvent / addEventListener
- Chart.removeSeries() now correctly removes the legend objects without error.
- Fixed an issue where tall charts could lose interactivity.

4

Data Formats

The following is a brief summary of the data formats supported by Emprise JavaScript Charts. For additional information please see the individual class help files and example code available at <http://www.ejschart.com/help/>

XML

The [EJSC.XMLDataHandler](#) class will load an XML file containing chart data using AJAX. The following XML formats are supported:

Full:

```
<graph>
  <plot>
    <point x="" y="" />
  </plot>
</graph>
```

Short:

```
<G>
  <L>
    <P x="" y="" />
  </L>
</G>
```

Compact:

```
<G>
  <L values="X|Y,X|Y,X|Y" />
</G>
```

Array

The [EJSC.ArrayDataHandler](#) class will load chart data from a JavaScript array. The basic format of the array is as follows:

```
[
  [X Value, Y Value],
  [X Value, Y Value]
]
```

CSV (Comma Separated Values)

The [EJSC.CSVFileDataHandler](#) and [EJSC.CSVStringDataHandler](#) classes support a comma separated list of data points. [EJSC.CSVFileDataHandler](#) will load the data points list from a file on the server using AJAX. [EJSC.CSVStringDataHandler](#) takes a string in its constructor specifying the CSV text.

```
X|Y,X|Y,X|Y
```

JSON (JavaScript Object Notation)

The [EJSC.JSONFileDataHandler](#) and [EJSC.JSONStringDataHandler](#) classes support JSON formatted data points. [EJSC.JSONFileDataHandler](#) will load the data points list from a file on the server using AJAX. [EJSC.JSONStringDataHandler](#) takes a string in its constructor specifying the JSON text.

```
{
  {"x":"x value", "y":"y value"},
  {"x":"x value", "y":"y value"}
}
```

4.1 XML - Full

The full xml format is the most verbose and the most human readable of the supported formats. This format is ideal for experimenting with chart configuration and charts with smaller datasets.

General Usage:

```
<graph>
  <plot>
    <point x="1" y="1" />
    <point x="2" y="2" />
    <point x="3" y="3" />
    <point x="4" y="4" />
  </plot>
</graph>
```

Series Data Formats:

The above example is used for the majority of currently supported data series types. There are exceptions such as the [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#) and others. For a full description of the data format for a given series, see the Data Formats topic below each series section.

Text Labels:

At times, numeric labels and the auto scaling options in the chart are not necessary, not available or not desired for display data. A [EJSC.BarSeries](#) for instance, which is used to compare number of widgets sold by color. The chart supports providing text as the X value, rather than a number:

```
<graph>
  <plot>
    <point x="Blue" y="100" />
    <point x="Red" y="200" />
    <point x="Green" y="50" />
  </plot>
</graph>
```

User-Defined Data:

When displaying custom hints and implementing drill down style reports it is often necessary to have an additional piece of data associated with each data point such as a database id value. The full and short XML formats support the **userdata** property which is read in and assigned to the associated [EJSC.Point](#) descendant. The value specified is entirely up to the developer. It could be a set of integers representing a database primary key value, a url which points to drill-down data or even a javascript function. The **userdata** property of a point is available during point-related events in the chart such as [EJSC.Chart.onDoubleClickPoint](#), [EJSC.Chart.onAfterSelectPoint](#), etc.

```
<graph>
  <plot>
    <point x="1" y="100" userdata="WHERE PointId=10432" />
    <point x="2" y="200" userdata=".//drillDown2.xml" />
    <point x="3" y="50" userdata="alert('this is the userdata');" />
  </plot>
</graph>
```

4.2 XML - Short

The short XML format provides the same functionality as the [full format](#) but with less transfer overhead (there is no reduction in the processing overhead of extracting the point data, see the Array and CSV formats for more concise options).

The general format is as follows:

```
<G>
  <L>
    <P x="" y="" userdata="" />
  </L>
</G>
```

The **<G>** tag relates to the **<graph>** tag in the full format, the **<L>** tag relates to the **<plot>** tag and **<P>**

is equivalent to <point>.

Support for pie charts is provided in the same manner as with the full format, i.e.

```
<P x="" label="" />
```

4.3 XML - Compact

The compact xml format is geared towards larger data sets which need to reduce the overhead associated with transfer and extraction of chart data via a more verbose xml format.

The data is provided in csv-like format and stored in the "values" attribute of the <L> tag:

```
<G>
  <L values="1|1,2|2,3|3" />
</G>
```

For the majority of series, the above example would be used to provide X,Y coordinates.

5 API Reference

5.1 EJSC

Top level namespace for all classes and variables used by the Emprise JavaScript Charts package. Use of this namespace prevents variable name collisions with other available JavaScript packages.

5.1.1 Properties

5.1.1.1 DefaultImagePath

Definition

string **DefaultImagePath** = "images/"

Description

Relative path defining the path to all images used by EJSC classes.

5.1.1.2 DefaultColors

Definition

```
array defaultColors = [
  "rgb(120,90,59)",
  "rgb(53,115,53)",
  "rgb(178,87,56)",
  "rgb(203,143,71)",
  "rgb(55,106,155)",
  "rgb(205,197,51)",
  "rgb(209,130,139)",
  "rgb(159,153,57)",
  "rgb(206,173,136)",
```

```
"rgb(191,132,72)",
"rgb(151,135,169)",
"rgb(140,48,51)",
"rgb(59,144,187)",
"rgb(197,190,104)",
"rgb(109,136,79)",
"rgb(144,100,144)",
"rgb(181,94,94)",
"rgb(59,144,144)",
"rgb(204,136,92)",
"rgb(139,167,55)",
"rgb(205,171,66)",
"rgb(150,184,211)"
]
```

Description

This array is used in each chart to specify available series colors. Add to or modify this array in order to define a single set of default colors used by all charts on a page.

5.1.1.3 DefaultBarColors

Definition

```
array defaultBarColors = [
    "rgb(120,90,59)",
    "rgb(53,115,53)",
    "rgb(178,87,56)",
    "rgb(203,143,71)",
    "rgb(55,106,155)",
    "rgb(205,197,51)",
    "rgb(209,130,139)",
    "rgb(159,153,57)",
    "rgb(206,173,136)",
    "rgb(191,132,72)",
    "rgb(151,135,169)",
    "rgb(140,48,51)",
    "rgb(59,144,187)",
    "rgb(197,190,104)",
    "rgb(109,136,79)",
    "rgb(144,100,144)",
    "rgb(181,94,94)",
    "rgb(59,144,144)",
    "rgb(204,136,92)",
    "rgb(139,167,55)",
    "rgb(205,171,66)",
    "rgb(150,184,211)"
]
```

Description

Defines the pool of default colors available for bar series bars.

5.1.1.4 DefaultPieColors

Definition

```
array defaultPieColors = [
    "rgb(120,90,59)",
    "rgb(53,115,53)",
    "rgb(178,87,56)",
    "rgb(203,143,71)",
    "rgb(55,106,155)",
    "rgb(205,197,51)",
    "rgb(209,130,139)",
    "rgb(159,153,57)",
    "rgb(206,173,136)",
    "rgb(191,132,72)",
    "rgb(151,135,169)",
    "rgb(140,48,51)",
    "rgb(59,144,187)",
    "rgb(197,190,104)",
    "rgb(109,136,79)",
    "rgb(144,100,144)",
    "rgb(181,94,94)",
    "rgb(59,144,144)",
    "rgb(204,136,92)",
    "rgb(139,167,55)",
    "rgb(205,171,66)",
    "rgb(150,184,211)"
]
```

Description

Defines the pool of default colors available for pie pieces.

5.1.1.5 STRINGS

Definition

```
object STRINGS: {
    building_message:      "Building Chart...",
    max_zoom_message:      "Max Zoom Reached",
    drawing_message:       "Drawing...",
    chart_legend_title:    "Chart Legend",
    y_axis_caption:        "Y Axis",
    x_axis_caption:        "X Axis"
},
```

Description

Defines the default strings used by the chart.

5.2 EJSC.Chart

Chart class that holds all the generic information for each chart that is being created.

The constructor expects the id or reference for a DOM object (preferably a div) and an optional set of object properties. **NOTE:** The contents of the DOM object will be cleared before rendering the chart.

Constructor

```
EJSC.Chart( string id [, object options] )
EJSC.Chart( DOMObject object [, object options] )
```

Example

```
var myChart = new EJSC.Chart("chart", {title:"My Chart"});
```

or

```
var myChartDiv = document.getElementById("myChart");
var myChart = new EJSC.Chart(myChartDiv, {title:"My Chart"});
```

Defining Chart Properties and Events

Chart properties may be set individually after the chart has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var myChart = new EJSC.Chart("chartDIV");
myChart.allow_zoom = false;
myChart.show_legend = false;
myChart.onDblClickPoint = function(point) {
    alert("Point Clicked: " + point.x + "," + point.y);
}
```

Setting properties in batch

```
var myChart = new EJSC.Chart(
    "chartDIV",
    {
        allow_zoom: false,
        show_legend: false,
        onDblClickPoint: function(point) {
            alert("Point Clicked: " + point.x + "," + point.y);
        }
    }
);
```

5.2.1 Properties

5.2.1.1 allow_interactivity

Definition

boolean **allow_interactivity** = true

Description

Defines if the chart can be interacted with (ie zooming, moving, point selection, etc.).

Example

>> Turn off all interactivity for the chart

```
var chart = new EJSC.Chart(
    "chart",
    {allow_interactivity: false}
);
```

5.2.1.2 allow_mouse_wheel_zoom

Definition

boolean **allow_mouse_wheel_zoom** = true

Description

Defines if the chart can be zoomed via the scroll wheel on the mouse. This is automatically disabled if [allow_interactivity](#) or [allow_zoom](#) is set to false.

Example

>> Turn off wheel zooming for the chart.

```
var chart = new EJSC.Chart(
    "chart",
    {allow_mouse_wheel_zoom: false}
);
```

5.2.1.3 allow_move

Definition

boolean **allow_move** = true

Description

Defines if the chart can be moved once it has been zoomed in. This is automatically disabled if [allow_interactivity](#) is set to false.

Example

>> Turn off moving for the chart.

```
var chart = new EJSC.Chart(
    "chart",
```

```
    {allow_move: false}  
);
```

5.2.1.4 allow_zoom

Definition

boolean **allow_zoom** = true

Description

Defines if the chart can be zoomed. This is automatically disabled if [allow_interactivity](#) is set to false.

Example

>> Turn off zooming for the chart.

```
var chart = new EJSC.Chart(  
    "chart",  
    {allow_zoom: false}  
);
```

5.2.1.5 allow_hide_error

Definition

boolean **allow_hide_error** = false

Description

Defines whether the chart can overwrite an error message with a non-error message or hide the error message after a brief period of time.

Example

>> Allow all messages, including errors, to be hidden after a brief period of time

```
var chart = new EJSC.Chart(  
    "chart",  
    {  allow_hide_error: true }  
);
```

5.2.1.6 auto_find_point_by_x

Definition

boolean **auto_find_point_by_x** = false

Description

Defines if the select point routine should select points based only on the X position of the cursor.

Example

>> Allow point selection to occur on click anywhere within the Y axis, find the closest point based solely on X.

```
var chart = new EJSC.Chart(  
    "chart",  
    {auto_find_point_by_x: true}  
);
```

5.2.1.7 auto_resize

Definition

boolean **auto_resize** = true

Description

Defines if the chart will start a timer to check for size changes in order to automatically redraw. If you are controlling the display, size and position of the chart div container manually, it may be beneficial to turn this option off in order to eliminate the timer overhead.

Example

>> Turn off the chart's auto resize functionality

```
var chart = new EJSC.Chart(  
    "chart",  
    {auto_resize: false}  
);
```

5.2.1.8 auto_zoom

Definition

string **auto_zoom** = undefined

Valid property values:


'x'

'y'

Description

Defines if the chart should auto-select the zoom area based on the X or Y coordinates selected by the user. The other coordinates are automatically selected based on best fit for the data defined in the range selected.

Example



>> Allow user to select beginning and ending X values to zoom, then auto-scale the Y axis according to the data.

```
var chart = new EJSC.Chart(
    "chart",
    { auto_zoom: "y" }

);
```

5.2.1.9 **axis_bottom**

Definition

[EJSC.Axis axis_bottom](#) = EJSC.LinearAxis

Description

Defines the axis that will be at the bottom of the chart. All four axes are defined as EJSC.LinearAxis by default when the chart is created and do not need to be manually created unless a different type of axis is needed. These properties automatically allow the setting of axis properties during chart creation as shown in the example below.

Types:

[EJSC.LinearAxis](#)
[EJSC.LogarithmicAxis](#)

Example

>> Hide the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { visible: false }
    }
);
```

>> Display a base 10 logarithmic axis at the bottom of the chart.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: new EJSC.LogarithmicAxis({ base: 10 })
    }
);
```

5.2.1.10 axis_left

Definition

EJSC.Axis axis_left = EJSC.LinearAxis

Description

Defines the axis that will be at the left side of the chart. All four axes are defined as EJSC.LinearAxis by default when the chart is created and do not need to be manually created unless a different type of axis is needed. These properties automatically allow the setting of axis properties during chart creation as shown in the example below.

Types:

EJSC.LinearAxis
EJSC.LogarithmicAxis

Example

>> Hide the left axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_left: { visible: false }
    }
);
```

>> Display a base 10 logarithmic axis at the left side of the chart.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_left: new EJSC.LogarithmicAxis({ base: 10 })
    }
);
```

5.2.1.11 axis_right

Definition

EJSC.Axis axis_right = EJSC.LinearAxis

Description

Defines the axis that will at the right side of the chart. All four axes are defined as EJSC.LinearAxis by default when the chart is created and do not need to be manually created unless a different type of axis is needed. These properties automatically allow the setting of axis properties during chart creation as shown in the example below.

Types:

EJSC.LinearAxis
EJSC.LogarithmicAxis

Example

>> Show the right axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_right: { visible: true }
    }
);
```

>> Display a base 10 logarithmic axis at the right side of the chart.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_right: new EJSC.LogarithmicAxis({ base: 10 })
    }
);
```

5.2.1.12 axis_top

Definition

EJSC.Axis axis_top = EJSC.LinearAxis

Description

Defines the axis that will at the top of the chart. All four axes are defined as EJSC.LinearAxis by default when the chart is created and do not need to be manually created unless a different type of axis is needed. These properties automatically allow the setting of axis properties during chart creation as shown in the example below.

Types:

EJSC.LinearAxis
EJSC.LogarithmicAxis

Example

>> Show the top axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_top: { visible: true }
    }
);
```

>> Display a base 10 logarithmic axis at the top of the chart.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_top: new EJSC.LogarithmicAxis({ base: 10 })
    }
);
```

5.2.1.13 background

Definition

```
object background = {
    color: "#FFF",
    opacity: 0,
    includeTitle: false
};
```

Description

Defines the color and opacity of the chart area background. If the includeTitle property is set to true, the title bar area will be filled as well. If opacity is 0, no fill will occur.

NOTE: To set the color of then entire chart area (all axes, chart, titlebar, etc.), set the background-color style for the chart DOM object.

```
<div id="chart" style="width: 400px; height: 400px; background-color:#ffff00;"></div>
```

5.2.1.14 building_message

Definition

```
string building_message = EJSC.STRINGS["building_message"]
```

Description

Defines if text to display while the chart is being initially assembled. The default string used for all charts in the page is drawn from the EJSC.Strings property.

5.2.1.15 drawing_message

Definition

```
string drawing_message = EJSC.STRINGS["drawing_message"]
```

Description

Defines if text to display while the chart is being drawn. The default string used for all charts in the page is drawn from the EJSC.Strings property.

5.2.1.16 legend_title

Definition

```
string legend_title = EJSC.STRINGS["chart_legend_title"]
```

Description

Defines the caption displayed in the chart legend title bar. To modify this caption after chart creation, use [Chart.setLegendTitle\(\)](#)

5.2.1.17 max_zoom_message

Definition

```
string max_zoom_message = EJSC.STRINGS["max_zoom_message"]
```

Description

Defines if text to display when the maximum zoom has been reached. The default string used for all charts in the page is drawn from the EJSC.Strings property.

5.2.1.18 message_timeouts

Definition

```
object message_timeouts = {  
    progress: 500,  
    nodata: 500,  
    info: 500,  
    error: 2000  
};
```

Description

Defines the amount of time in milliseconds to display a particular message type.

5.2.1.19 proximity_snap

Definition

```
integer proximity_snap = 5
```

Description

Determines the maximum number of pixels away from a point the cursor can be for point selection and hints.

Example

>> Allow clicks to trigger point selection up to 9 pixels away from the actual point.

```
var chart = new EJSC.Chart(  
    "chart",  
    {proximity_snap: 8}  
) ;
```

5.2.1.20 show_hints

Definition

```
boolean show_hints = true
```

Description

Defines whether hints should be selected when a point is hovered over or selected. This is automatically disabled if [allow_interactivity](#) is set to false.

Example

>> Turn off hints and point selection.

```
var chart = new EJSC.Chart(  
    "chart",  
    {show_hints: false}  
) ;
```

5.2.1.21 show_legend

Definition

```
boolean show_legend = true
```

Description

Defines if the chart legend should be displayed.

Example

>> Turn off legend display

```
var chart = new EJSC.Chart(  
    "chart",  
    {show_legend: false}  
) ;
```

5.2.1.22 show_messages

Definition

```
boolean show_messages = true
```

Description

Defines if progress messages should be displayed above the chart or not.

Example

```
>> Turn off progress messages.
```

```
var chart = new EJSC.Chart(  
    "chart",  
    {show_messages: false}  
);
```

5.2.1.23 show_titlebar

Definition

```
boolean show_titlebar = true
```

Description

Defines if the titlebar (containing chart title and mouse position indicators) should be displayed above the chart.

Example

```
>> Display the chart without a titlebar
```

```
var chart = new EJSC.Chart(  
    "chart",  
    {show_titlebar: false}  
);
```

5.2.1.24 title

Definition

```
string title = "Emprise JavaScript Chart"
```

Description

Defines the title of the chart. It is displayed at the top left of the chart.

Example

```
>> Give the chart a name.
```

```
var chart = new EJSC.Chart(  
    "chart",  
    {title: "2007: Total Widget Sales by Month"}  
);
```

5.2.2 Methods

5.2.2.1 acquireSeries

Definition

void [acquireSeries](#)([EJSC.Series](#) series, boolean redraw)

Description

Moves a series from one chart to another. This method will remove the series from the chart which currently owns it and add it to the chart making the acquireSeries call.

Sends:

series - The series to be moved

redraw - Boolean flag telling the old and new charts if they should redraw immediately.

Specifying **false** here will require that both charts [redraw\(\)](#) methods are called in order to display the results of the acquisition.

5.2.2.2 addSeries

Definition

[EJSC.Series](#) [addSeries](#)([EJSC.Series](#) series, boolean redraw)

Description

Adds a new series to the chart and returns the newly added series (this is useful when creating series inline as shown in the example below). The series must descend from [EJSC.Series](#).

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the series to draw. The default, if redraw is omitted is **true**.

Note: If the series has not defined a title (i.e. Series.title = "") at the time addSeries is called, a default title of "Series <index>" will be assigned (where <index> is the current series index in internal series storage).

Types:

[EJSC.AnalogGaugeSeries](#)

[EJSC.AreaSeries](#)

[EJSC.BarSeries](#)

[EJSC.CandlestickSeries](#)

[EJSC.FloatingBarSeries](#)

[EJSC.FunctionSeries](#)

[EJSC.LineSeries](#)

[EJSC.OpenHighLowCloseSeries](#)

[EJSC.PieSeries](#)
[EJSC.ScatterSeries](#)
[EJSC.StackedBarSeries](#)
[EJSC.TrendSeries](#)

Example

>> Add a line series to the chart.

```
var myChart = new EJSC.Chart("chart");
var mySeries = myChart.addSeries(new EJSC.LineSeries(...));
```

5.2.2.3 clearSelectedPoint

Definition

```
void clearSelectedPoint( )
```

Description

Clears the current point selection and hides the hint if necessary.

5.2.2.4 exportSVG

Definition

```
string exportSVG( object Options )
```

Options Described (parameter {default value})

- **includeHeader {true}**

The includeHeader property defines whether the result should include the xml declaration (<?xml version="1.0"?>) and the SVG doctype tags.

- **height {chart height in pixels}**

The height property defines the height attribute of the viewBox attribute in the output svg tag (see [viewbox](#)). By default this is the pixel height of the chart but may be set to an arbitrary number or percentage such as "100%"

- **width {chart width in pixels}**

The width property defines the width attribute of the viewBox attribute in the output svg tag (see [viewbox](#)). By default this is the pixel width of the chart but may be set to an arbitrary number or percentage such as "100%"

- **namespace {none}**

The namespace property defines the prefix namespace to use for the svg tags. This is useful when used with includeHeader=false if including the resulting svg inside another document type. By default, this left undefined and the resulting svg will look something like <svg ... >...</svg>. If

defined, for example as namespace = mysvg, the resulting svg will look like <mysvg:svg ...>...</mysvg:svg>.

Description

This method will export the chart as it is currently rendered as SVG. This string can be returned to the server for processing into many different forms such as png or pdf. The server-side processing of this data is beyond the scope of this help document.

Example:

```
<script type="text/javascript">

    var chart = new EJSC.Chart("myChart", {});
    var series = new EJSC.LineSeries(
        new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,2],[5,1]]),
        {}
    );
    chart.addSeries(series);

    function buttonClick() {
        alert(chart.exportSVG({
            includeHeader: false,
            height: "50%",
            width: "50%",
            namespace: "mySVG"
        }));
    }
}

</script>
<button onclick="buttonClick()">Export SVG</button>
```

5.2.2.5 exportSVGLegend

Definition

string **exportSVGLegend(object Options)**

Options Described (parameter {default value})

- **orientation {"horizontal"}**

The orientation property defines how the legend dimensions will be calculated. Valid options are "horizontal" and "vertical". When using horizontal, the legend's width will match the chart's width and the legend items will be displayed left to right, top to bottom. The height will expand as needed to accomidate all legend items. Specifying vertical for orientation will cause the legend to match the charts height and display the legend items top to bottom, left to right, expanding the width of the legend as necessary.

- **includeHeader {true}**

The includeHeader property defines whether the result should include the xml declaration (<?xml version="1.0"?>) and the SVG doctype tags.

- **height {chart height in pixels}**

The height property defines the height attribute of the viewBox attribute in the output svg tag (see [viewbox](#)). By default this is the pixel height of the chart but may be set to an arbitrary number or percentage such as "100%"

- **width {chart width in pixels}**

The width property defines the width attribute of the viewBox attribute in the output svg tag (see [viewbox](#)). By default this is the pixel width of the chart but may be set to an arbitrary number or percentage such as "100%"

- **namespace {none}**

The namespace property defines the prefix namespace to use for the svg tags. This is useful when used with includeHeader=false if including the resulting svg inside another document type. By default, this left undefined and the resulting svg will look something like <svg ... >...</svg>. If defined, for example as namespace = mysvg, the resulting svg will look like <mysvg:svg ...>...</mysvg:svg>.

- **border {}**

- **show {true}**

The show property determines whether or not to draw a border around the entire legend area.

- **color {"#000"}**

The color property specifies the color of the border, only applicable if show is true.

- **size {1}**

The size specifies the size (thickness) of the border drawn, only applicable if show is true.

- **show_title {true}**

The show_title property determines whether to draw the title area of the legend. If false or if the chart's title property is blank, the legend title area will not be drawn.

Description

This method will export the chart legend as it relates to the currently rendered chart. The legend is exported in a more print friendly manner and may be customized using the options described above. The exported SVG string can be returned to the server for processing into many different forms such as png or pdf. The server-side processing of this data is beyond the scope of this help document.

Example:

```

<script type="text/javascript">

    var chart = new EJSC.Chart("myChart", {});
    var series = new EJSC.LineSeries(
        new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,2],[5,1]]),
        {}
    );
    chart.addSeries(series);

    function buttonClick() {
        alert(chart.exportSVG({
            height: "50%",
            width: "50%",
            border: {
                show: true,
                color: "#F00",
                size: 4
            },
            show_title: false
        }));
    }

</script>
<button onclick="buttonClick();">Export SVG</button>

```

5.2.2.6 findClosestPoint**Definition**

[EJSC.Point](#) **findClosestPoint(** interger x, integer y, boolean select, boolean sticky **)**

Description

Given X and Y as screen pixel coordinates (not chart coordinates), this method will find and return the closest point in any of its series. Optionally, the point may be selected by sending true for the select parameter and displayed as either as a popup hint (i.e. when a user hovers over a point) by sending false for the sticky parameter or a sticky hint (i.e. a user clicks on a point) by sending true.

5.2.2.7 getMinMaxYInXRange

DEPRECATED - Will be replaced in a future version

Definition

object [getMinMaxYInXRange\(](#) float x_min, float x_max [\)](#)

RETURNS:

{ y_min: float, y_max: float }

Description

Returns the min and max Y values for the provided X range.

5.2.2.8 **getZoomBoxPixelCoordinates**

Definition

object **getZoomBoxPixelCoordinates**(string ScreenOrChart)

RETURNS:

{ left: integer, top: integer, right: integer, bottom: integer, width: integer, height: integer }

ScreenOrChart Values:

"screen"
"chart"

Description

Returns the current pixel coordinates of the zoom box (whether visible or not). The ScreenOrChart parameter may be used to specify if the coordinates returned are based off the top left of the chart ("chart"), or the top left of the page ("screen").

5.2.2.9 **hideTitlebar**

Definition

void **hideTitlebar**()

Description

Hides the titlebar, resizes and chart area and redraws all visible series.

No effect if the titlebar is already hidden.

5.2.2.10 **hideZoomBox**

Definition

void **hideZoomBox**()

Description

Hides the zoom box. No effect if the zoom box is already hidden.

5.2.2.11 **redraw**

Definition

void **redraw**(boolean reselectPoint)

Description

Resizes chart elements (if necessary) and redraws the entire chart and all series contained within. The **reselectPoint** parameter determines whether to retain point selection (if any) between redraws.

5.2.2.12 remove

Definition

```
void remove()
```

Description

Removes the chart from the page, cleans up all attached events, references, timeouts and intervals and clears the contents of the parent element (specified during creation).

5.2.2.13 removeSeries

Definition

```
void removeSeries( EJSC.Series series, boolean redraw )
```

Description

Removes the specified series from the chart and triggers an immediate rescaling and redraw. Send in redraw = false if performing multiple removes and want to delay redrawing until complete.

5.2.2.14 selectPoint

Definition

```
void selectPoint( EJSC.Point point, boolean sticky )
```

Description

Selects the point provided. The sticky property specifies whether the hint window will close when the mouse moves over another point in the chart.

The point object can be retrieved using the [Chart.findClosestPoint\(\)](#) or [Series.findClosestPoint\(\)](#) methods.

5.2.2.15 setAutoResize

Definition

```
void setAutoResize( boolean auto_resize )
```

Description

Enables or disables the [auto_resize](#) functionality once the chart has been created.

5.2.2.16 setLegendTitle

Definition

```
void setLegendTitle( string title )
```

Description

Updates the caption in the legend window title bar.

5.2.2.17 setTitle**Definition**

void **setTitle**(string title)

Description

Updates the chart title shown in the title area of the chart. This method must be used to change the title once the chart has been rendered.

To set a default chart title on creation, see [EJSC.Chart.title](#).

5.2.2.18 showTitlebar**Definition**

void **showTitlebar**()

Description

Shows the titlebar, resizes and chart area and redraws all visible series.

No effect if the titlebar is already visible.

5.2.2.19 showZoomBox**Definition**

void **showZoomBox**(coordinate x_min, coordinate x_max, string x_axis, coordinate y_min, coordinate y_max, string y_axis)

Description

Shows the zoom box at the specified chart coordinates using the axes specified.

Example

>> Show the zoom box at x=10,y=10, x=100, y=100

```
var chart = new EJSC.Chart("chart",
{
    axis_bottom: {
        min_extreme: 0,
        max_extreme: 200
    },
    axis_left: {
```

```
        min_extreme: 0,
        max_extreme: 2000
    }
}
);
chart.showZoomBox(10, 200, "bottom", 100, 100, "left");
```

5.2.3 Events

5.2.3.1 onAfterBuild

Definition

void [onAfterBuild](#)([EJSC.Chart](#) chart)

Description

Called immediately after the chart has finished writing itself to the page. Sends the chart object which triggered the event.

5.2.3.2 onAfterDraw

Definition

void [onAfterDraw](#)([EJSC.Chart](#) chart)

Description

Called after a drawing option has completed. Sends the chart object which triggered the event.

5.2.3.3 onAfterMove

Definition

void [onAfterMove](#)([EJSC.Chart](#) chart)

Description

Called after the chart has been dragged/moved while zoomed in. Sends the chart object which triggered the event.

5.2.3.4 onAfterSelectPoint

Definition

void [onAfterSelectPoint](#)([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, DOMObject hint_element, string HoverOrSelect)

Description

Called after a point has been selected due to mouse over (hover) or physical selection (click, keyboard).

Sends:

point - The point object selected.
series - The series object in which the point exists.
chart - The chart object which triggered the event (owns the series/point).
hint_element - The DOM object which contains the hint text/markup
HoverOrSelect - String "hover" or "select" to indicate what triggered the event.

5.2.3.5 onAfterUnselectPoint

Definition

void **onAfterUnselectPoint()**

Description

Called after a point has lost selection.

5.2.3.6 onAfterZoom

Definition

void **onAfterZoom(EJSC.Chart chart)**

Description

Called after the chart has been zoomed. Sends the chart object which triggered the event.

5.2.3.7 onBeforeBuild

Definition

void **onBeforeBuild(EJSC.Chart chart)**

Description

Called immediately before the chart begins writing itself to the page. Sends the chart object which triggered the event.

5.2.3.8 onBeforeDblClick

Definition

boolean **onBeforeDblClick(EJSC.Chart chart)**

Description

Called before the chart does any processing related to a double click. Return **false** may be used to cancel all additional processing.

5.2.3.9 onBeforeDraw

Definition

boolean **onBeforeDraw()**

Description

Called before the chart is drawn. If return is false, draw is canceled.

5.2.3.10 onBeforeSelectPoint

Definition

boolean **onBeforeSelectPoint(EJSC.Point point, EJSC.Series series, EJSC.Chart chart, DOMObject hint_element, string HoverOrSelect)**

Description

Called after a point has been selected due to mouse over (hover) or physical selection (click, keyboard).

Sends:

point - The point object about to be selected.
series - The series object in which the point exists.
chart - The chart object which triggered the event (owns the series/point).
hint_element - The DOM object which contains the hint text/markup
HoverOrSelect - String "hover" or "select" to indicate what triggered the event.

5.2.3.11 onBeforeUnselectPoint

Definition

void **onBeforeUnselectPoint(EJSC.Point point, EJSC.Series series, EJSC.Chart chart)**

Description

Called before a point has been unselected. If return is false, current point selection is not lost.

Sends:

point - The point object about to lose selected.

5.2.3.12 onDbClickPoint

Definition

boolean **onDbClickPoint(EJSC.Point point, EJSC.Series series, EJSC.Chart chart)**

Description

Called when a point is double clicked or the ENTER key is pressed and a point is selected. If return is false, cancels zoom-out (if axis are shown).

5.2.3.13 onShowHint

Definition

```
string onShowHint( EJSC.Point point, EJSC.Series series, EJSC.Chart chart, DOMObject  
hint_element, string HoverOrSelect )
```

Description

Called after a point has been selected due to mouse over (hover) or physical selection (click, keyboard).

A custom string may be returned in order to specify the contents of the hint window. See [Text Replacement Options](#) for more details.

Sends:

- point - The point object selected.
- series - The series object in which the point exists.
- chart - The chart object which triggered the event (owns the series/point).
- hint_element - The DOM object which contains the hint text/markup
- HoverOrSelect - String "hover" or "select" to indicate what triggered the event.

5.2.3.14 onShowMessage

Definition

```
void onShowMessage( string message, string type )
```

Description

Called when the status message is displayed (in the top right corner of the chart).

Sends:

- message - The text to be displayed
- type - A string identifying the type of message window. This may be "error" or "info"

5.2.3.15 onUserBeginZoom

Definition

```
boolean onUserBeginZoom( EJSC.Chart chart )
```

Description

Called when the user begins to draw the zoom box by clicking in the chart area and dragging down and to the right.

Returning false will cancel the zoom operation and hide the zoom box.

5.2.3.16 onUserEndZoom

Definition

```
boolean onUserEndZoom( EJSC.Chart chart )
```

Description

Called when the user finishes drawing the zoom box but before the zoom takes place.

Returning false will cancel the zoom operation and hide the zoom box.

5.2.4 Deprecated

5.2.4.1 Properties

5.2.4.1.1 force_static_points

DEPRECATED See [EJSC.Axis.force_static_points](#)

5.2.4.1.2 force_static_points_x

DEPRECATED See [EJSC.Axis.force_static_points](#)

5.2.4.1.3 force_static_points_y

DEPRECATED See [EJSC.Axis.force_static_points](#)

5.2.4.1.4 legendTitle

DEPRECATED See [EJSC.Chart.legend_title](#)

5.2.4.1.5 show_crosshairs

DEPRECATED See [EJSC.Axis.crosshair](#)

5.2.4.1.6 show_grid

DEPRECATED See [EJSC.Axis.grid](#)

5.2.4.1.7 show_mouse_position

DEPRECATED See [EJSC.Axis.cursor_position](#)

5.2.4.1.8 show_x_axis

DEPRECATED See [EJSC.Axis.visible](#)

5.2.4.1.9 show_y_axis

DEPRECATED See [EJSC.Axis.visible](#)

5.2.4.1.10 x_axis_caption

DEPRECATED See [EJSC.Axis.caption](#)

5.2.4.1.11 x_axis_className

DEPRECATED See [EJSC.Axis.caption_class](#)

5.2.4.1.12 x_axis_extremes_ticks

DEPRECATED See [EJSC.Axis.extremes_ticks](#)

5.2.4.1.13 x_axis_formatter

DEPRECATED See [EJSC.Axis.formatter](#)

5.2.4.1.14 x_axis_max_tick_interval

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.15 x_axis_min_tick_interval

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.16 x_axis_minor_ticks

DEPRECATED See [EJSC.Axis.minor_ticks](#)

5.2.4.1.17 x_axis_size

DEPRECATED See [EJSC.Axis.size](#)

5.2.4.1.18 x_axis_stagger_ticks

DEPRECATED See [EJSC.Axis.stagger_ticks](#)

5.2.4.1.19 x_axis_tick_className

DEPRECATED See [EJSC.Axis.label_class](#)

5.2.4.1.20 x_axis_tick_count

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.21 x_cursor_position_caption

DEPRECATED See [EJSC.Axis.cursor_position](#)

5.2.4.1.22 x_cursor_position_formatter

DEPRECATED See [EJSC.Axis.cursor_position](#)

5.2.4.1.23 x_max

DEPRECATED See [EJSC.Axis.max_extreme](#)

5.2.4.1.24 x_min

DEPRECATED See [EJSC.Axis.min_extreme](#)

5.2.4.1.25 x_value_hint_caption

DEPRECATED See [EJSC.Axis.hint_caption](#)

5.2.4.1.26 x_zero_plane

DEPRECATED See [EJSC.Axis.zero_plane](#)

5.2.4.1.27 y_axis_caption

DEPRECATED See [EJSC.Axis.caption](#)

5.2.4.1.28 y_axis_className

DEPRECATED See [EJSC.Axis.caption_class](#)

5.2.4.1.29 y_axis_extremes_ticks

DEPRECATED See [EJSC.Axis.extremes_ticks](#)

5.2.4.1.30 y_axis_formatter

DEPRECATED See [EJSC.Axis.formatter](#)

5.2.4.1.31 y_axis_max_tick_interval

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.32 y_axis_min_tick_interval

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.33 y_axis_minor_ticks

DEPRECATED See [EJSC.Axis.minor_ticks](#)

5.2.4.1.34 y_axis_size

DEPRECATED See [EJSC.Axis.size](#)

5.2.4.1.35 y_axis_tick_className

DEPRECATED See [EJSC.Axis.label_class](#)

5.2.4.1.36 y_axis_tick_count

DEPRECATED See [EJSC.Axis.major_ticks](#)

5.2.4.1.37 y_cursor_position_caption

DEPRECATED See [EJSC.Axis.cursor_position](#)

5.2.4.1.38 y_cursor_position_formatter

DEPRECATED See [EJSC.Axis.cursor_position](#)

5.2.4.1.39 y_max

DEPRECATED See [EJSC.Axis.max_extreme](#)

5.2.4.1.40 y_min

DEPRECATED See [EJSC.Axis.min_extreme](#)

5.2.4.1.41 y_value_hint_caption

DEPRECATED See [EJSC.Axis.hint_caption](#)

5.2.4.1.42 y_zero_plane

DEPRECATED See [EJSC.Axis.zero_plane](#)

5.2.4.2 Methods

5.2.4.2.1 addXAxisBin

DEPRECATED See [EJSC.Axis.addBin](#)

5.2.4.2.2 addYAxisBin

DEPRECATED See [EJSC.Axis.addBin](#)

5.2.4.2.3 convertPixelToPoint

DEPRECATED See [EJSC.Axis.pixelToPoint](#)

5.2.4.2.4 convertPointToPoint

DEPRECATED See [EJSC.Axis.pointToPoint](#)

5.2.4.2.5 findClosestPointInSeries

DEPRECATED See [EJSC.Series.findClosestPoint](#)

5.2.4.2.6 hideGrid

DEPRECATED See [EJSC.Axis.hideGrid](#)

5.2.4.2.7 hideXAxis

DEPRECATED See [EJSC.Axis.hide](#)

5.2.4.2.8 hideYAxis

DEPRECATED See [EJSC.Axis.hide](#)

5.2.4.2.9 getXExtremes

DEPRECATED See [EJSC.Axis.getExtremes](#)

5.2.4.2.10 getYExtremes

DEPRECATED See [EJSC.Axis.getExtremes](#)

5.2.4.2.11 getZoom

DEPRECATED See [EJSC.Axis.getZoom](#)

5.2.4.2.12 removeXAxisBin

DEPRECATED See [EJSC.Axis.removeBin](#)

5.2.4.2.13 removeYAxisBin

DEPRECATED See [EJSC.Axis.removeBin](#)

5.2.4.2.14 selectClosestPoint

DEPRECATED See [EJSC.Chart.findClosestPoint](#)

5.2.4.2.15 setCrosshairs

DEPRECATED See [EJSC.Axis.setCrosshair](#)

5.2.4.2.16 setXAxisCaption

DEPRECATED See [EJSC.Axis.setCaption](#)

5.2.4.2.17 setXExtremes

DEPRECATED See [EJSC.Axis.setExtremes](#)

5.2.4.2.18 setYAxisCaption

DEPRECATED See [EJSC.Axis.setCaption](#)

5.2.4.2.19 setYExtremes

DEPRECATED See [EJSC.Axis.setExtremes](#)

5.2.4.2.20 setZoom

DEPRECATED See [EJSC.Axis.setZoom](#)

5.2.4.2.21 showGrid

DEPRECATED See [EJSC.Axis.showGrid](#)

5.2.4.2.22 showXAxis

DEPRECATED See [EJSC.Axis.show](#)

5.2.4.2.23 showYAxis

DEPRECATED See [EJSC.Axis.show](#)

5.2.4.3 Events

5.2.4.3.1 onAfterShowCrosshairs

DEPRECATED

There is no direct replacement for this event. See [EJSC.Axis.onShowCrosshair](#)

5.2.4.3.2 onBeforeBeginZoom

DEPRECATED See [EJSC.Chart.onUserBeginZoom](#)

5.2.4.3.3 onBeforeEndZoom

DEPRECATED See [EJSC.Chart.onUserEndZoom](#)

5.2.4.3.4 onShowCrosshairs

DEPRECATED

There is no direct replacement for this event. See [EJSC.Axis.onShowCrosshair](#)

5.2.4.3.5 onXAxisNeedsTicks

DEPRECATED See [EJSC.Axis.onNeedsTicks](#)

5.2.4.3.6 onYAxisNeedsTicks

DEPRECATED See [EJSC.Axis.onNeedsTicks](#)

5.3 Axes Types

5.3.1 LinearAxis

LinearAxis is the default axis type for all four chart axes.

The constructor takes an optional set of object properties used to perform initial configuration.

Constructor

```
EJSC.LinearAxis( [ object options] )
```

Example

```
var chart = new EJSC.Chart("myChart", {
    axis_bottom: new EJSC.LinearAxis({
        caption: "Test"
    })
});
```

Defining Properties and Events

LinearAxis properties may be set individually after the chart has been initialized and/or the axis has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var chart = new EJSC.Chart("myChart", {
    axis_bottom: new EJSC.LinearAxis()
});
chart.axis_bottom.caption = "Test";
chart.axis_bottom.color = "#F00";
```

Setting properties in batch

```
var chart = new EJSC.Chart("myChart", {
    axis_bottom: new EJSC.LinearAxis({
        caption: "Test",
        color: "#F00"
    })
});
```

5.3.1.1 Properties

5.3.1.1.1 background (inherited)

Definition

```
object background = {
    color: "#fff",
    opacity: 0,
    includeTitle: false
};
```

Description

Defines the color and opacity of the axis area background. Setting the includeTitle property to true will fill the axis caption area as well as the ticks. If opacity is set to 0, no fill will occur.

5.3.1.1.2 border (inherited)

Definition

```
object border = {
    thickness: 1,
    color: undefined,
    opacity: 100,
    show: true
}
```

Description

Defines the appearance of the axis side bordering the chart area. By default the border color inherits the axis color property ([EJSC.Axis.color](#))

Example

>> Provide a 2 pixel tall green border on the bottom axis.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom:
            border: { thickness: 2, color: "#0F0" }
    }
);
```

5.3.1.1.3 caption (inherited)

Definition

```
string caption = "Axis"
```

Description

Defines the text to be displayed below or beside the axis.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Customize the bottom axis caption.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption: "Year" }
    }
);
```

5.3.1.1.4 caption_class (inherited)

Definition

```
string caption_class = ""
```

Description

Defines the CSS className to assign to the axis caption.

For styling the tick labels, see [EJSC.Axis.label_class](#)

Example

>> Style the axis caption bold.

```
<style> .AxisCaption { font-style: bold; } </style>

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption_class: "AxisCaption" }
    }
);
```

5.3.1.1.5 color (inherited)

Definition

```
string color = "#FFF"
```

Description

Defines the default color of the axis border and tick marks. If the sub properties such as minor_ticks.color, major_ticks.color, border.color are left undefined, they inherit the value set here.

Example

>> Color the axis border and tick marks red

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { color: "#F00" }
    }
);
```

5.3.1.1.6 crosshair (inherited)

Definition

```
object crosshair = {
    show: false,
    color: "#F00"
}
```

Description

Defines if crosshair should be shown on the chart at the current mouse coordinates as they relate to the given axis. May be enabled and disabled for each axis independently. This is automatically disabled for all axes if [EJSC.Chart.allow_interactivity](#) is set to false.

Example

>> Show crosshair based on the bottom axis mouse position.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            crosshair: { show: true }
        }
    }
);
```

5.3.1.1.7 cursor_position (inherited)

Definition

```
object cursor_position = {
    show: false,
    color: "#F00",
    textColor: "#FFF",
    formatter: undefined,
    caption: undefined,
    className: undefined
}
```

Description

Defines the display properties of the cursor position feature for an axis. These properties may be used to turn the cursor position indicator on and off as well as configure the styling and color.

show: determines whether or not to display the cursor position while the mouse is within the chart area

color: sets the background and line color

textColor: sets the text color

formatter: defines a formatter to use when displaying coordinates, if left undefined it will use the axis formatter

caption: defines text to use as a prefix to the current coordinate

className: a CSS class name to be used for additional styling

Example

>> Turn on cursor position for the bottom axis and configure to display a related label

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            cursor_position: {
                show: true,
                caption: "Sales"
            }
        }
    }
);
```

```
        }
    }
);
}
```

5.3.1.1.8 extremes_ticks (inherited)

Definition

```
boolean extremes_ticks = false
```

Description

Defines if the min and max values should be forced to land on the next tick mark.

Example

>> Force tick marks at the min and max coordinates of the bottom axis (left and right sides of the chart)

```
var chart = new EJSC.Chart(
    "chart",
{
    axis_bottom: { extremes_ticks: true }
}
);
```

5.3.1.1.9 force_static_points (inherited)

Definition

```
boolean force_static_points = false
```

Description

Defines if the chart should force ticks to match up to every point by converting the data to strings.

Example

>> Display every bottom axis data point, essentially disable auto axis scaling.

```
var chart = new EJSC.Chart(
    "chart",
{
    axis_bottom: { force_static_points: true }
}
);
```

5.3.1.1.10 formatter (inherited)

Definition

EJSC.Formatter **formatter** = EJSC.Formatter

Description

Defines the formatter that will be used to format the tick marks on the axis before displaying them.

Types:

[EJSC.DateFormatter](#)
[EJSC.NumberFormatter](#)
[EJSC.StringFormatter](#)

Example

>> Display bottom axis tick labels as \$0.00

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            formatter: new EJSC.NumberFormatter( { currency_symbol: "$",
forced_decimals: 2, variable_decimals: 2 } )
        }
    }
);
```

5.3.1.1.11 grid (inherited)

Definition

```
object grid = {
    thickness: 1,
    color: "rgb(230,230,230)",
    opacity: 100,
    show: true
}
```

Description

Defines the appearance and visibility of the grid drawn in the background.

Example

>> Do not draw the background grid for the top and right axes.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_top: {
            grid: { show: false }
        },
        axis_right: {
            grid: { show: false }
        }
    }
);
```

5.3.1.1.12 hint_caption (inherited)

Definition

```
string hint_caption = "Value:"
```

Description

Defines the text to display in front of the axis-related value in the hint (leave blank to hide the value when displaying the hint).

Example

>> Customize the value label in the hint window

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            hint_caption: "Month:"
        }
    }
);
```

5.3.1.1.13 label_class (inherited)

Definition

```
string label_class = ""
```

Description

Defines the CSS className to assign to the axis tick labels. Used in conjunction with [EJSC.Axis.stagger_ticks](#) and [EJSC.Axis.size](#), this property allows for greater control over the size and staggering of tick labels on the top and bottom axes.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Style the axis tick labels grey, make them 24 pixels high to enable text wrapping and enable two levels of tick staggering.

```
<style> .AxisTickLabels { color: #999; height: 24px; } </style>

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            label_class: "AxisTickLabels",
            size: 48
        }
    }
);
```

5.3.1.1.14 major_ticks (inherited)

Definition

```
object major_ticks = {  
    thickness: 1,  
    size: 4,  
    color: undefined,  
    opacity: 100,  
    show: true,  
    count: undefined,  
    offset: 0,  
    min_interval: undefined,  
    max_interval: undefined  
}
```

Description

This set of properties defines the characteristics of the major ticks for a given axis.

thickness: the height or width (depending on axis orientation) of the tick mark

size: the amount the tick mark extends from the axis border, may be specified as a number or a string containing % for a percentage

color: the color of the tick marks, if left undefined this property inherits its value from [EJSC.Axis.color](#)

opacity: the opacity of the tick marks

show: specifies whether to draw the tick marks

count: the number of tick marks to draw, if left undefined the axis will determine the proper amount of ticks to draw automatically based on the range of data available to the axis

Note: This property is not compatible with text labels (i.e. x axis values are "Gizmos", "Widgets", instead of numbers)

offset: distance in pixels or percent from the axis border to begin drawing the tick marks,

min_interval: Defines the minimum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

max_interval: Defines the maximum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

5.3.1.1.15 max_extreme (inherited)

Definition

```
float max_extreme = undefined
```

Description

Defines the maximum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
{
    axis_bottom: {
        max_extreme: 500.00
    }
);

```

5.3.1.1.16 min_extreme (inherited)

Definition

float **min** = undefined

Description

Defines the minimum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
{
    axis_bottom: {
        min_extreme: -500.00
    }
);

```

5.3.1.1.17 minor_ticks (inherited)

Definition

```
object minor_ticks = {
    show: false,
    color: "rgb(0,0,0)",
    opacity: 20
    thickness: 1,
    count: 7,
    size: 4,
    offset: 0
}
```

Description

Defines the properties of the minor tick marks to be drawn on the axis. The color, opacity and thickness (width of ticks in pixels) properties define the style of the tick marks. The count property defines the number of tick marks to be drawn between each major tick mark. The size property defines the height of the ticks (in pixels or percent). The offset property defines the distance away from the axis the minor tick marks begin drawing.

Example

>> Display red minor tick marks on the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            minor_ticks: { show: true, color: "#FF0000" }
        }
    }
);
```

5.3.1.1.18 size (inherited)

Definition

integer **size** = 20

Description

Defines the height of horizontal axes or width of vertical axes (in pixels) of the tick area. To fully enable staggered ticks on horizontal axes, set this property to a multiple of 20 (or axis tick height), i.e. two levels = 40, three levels = 60.

For additional control over the format of the labels, see the [EJSC.Axis.label_class](#) property.

Example

>> Make axis tick area twice as tall, enabling staggered ticks (default tick label height is 20 pixels)

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { size: 40 }
    }
);
```

5.3.1.1.19 stagger_ticks (inherited)

Definition

boolean **stagger_ticks** = true

Description

Determines whether the axis tick labels are staggered.

NOTE: This property is only applicable to horizontal axes (i.e. [EJSC.Chart.axis_top](#) and [EJSC.Chart.axis_bottom](#))

Example

>> Disable tick staggering for the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { stagger_ticks: false }
    }
);
```

5.3.1.1.20 visible (inherited)

Definition

boolean **visible** = true

Description

Defines if the axis (containing axis caption and tick labels) should be displayed.

Example

>> Remove the bottom axis from the chart to allow additional room for data

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { visible: false }
    }
);
```

5.3.1.1.21 zero_plane (inherited)

Definition

```
object zero_plane = {
    color: "rgb(0,0,0)",
    show: false,
    opacity: 100,
    thickness: 1,
    coordinate: 0
}
```

Description

Defines the properties of the zero plane line to be drawn at 0 (or whatever the coordinate property is set to). It is used to specify if the line should be shown as well as its color, thickness and opacity. The coordinate property allows the base of [EJSC.BarSeries](#), [EJSC.StackedBarSeries](#) and [EJSC.AreaSeries](#)

changed.

Example

>> Display a 2 pixel thick dark green line on the zero plane of the left axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_left: {
            zero_plane: { show: true, color: "rgb(7,89,5)", thickness:
2 }
        }
    }
);
```

5.3.1.2 Methods

5.3.1.2.1 addBin (inherited)

Definition

void **addBin**(String label, boolean redraw)

Description

Adds a new static label to the axis and sets the appropriate flags if necessary to force the chart to draw using static labels (as opposed to a dynamic range based on series data).

This method is useful if there is a need to include bins which may not be part of any series added (i.e. chart labels should be "Apples", "Oranges", "Pears" but the series data only contains data pertaining to Apples and Pears).

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the chart to draw. The default, if redraw is omitted is **true**.

Note:

Manually added bins may only be removed if there are no series currently utilizing them.

Example

>> Add bins in a specific order to ensure they appear the same each time the chart is loaded, regardless of the order in which they appear in the data.

```
var myChart = new EJSC.Chart("chart");
myChart.axis_bottom.addBin("Salesman 1");
myChart.axis_bottom.addBin("Salesman 2");
myChart.axis_bottom.addBin("Salesman 3");
```

```
var mySeries = myChart.addSeries(
    new EJSC.BarSeries(...)
```

);

5.3.1.2.2 getExtremes (inherited)

Definition

object **getExtremes()**

RETURNS:

{ min: float, max: float }

Description

Returns the current axis extreme values.

To set the extreme values, see [EJSC.Axis.setExtremes](#)

5.3.1.2.3 getZoom (inherited)

Definition

object **getZoom()**

RETURNS:

{ min: float, max: float }

Description

Returns the current zoom coordinates for a given axis in chart units.

To set the zoom coordinates, see [EJSC.Axis.setZoom](#)

5.3.1.2.4 getZoomBoxCoordinates (inherited)

Definition

void **getZoomBoxCoordinates()**

RETURNS:

{ min: float, max: float }

Description

Returns the min and max values for a given axis of the current zoom box. These values are in chart coordinates, not pixels.

5.3.1.2.5 hide (inherited)

Definition

void **hide()**

Description

Hides the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already hidden.

5.3.1.2.6 `hideGrid` (inherited)

Definition

```
void hideGrid( boolean redraw )
```

Description

Hides the background grid for a given axis and if redraw is omitted or true, redraws the chart

No effect if the grid is already hidden.

5.3.1.2.7 `pixelToPoint` (inherited)

Definition

```
float pixelToPoint( integer Pixel )
```

Description

Converts the pixel coordinate into chart units based on an axis. The result will be undefined if the pixel location is outside of the chart area.

5.3.1.2.8 `pointToPixel` (inherited)

Definition

```
integer pointToPixel( number coordinate )
```

Description

Converts the chart coordinates based on axis data into the appropriate pixel position for that point (x or y depending on the orientation of the axis)

The result will be undefined if the coordinate provided is outside the currently displayed range.

5.3.1.2.9 `removeBin` (inherited)

Definition

```
void removeBin( String label, boolean redraw )
```

Description

Removes a bin (static text label) from the axis.

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the chart to draw. The default, if redraw is omitted is **true**.

Note:

Bins may only be removed using this method if they were added using [EJSC.Axis.addBin](#) and no series are currently utilizing them.

5.3.1.2.10 resetZoom (inherited)

Definition

void **resetZoom()**

Description

Resets the zoom for a given axis to use its extreme values for min and max (as if a user had double-clicked the chart or drawn the zoom rectangle anywhere but down and right)

5.3.1.2.11 setCaption (inherited)

Definition

void **setCaption(string caption)**

Description

Updates the axis caption. This method must be used to change the caption once the chart has been rendered. To set a default caption on creation, see [EJSC.Axis.caption](#).

5.3.1.2.12 setCrosshair (inherited)

Definition

void **setCrosshair(boolean visible, float coordinate, boolean fireEvent)**

Description

This method may be used to hide, show and position the cursor position indicator. If the fireEvent parameter is set to true or left undefined the [EJSC.Axis.onShowCrosshair](#) or [EJSC.Axis.onHideCrosshair](#) events will fire.

5.3.1.2.13 setExtremes (inherited)

Definition

void **setExtremes(float min, float max)**

Description

Updates the manual extremes for the axis. Use this method if the series data does not span the range to be displayed on the chart or to limit 100% zoom to a range smaller than the series data.

Example

>> Series data only spans 18 hours on the bottom axis but the chart needs to display an entire day

```
var myChart = new EJSC.Chart( "chart" );
myChart.axis_bottom.setExtremes( 0, 86400000 );
```

5.3.1.2.14 setZoom (inherited)

Definition:

```
void setZoom( float min, float max )
```

Description

Sets the current zoom of the axis to the specified coordinates.

5.3.1.2.15 show (inherited)

Definition

```
void show( )
```

Description

Shows the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already visible.

5.3.1.2.16 showGrid (inherited)

Definition

```
void showGrid( boolean redraw )
```

Description

Shows the background grid for the axis and if redraw is omitted or true, redraws the chart.

No effect if the grid is already visible.

5.3.1.3 Events

5.3.1.3.1 onHideCrosshair (inherited)

Definition

void **onHideCrosshair**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

Called when the axis crosshair is hidden by the chart. This can occur when the user moves their mouse outside of the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending false for the visible parameter and true for the fireEvent parameter.

5.3.1.3.2 onHideCursorPosition (inherited)

Definition

void **onHideCursorPosition**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is fired when the cursor position indicator for an axis is hidden. This will occur when the user's mouse leaves the chart area.

5.3.1.3.3 onNeedsTicks (inherited)

Definition

array **onNeedsTicks**(float min, float max, [EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is triggered whenever the axis ticks need to be redrawn / recalculated. It expects an array of [float y, string label] to be returned which defines exactly where to put the tick marks and labels. In addition, null may be returned in order to skip custom ticks for the current draw and use the chart's build in tick controls.

min: The current minimum value visible on the chart for the axis.

max: The current maximum y value visible on the chart for the axis.

axis: The axis which needs ticks.

chart: The chart that triggered the event.

Notes

- To use the label formatter already assigned to the axis, set label to null (i.e. [min, null])
- To use on an axis with bins (text instead of numbers), simply send in the bin (i.e. ["First Bin", null])

Example

A typical event handler may look like the following:

```
function doBottomAxisNeedsTicks(min, max, axis, chart) {  
  
    // Display 3 tick marks, one at min, one at max and one directly in between  
    var result = new Array();
```

```
result.push( [min, null] );
result.push( [min + ((max - min) / 2), null] );
result.push( [max, null] );

// Given a chart with a min and max of 0 and 100, the resulting array looks like:
// [
//   [0, null],
//   [50, null],
//   [100, null]
// ]
return result;
}
```

5.3.1.3.4 onShowCrosshair (inherited)

Definition

```
void onShowCrosshair( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the axis crosshair is shown by the chart. This can occur when the user moves their mouse into the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending true for the visible parameter and true for the fireEvent parameter.

5.3.1.3.5 onShowCursorPosition (inherited)

Definition

```
void onShowCursorPosition( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the cursor position indicator becomes visible or changes position on a given axis. This will occur when the user enters the chart area or moves their mouse within the chart area.

5.3.2 LogarithmicAxis

LogarithmicAxis may be created and assigned to any of the four chart axes in order to enable a logarithmic scale.

The constructor takes an optional set of object properties used to perform initial configuration.

Constructor

```
EJSC.LogarithmicAxis( [ object options ] )
```

Example

```
var chart = new EJSC.Chart("myChart", {
  axis_bottom: new EJSC.LogarithmicAxis{
```

```

        caption: "Test",
        base: 8
    })
});


```

Defining Properties and Events

LogarithmicAxis properties may be set individually after the chart has been initialized and/or the axis has been created or in batch using the options parameter during instantiation.

Setting properties individually

```

var chart = new EJSC.Chart("myChart", {
    axis_bottom: new EJSC.LogarithmicAxis()
});
chart.axis_bottom.base = 8;
chart.axis_bottom.caption = "Test";
chart.axis_bottom.color = "#F00";

```

Setting properties in batch

```

var chart = new EJSC.Chart("myChart", {
    axis_bottom: new EJSC.LinearAxis({
        base: 8,
        caption: "Test",
        color: "#F00"
    })
});

```

5.3.2.1 Properties

5.3.2.1.1 background (inherited)

Definition

```

object background = {
    color: "#fff",
    opacity: 0,
    includeTitle: false
};

```

Description

Defines the color and opacity of the axis area background. Setting the includeTitle property to true will fill the axis caption area as well as the ticks. If opacity is set to 0, no fill will occur.

5.3.2.1.2 base

Definition

```
number base = 10
```

Description

The term "base" refers to the number which is set to incremental powers to determine the ticks on the axis.

The tick values, if base = b, would be b^x where x is the linear incremental power.

When base = 10, and your range is 10 - 10,000, the tick marks would be:

```
10^1 = 10
10^2 = 100
10^3 = 1,000
10^4 = 10,000
```

5.3.2.1.3 border (inherited)

Definition

```
object border = {
    thickness: 1,
    color: undefined,
    opacity: 100,
    show: true
}
```

Description

Defines the appearance of the axis side bordering the chart area. By default the border color inherits the axis color property ([EJSC.Axis.color](#))

Example

>> Provide a 2 pixel tall green border on the bottom axis.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom:
            border: { thickness: 2, color: "#0F0" }
    }
);
```

5.3.2.1.4 caption (inherited)

Definition

```
string caption = "Axis"
```

Description

Defines the text to be displayed below or beside the axis.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Customize the bottom axis caption.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption: "Year" }
    }
);
```

5.3.2.1.5 caption_class (inherited)

Definition

string **caption_class** = ""

Description

Defines the CSS className to assign to the axis caption.

For styling the tick labels, see [EJSC.Axis.label_class](#)

Example

>> Style the axis caption bold.

```
<style> .AxisCaption { font-style: bold; } </style>

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption_class: "AxisCaption" }
    }
);
```

5.3.2.1.6 color (inherited)

Definition

string **color** = "#FFF"

Description

Defines the default color of the axis border and tick marks. If the sub properties such as minor_ticks.color, major_ticks.color, border.color are left undefined, they inherit the value set here.

Example

>> Color the axis border and tick marks red

```
var chart = new EJSC.Chart(
    "chart",
    {
```

```
        axis_bottom: { color: "#F00" }
    }
);
```

5.3.2.1.7 crosshair (inherited)

Definition

```
object crosshair = {
    show: false,
    color: "#F00"
}
```

Description

Defines if crosshair should be shown on the chart at the current mouse coordinates as they relate to the given axis. May be enabled and disabled for each axis independently. This is automatically disabled for all axes if [EJSC.Chart.allow_interactivity](#) is set to false.

Example

>> Show crosshair based on the bottom axis mouse position.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            crosshair: { show: true }
        }
    }
);
```

5.3.2.1.8 cursor_position (inherited)

Definition

```
object cursor_position = {
    show: false,
    color: "#F00",
    textColor: "#FFF",
    formatter: undefined,
    caption: undefined,
    className: undefined
}
```

Description

Defines the display properties of the cursor position feature for an axis. These properties may be used to turn the cursor position indicator on and off as well as configure the styling and color.

show: determines whether or not to display the cursor position while the mouse is within the chart area

color: sets the background and line color

textColor: sets the text color

formatter: defines a formatter to use when displaying coordinates, if left undefined it will use the axis formatter

caption: defines text to use as a prefix to the current coordinate
className: a CSS class name to be used for additional styling

Example

>> Turn on cursor position for the bottom axis and configure to display a related label

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            cursor_position: {
                show: true,
                caption: "Sales"
            }
        }
    }
);
```

5.3.2.1.9 extremes_ticks (inherited)

Definition

boolean **extremes_ticks** = false

Description

Defines if the min and max values should be forced to land on the next tick mark.

Example

>> Force tick marks at the min and max coordinates of the bottom axis (left and right sides of the chart)

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { extremes_ticks: true }
    }
);
```

5.3.2.1.10 force_static_points (inherited)

Definition

boolean **force_static_points** = false

Description

Defines if the chart should force ticks to match up to every point by converting the data to strings.

Example

>> Display every bottom axis data point, essentially disable auto axis scaling.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { force_static_points: true }
    }
);
```

5.3.2.1.11 formatter (inherited)

Definition

[EJSC.Formatter formatter](#) = EJSC.Formatter

Description

Defines the formatter that will be used to format the tick marks on the axis before displaying them.

Types:

[EJSC.DateFormatter](#)
[EJSC.NumberFormatter](#)
[EJSC.StringFormatter](#)

Example

>> Display bottom axis tick labels as \$0.00

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            formatter: new EJSC.NumberFormatter( { currency_symbol: "$",
forced_decimals: 2, variable_decimals: 2 } )
        }
    }
);
```

5.3.2.1.12 grid (inherited)

Definition

```
object grid = {
    thickness: 1,
    color: "rgb(230,230,230)",
    opacity: 100,
    show: true
}
```

Description

Defines the appearance and visibility of the grid drawn in the background.

Example

>> Do not draw the background grid for the top and right axes.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_top: {
            grid: { show: false }
        },
        axis_right: {
            grid: { show: false }
        }
    }
);
```

5.3.2.1.13 hint_caption

Definition

string **hint_caption** = "Value:"

Description

Defines the text to display in front of the axis-related value in the hint (leave blank to hide the value when displaying the hint).

Example

>> Customize the value label in the hint window

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            hint_caption: "Month:"
        }
    }
);
```

5.3.2.1.14 label_class (inherited)

Definition

string **label_class** = ""

Description

Defines the CSS className to assign to the axis tick labels. Used in conjunction with [EJSC.Axis.stagger_ticks](#) and [EJSC.Axis.size](#), this property allows for greater control over the size and staggering of tick labels on the top and bottom axes.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Style the axis tick labels grey, make them 24 pixels high to enable text wrapping and enable two levels of tick staggering.

```
<style> .AxisTickLabels { color: #999; height: 24px; } </style>

var chart = new EJSC.Chart(
    "chart",
{
    axis_bottom: {
        label_class: "AxisTickLabels",
        size: 48
    }
);

```

5.3.2.1.15 major_ticks (inherited)

Definition

```
object major_ticks = {
    thickness: 1,
    size: 4,
    color: undefined,
    opacity: 100,
    show: true,
    count: undefined,
    offset: 0,
    min_interval: undefined,
    max_interval: undefined
}
```

Description

This set of properties defines the characteristics of the major ticks for a given axis.

thickness: the height or width (depending on axis orientation) of the tick mark

size: the amount the tick mark extends from the axis border, may be specified as a number or a string containing % for a percentage

color: the color of the tick marks, if left undefined this property inherits its value from [EJSC.Axis.color](#)

opacity: the opacity of the tick marks

show: specifies whether to draw the tick marks

count: the number of tick marks to draw, if left undefined the axis will determine the proper amount of ticks to draw automatically based on the range of data available to the axis

Note: This property is not compatible with text labels (i.e. x axis values are "Gizmos", "Widgets", instead of numbers)

offset: distance in pixels or percent from the axis border to begin drawing the tick marks,

min_interval: Defines the minimum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

max_interval: Defines the maximum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

5.3.2.1.16 max_extreme (inherited)

Definition

float **max_extreme** = undefined

Description

Defines the maximum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            max_extreme: 500.00
        }
    }
);
```

5.3.2.1.17 min_extreme (inherited)

Definition

float **min** = undefined

Description

Defines the minimum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            min_extreme: -500.00
        }
    }
);
```

5.3.2.1.18 minor_ticks (inherited)

Definition

```
object minor_ticks = {
    show: false,
    color: "rgb(0,0,0)",
    opacity: 20
    thickness: 1,
    count: 7,
    size: 4,
    offset: 0
}
```

Description

Defines the properties of the minor tick marks to be drawn on the axis. The color, opacity and thickness (width of ticks in pixels) properties define the style of the tick marks. The count property defines the number of tick marks to be drawn between each major tick mark. The size property defines the height of the ticks (in pixels or percent). The offset property defines the distance away from the axis the minor tick marks begin drawing.

Example

>> Display red minor tick marks on the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            minor_ticks: { show: true, color: "#FF0000" }
        }
    }
);
```

5.3.2.1.19 size (inherited)

Definition

integer **size** = 20

Description

Defines the height of horizontal axes or width of vertical axes (in pixels) of the tick area. To fully enable staggered ticks on horizontal axes, set this property to a multiple of 20 (or axis tick height), i.e. two levels = 40, three levels = 60.

For additional control over the format of the labels, see the [EJSC.Axis.label_class](#) property.

Example

>> Make axis tick area twice as tall, enabling staggered ticks (default tick label height is 20 pixels)

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { size: 40 }
    }
);
```

5.3.2.1.20 stagger_ticks (inherited)

Definition

boolean **stagger_ticks** = true

Description

Determines whether the axis tick labels are staggered.

NOTE: This property is only applicable to horizontal axes (i.e. [EJSC.Chart.axis_top](#) and [EJSC.Chart.axis_bottom](#))

Example

>> Disable tick staggering for the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { stagger_ticks: false }
    }
);
```

5.3.2.1.21 visible (inherited)

Definition

boolean **visible** = true

Description

Defines if the axis (containing axis caption and tick labels) should be displayed.

Example

>> Remove the bottom axis from the chart to allow additional room for data

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { visible: false }
    }
);
```

5.3.2.1.22 zero_plane (inherited)

Definition

```
object zero_plane = {
    color: "rgb(0,0,0)",
    show: false,
    opacity: 100,
    thickness: 1,
    coordinate: 0
}
```

Description

Defines the properties of the zero plane line to be drawn at 0 (or whatever the coordinate property is set to). It is used to specify if the line should be shown as well as its color, thickness and opacity. The coordinate property allows the base of [EJSC.BarSeries](#), [EJSC.StackedBarSeries](#) and [EJSC.AreaSeries](#) changed.

Example

>> Display a 2 pixel thick dark green line on the zero plane of the left axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_left: {
            zero_plane: { show: true, color: "rgb(7,89,5)", thickness: 2 }
        }
    }
);
```

5.3.2.2 Methods

5.3.2.2.1 addBin (inherited)

Definition

```
void addBin( String label, boolean redraw )
```

Description

Adds a new static label to the axis and sets the appropriate flags if necessary to force the chart to draw using static labels (as opposed to a dynamic range based on series data).

This method is useful if there is a need to include bins which may not be part of any series added (i.e. chart labels should be "Apples", "Oranges", "Pears" but the series data only contains data pertaining to Apples and Pears).

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the chart to draw. The default, if redraw is omitted is **true**.

Note:

Manually added bins may only be removed if there are no series currently utilizing them.

Example

>> Add bins in a specific order to ensure they appear the same each time the chart is loaded, regardless of the order in which they appear in the data.

```
var myChart = new EJSC.Chart("chart");
myChart.axis_bottom.addBin("Salesman 1");
myChart.axis_bottom.addBin("Salesman 2");
myChart.axis_bottom.addBin("Salesman 3");

var mySeries = myChart.addSeries(
    new EJSC.BarSeries(...)
);
```

5.3.2.2.2 getExtremes (inherited)

Definition

object **getExtremes()**

RETURNS:

{ min: float, max: float }

Description

Returns the current axis extreme values.

To set the extreme values, see [EJSC.Axis.setExtremes](#)

5.3.2.2.3 getZoom (inherited)

Definition

object **getZoom()**

RETURNS:

{ min: float, max: float }

Description

Returns the current zoom coordinates for a given axis in chart units.

To set the zoom coordinates, see [EJSC.Axis.setZoom](#)

5.3.2.2.4 getZoomBoxCoordinates (inherited)

Definition

void **getZoomBoxCoordinates()**

RETURNS:

{ min: float, max: float }

Description

Returns the min and max values for a given axis of the current zoom box. These values are in chart coordinates, not pixels.

5.3.2.2.5 **hide** (inherited)

Definition

void **hide()**

Description

Hides the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already hidden.

5.3.2.2.6 **hideGrid** (inherited)

Definition

void **hideGrid(boolean redraw)**

Description

Hides the background grid for a given axis and if redraw is omitted or true, redraws the chart

No effect if the grid is already hidden.

5.3.2.2.7 **pixelToPoint** (inherited)

Definition

float **pixelToPoint(integer Pixel)**

Description

Converts the pixel coordinate into chart units based on an axis. The result will be undefined if the pixel location is outside of the chart area.

5.3.2.2.8 **pointToPixel** (inherited)

Definition

integer **pointToPixel(number coordinate)**

Description

Converts the chart coordinates based on axis data into the appropriate pixel position for that point (x or y depending on the orientation of the axis)

The result will be undefined if the coordinate provided is outside the currently displayed range.

5.3.2.2.9 removeBin (inherited)

Definition

```
void removeBin( String label, boolean redraw )
```

Description

Removes a bin (static text label) from the axis.

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the chart to draw. The default, if redraw is omitted is **true**.

Note:

Bins may only be removed using this method if they were added using [EJSC.Axis.addBin](#) and no series are currently utilizing them.

5.3.2.2.10 resetZoom (inherited)

Definition

```
void resetZoom()
```

Description

Resets the zoom for a given axis to use its extreme values for min and max (as if a user had double-clicked the chart or drawn the zoom rectangle anywhere but down and right)

5.3.2.2.11 setCaption (inherited)

Definition

```
void setCaption( string caption )
```

Description

Updates the axis caption. This method must be used to change the caption once the chart has been rendered. To set a default caption on creation, see [EJSC.Axis.caption](#).

5.3.2.2.12 setCrosshair (inherited)

Definition

```
void setCrosshair( boolean visible, float coordinate, boolean fireEvent )
```

Description

This method may be used to hide, show and position the cursor position indicator. If the fireEvent parameter is set to true or left undefined the [EJSC.Axis.onShowCrosshair](#) or [EJSC.Axis.onHideCrosshair](#) events will fire.

5.3.2.2.13 setExtremes (inherited)

Definition

```
void setExtremes( float min, float max )
```

Description

Updates the manual extremes for the axis. Use this method if the series data does not span the range to be displayed on the chart or to limit 100% zoom to a range smaller than the series data.

Example

>> Series data only spans 18 hours on the bottom axis but the chart needs to display an entire day

```
var myChart = new EJSC.Chart( "chart" );
myChart.axis_bottom.setExtremes( 0, 86400000 );
```

5.3.2.2.14 setZoom (inherited)

Definition:

```
void setZoom( float min, float max )
```

Description

Sets the current zoom of the axis to the specified coordinates.

5.3.2.2.15 show (inherited)

Definition

```
void show( )
```

Description

Shows the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already visible.

5.3.2.2.16 showGrid (inherited)

Definition

void **showGrid**(boolean redraw)

Description

Shows the background grid for the axis and if redraw is omitted or true, redraws the chart.

No effect if the grid is already visible.

5.3.2.3 Events

5.3.2.3.1 onHideCrosshair (inherited)

Definition

void **onHideCrosshair**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

Called when the axis crosshair is hidden by the chart. This can occur when the user moves their mouse outside of the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending false for the visible parameter and true for the fireEvent parameter.

5.3.2.3.2 onHideCursorPosition (inherited)

Definition

void **onHideCursorPosition**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is fired when the cursor position indicator for an axis is hidden. This will occur when the user's mouse leaves the chart area.

5.3.2.3.3 onNeedsTicks (inherited)

Definition

array **onNeedsTicks**(float min, float max, [EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is triggered whenever the axis ticks need to be redrawn / recalculated. It expects an array of [float y, string label] to be returned which defines exactly where to put the tick marks and labels. In addition, null may be returned in order to skip custom ticks for the current draw and use the chart's build in tick controls.

min: The current minimum value visible on the chart for the axis.
max: The current maximum y value visible on the chart for the axis.
axis: The axis which needs ticks.
chart: The chart that triggered the event.

Notes

- To use the label formatter already assigned to the axis, set label to null (i.e. [min, null])
- To use on an axis with bins (text instead of numbers), simply send in the bin (i.e. ["First Bin", null])

Example

A typical event handler may look like the following:

```
function doBottomAxisNeedsTicks(min, max, axis, chart) {
    // Display 3 tick marks, one at min, one at max and one directly in between
    var result = new Array();

    result.push( [min, null] );
    result.push( [min + ((max - min) / 2), null] );
    result.push( [max, null] );

    // Given a chart with a min and max of 0 and 100, the resulting array looks like:
    // [
    //   [0, null],
    //   [50, null],
    //   [100, null]
    // ]
    return result;
}
```

5.3.2.3.4 onShowCrosshair (inherited)

Definition

```
void onShowCrosshair( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the axis crosshair is shown by the chart. This can occur when the user moves their mouse into the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending true for the visible parameter and true for the fireEvent parameter.

5.3.2.3.5 onShowCursorPosition (inherited)

Definition

```
void onShowCursorPosition( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the cursor position indicator becomes visible or changes position on a given axis. This will occur when the user enters the chart area or moves their mouse within the chart area.

5.4 Series Types

5.4.1 EJSC.AnalogGaugeSeries

In order to use the AnalogGaugeSeries, the file EJSChart_Gauges.js must be included in the HTML page after the inclusion of the standard EJSChart.js file.

```
<head>
    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>
    <script type="text/javascript" src="/EJSChart/EJSChart_Gauges.js"></script>
</head>
```

The AnalogGaugeSeries is rendered as a circular (or semi-circular) gauge with a needle directed towards the current value stored in its [EJSC.GaugePoint](#).

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.AnalogGaugeSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var myAnalogGaugeSeries = new EJSC.AnalogGaugeSeries(
    new EJSC.ArrayDataHandler([[50,"Gauge Value"]]),
    { title: "New Analog Gauge Series" }
);
```

Defining Properties and Events

AnalogGaugeSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.AnalogGaugeSeries(new EJSC.ArrayDataHandler([[50,"Gauge Value"]]));
mySeries.title = "New Analog Gauge Series";
mySeries.min = 0;
mySeries.max = 100;
```

Setting properties in batch

```
var mySeries = new EJSC.AnalogGaugeSeries(
    new EJSC.ArrayDataHandler([[50,"Gauge Value"]]),
```

```

        { title: "New Analog Gauge Series", min: 0, max: 100 }
    );

```

5.4.1.1 Properties

5.4.1.1.1 anchor

Definition

```

object anchor = {
    color:          'rgb(0,0,0)',
    opacity:        100 ,
    size:           10
}

```

Description

Defines the parameters for the anchor on the gauge.

Properties

string color	– Defines the color of the anchor.
integer opacity	– Defines the opacity of the anchor.
integer size	– Defines the diameter (in pixels) of the anchor.

5.4.1.1.2 axis

Definition

```

object axis = {
    color:          'rgb(255,255,255)',
    innerBorderColor: 'rgb(0,0,0)',
    innerBorderOpacity: 100 ,
    innerBorderWidth: 1 ,
    innerBorderVisible: true ,
    opacity:        0 ,
    outerBorderColor: 'rgb(0,0,0)',
    outerBorderOpacity: 100 ,
    outerBorderWidth: 1 ,
    outerBorderVisible: true ,
    thickness:      15
}

```

Description

Defines the parameters for the axis on the gauge.

Properties

string color	– Defines the background color of the axis.
string innerBorderColor	– Defines the color of the inner border.
integer innerBorderOpacity	– Defines the opacity of the inner border.

integer innerBorderWidth	– Defines the width of the inner border.
integer innerBorderVisible	– Defines whether the inner border is visible or not.
integer opacity	– Defines the opacity of the background color of the axis.
string outerBorderColor	– Defines the color of the outer border.
integer outerBorderOpacity	– Defines the opacity of the outer border.
integer outerBorderWidth	– Defines the width of the outer border.
boolean outerBorderVisible	– Defines whether the outer border is visible or not.
integer thickness	– Defines the thickness of the axis.

5.4.1.1.3 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.1.1.4 fillColor

Definition

string **fillColor** = undefined

Description

Defines the background fill color of the gauge. Leave undefined for no fill color. This should be defined as `rgb(<RED>,<GREEN>,<BLUE>)`, i.e. red = "rgb(255,0,0)"

5.4.1.1.5 fillOpacity

Definition

integer **fillOpacity** = 100

Description

Defines the opacity for the background fill color of the gauge.

5.4.1.1.6 height

Definition

string **height** = "100%"

Description

Defines the total height of the gauge. This may be specified in percent of the chart as shown above as

the default value, or in exact pixels by specifying a number (i.e. height = 150;).

5.4.1.1.7 label

Definition

```
object label = {  
    className: "",  
    textAlign: 'center',  
    position: 'centerBottom',  
    lines: 1  
}
```

Description

Defines the parameters for the label on the gauge.

Properties

string className	– Defines a class (to be defined in an attached stylesheet) to be applied to the label.
string textAlign	– Defines the alignment of the text in the label ('left', 'center', or 'right').
string position	– Defines the position on the gauge the label will be placed (see below).
integer lines	– Defines the number of lines to display in the label. (Text will overflow unless otherwise specified in the attached style class).

Values for position:

- bottom
- centerBottom
- centerLeft
- centerRight
- centerTop
- left
- right
- top

5.4.1.1.8 legendIsVisible (inherited)

Definition

```
boolean legendIsVisible = true
```

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.1.1.9 lock

Definition

```
object lock = {
```

```
    color:      'rgb(0,0,0)',  
    offset:     5 ,  
    opacity:   100 ,  
    size:       6 ,  
    visible:  false  
}
```

Description

Defines the parameters for the "locks", or "pegs" on the gauge.

Properties

string **color** – Defines the color of the locks.
integer **offset** – Defines the distance (in pixels) the needle is allowed to extend past the min/max value.
Set to undefined to turn locks off.
integer **opacity** – Defines the opacity of the locks.
integer **size** – Defines the diameter (in pixels) of the locks.
boolean **visible** – Defines whether or not to visually show the locks.

5.4.1.1.10 marker_position

Definition

```
string marker_position = "outer"
```

Description

Defines where the tick markers will be positioned with respect to the axis.

Quadrants:

- outer
- inner

5.4.1.1.11 max

Definition

```
float max = 100
```

Description

Defines the maximum value to be displayed on the gauge.

5.4.1.1.12 min

Definition

```
float min = 0
```

Description

Defines the minimum value to be displayed on the gauge.

5.4.1.1.13 minorTick

Definition

```
object minorTick = {
    color: 'rgb(150,150,150)' ,
    count: 4 ,
    offset: 0 ,
    opacity: 100 ,
    size: 1 ,
    thickness: 15
}
```

Description

Defines the parameters for the minor ticks on the gauge.

Properties

string color	– Defines the color of the minor tick marks.
integer count	– Defines the number of minor tick marks to display between each major tick mark.
integer offset	– Defines the distance (in pixels) the minor tick marks are pushed out from the inner axis border.
integer opacity	– Defines the opacity of the minor tick marks.
integer size	– Defines the width (in pixels) of the minor tick marks.
integer thickness	– Defines the thickness (in pixels) of the minor tick marks.

5.4.1.1.14 needle

Definition

```
object needle = {
    borderColor: 'rgb(0,0,0)' ,
    borderOpacity: 100 ,
    borderWidth: 1 ,
    color: 'rgb(0,0,0)' ,
    opacity: 100 ,
    size: 4
}
```

Description

Defines the parameters for the needle on the gauge.

Properties

string borderColor	– Defines the color of the border.
integer borderOpacity	– Defines the opacity of the border.

integer borderWidth	– Defines the width of the border.
string color	– Defines the background color of the needle.
integer opacity	– Defines the opacity of the needle.
integer size	– Defines the width (in pixels) of the needle at its base.

5.4.1.1.15 position

Definition

```
string position = "center"
```

Description

Defines the quadrant of the chart that the gauge will appear in.

Quadrants:

- topLeft
- topCenter
- topRight
- centerLeft
- center
- centerRight
- bottomLeft
- bottomCenter
- bottomRight

5.4.1.1.16 range

Definition

```
object range = {
    borderColor: 'rgb(0,0,0)',
    borderOpacity: 100,
    borderWidth: 1 ,
    offset: 0 ,
    opacity: 100 ,
    style: 'doughnut',
    thickness: 15
}
```

Description

Defines the parameters for the ranges on the gauge.

Properties

string borderColor	– Defines the color of the border.
integer borderOpacity	– Defines the opacity of the border.
integer borderWidth	– Defines the width of the border.
integer offset	– Defines the distance (in pixels) the ranges are pushed in from the axis.
integer opacity	– Defines the opacity of the ranges.
string style	– Defines the style to draw the range in ('doughnut' or 'pie')

integer **thickness** – Defines the thickness (in pixels) of the ranges.

5.4.1.1.17 range_degrees

Definition

integer **range_degrees** = 180

Description

Defines the total angle (in degrees) the gauge will take up.

5.4.1.1.18 ranges

Definition

array **ranges** = new Array();

Description

Defines a series of ranges to be marked in the gauge.

Implementation

mySeries.ranges = [[int min, int max, string color] , ...]

Example

```
mySeries.ranges = [
    [0,10,'rgb(255,0,0)'],
    [10,20,'rgb(0,255,0)']
];
```

5.4.1.1.19 start_degree

Definition

integer **start_degree** = 270

Description

Defines the angle (in degrees) at which the gauges' min value is displayed.

5.4.1.1.20 tick

Definition

```
object tick = {
    className:      "",
    color:          'rgb(0,0,0)',
    offset:         0,
    opacity:        100,
```

```
    size:      1 ,  
    thickness: 15  
}
```

Description

Defines the parameters for the major ticks on the gauge.

Properties

string className	– Defines a class (to be defined in an attached stylesheet) to be applied to the tick markers.
string color	– Defines the color of the tick marks.
integer offset	– Defines the distance (in pixels) the tick marks are pushed out from the inner axis border.
integer opacity	– Defines the opacity of the tick marks.
integer size	– Defines the width (in pixels) of the tick marks.
integer thickness	– Defines the thickness (in pixels) of the tick marks.

5.4.1.1.21 **TickCount**

Definition

```
integer TickCount = 11
```

Description

Defines the number of major ticks to be displayed on the gauge's axis

5.4.1.1.22 **title** (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.1.1.23 **visible** (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.1.1.24 width

Definition

string **width** = "100%"

Description

Defines the total width of the gauge. This may be specified in percent of the chart as shown above as the default value, or in exact pixels by specifying a number (i.e. width = 150;).

5.4.1.1.25 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)
[EJSC.NumberFormatter](#)

5.4.1.2 Methods

5.4.1.2.1 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler()**

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.1.2.2 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.1.2.3 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.1.2.4 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.1.2.5 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.4.1.2.6 setDataHandler (inherited)

Definition

void **setDataHandler([EJSC.DataHandler](#) dataHandler, boolean reload)**

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.1.2.7 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.1.2.8 `show` (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.1.2.9 `showLegend` (inherited)

Definition

```
void showLegend( )
```

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.1.3 Events

5.4.1.3.1 `onAfterDataAvailable` (inherited)

Definition

```
boolean onAfterDataAvailable( EJSC.Chart chart, EJSC.Series series )
```

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.1.3.2 `onAfterVisibilityChange` (inherited)

Definition

```
boolean onAfterVisibilityChange( EJSC.Series series, EJSC.Chart chart, boolean visible )
```

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.1.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.1.4 Data Formats

The x parameter is required, label and userdata are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
  <plot>
    <point x="number or string" label="string" userdata="string"/>
  </plot>
<graph>
```

Short:

```
<G>
  <L>
    <P x="number or string" label="string" userdata="string"/>
  </L>
</G>
```

Compact: The values parameter is formatted as CSV

```
<G>
  <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```
[  
    ["x", "label", "userdata"]  
]
```

Null should be used to skip unused parameters:

```
[  
    ["x", null, "userdata"]  
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

```
"x|label|userdata"
```

Null should be used to skip unused parameters

```
"x|null|userdata"
```

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[{"x": "number or string", "label": "string", "userdata": "string"}]
```

5.4.2 EJSC.AreaSeries

AreaSeries is rendered by drawing a line from point to point and then filling the area defined.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.AreaSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.AreaSeries(  
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),  
    { title: "New Area Series" }  
>;
```

Defining Properties and Events

AreaSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.AreaSeries(new
EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]));
mySeries.lineWidth = 1;
mySeries.title = "New Area Series";
```

Setting properties in batch

```
var mySeries = new EJSC.AreaSeries(
new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
{ lineWidth: 1, title: "New Area Series" }
);
```

5.4.2.1 Properties

5.4.2.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.2.1.2 closeLine

Definition

boolean **closeLine** = true

Description

Defines whether the line drawn around the area returns to the zero plane to create a complete shape (true) or if it drawn only through the points in the data set (false).

5.4.2.1.3 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.2.1.4 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.2.1.5 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.2.1.6 drawPoints (inherited)

Definition

boolean **drawPoints** = false

Description

Determines whether the individual points in the series are visually indicated by round dots on the chart. The size and color of the fill and border are determined by the [pointColor](#), [pointSize](#), [pointBorderColor](#) and [pointBorderSize](#) properties.

Note: Setting this property to true for series which have a large number of points may impact performance as additional draws are required to render the points.

5.4.2.1.7 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:</strong>[y]"
}
);
```

5.4.2.1.8 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.2.1.9 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.2.1.10 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.2.1.11 opacity (inherited)

Definition

integer **opacity** = 50

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.2.1.12 pointBorderColor (inherited)

Definition

```
string pointBorderColor = "rgb(255,255,255)"
```

Description

Defines the color of the border drawn around the points. This property is only applicable when the series [drawPoints](#) property is set to true and [pointBorderSize](#) is greater than 0.

5.4.2.1.13 pointBorderSize (inherited)

Definition

```
integer pointBorderSize = 0
```

Description

Defines the size in pixels of the border drawn around the points. This property is only applicable when the series [drawPoints](#) property is set to true.

To draw points without any border, leave pointBorderSize set to 0.

5.4.2.1.14 pointColor (inherited)

Definition

```
string pointColor = undefined
```

Description

Defines the color of the point (circle) drawn at each data point in the series. If left undefined the point will inherit the series color.

This property is only applicable when the series [drawPoints](#) property is set to true.

5.4.2.1.15 pointSize (inherited)

Definition

```
integer pointSize = undefined
```

Description

Defines the size of the point (circle) drawn at each data point in the series. If left undefined the point diameter will be twice the line width of the series.

This property is only applicable when the series [drawPoints](#) property is set to true.

5.4.2.1.16 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.2.1.17 visible (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.2.1.18 x_axis (inherited)

Definition

```
string x_axis = "bottom"
```

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.2.1.19 x_axis_formatter (inherited)

Definition

```
string x_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.2.1.20 y_axis

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.2.1.21 y_axis_formatter (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.2.2 Methods

5.4.2.2.1 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler()**

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.2.2.2 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.2.2.3 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.2.2.4 `hideLegend` (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.2.2.5 `reload` (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base Series class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.2.2.6 `setColor` (inherited)

Definition

void **setColor**(string color)

Description

Changes the series color and causes the chart to redraw.

5.4.2.2.7 `setColoredLegend` (inherited)

Definition

void **setColoredLegend**(boolean coloredLegend)

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.2.2.8 setDataHandler (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.2.2.9 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.2.2.10 setOpacity (inherited)

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.2.2.11 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.2.2.12 show (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.2.2.13 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.2.3 Events

5.4.2.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable([EJSC.Chart](#) chart, [EJSC.Series](#) series)**

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.2.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.2.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart)**

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The

current visible state of the series may be checked using the `series.visible` property.

Returning `false` from this event handler will cancel the change in visibility.

5.4.2.3.4 `onShowHint` (inherited)

Definition

string `onShowHint(EJSC.Point point, EJSC.Series series, EJSC.Chart chart, string hint_string)`

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.2.4 Data Formats

The `x` and `y` parameters are required, `label` and `userdata` are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
    <plot>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
    </plot>
<graph>
```

Short:

```
<G>
    <L>
        <P x="number or string" y="number or string" label="string"
userdata="string"/>
        <P x="number or string" y="number or string" label="string"
userdata="string"/>
    </L>
</G>
```

Compact: The `values` parameter is formatted as CSV

```
<G>
    <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```
[  
  ["x", "y", "label", "userdata"],  
  ["x", "y", "label", "userdata"]  
]
```

Null should be used to skip unused parameters:

```
[  
  ["x", "y", null, "userdata"],  
  ["x", "y", null, "userdata"]  
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|y|label|userdata,x|y|label|userdata"

Null should be used to skip unused parameters

"x|y|null|userdata,x|y|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[  
  {"x": "number or string", "y": "number or  
string", "label": "string", "userdata": "string"},  
  {"x": "number or string", "y": "number or  
string", "label": "string", "userdata": "string"}  
]
```

5.4.2.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[label]	The label property of the current point

5.4.3 EJSC.BarSeries

BarSeries renders its points as vertical or horizontal bars which are fixed to a baseline.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.BarSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.BarSeries(  
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),  
    { title: "New Bar Series" }  
>;
```

Defining Properties and Events

BarSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.BarSeries(  
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]));  
    mySeries.lineWidth = 1;  
    mySeries.title = "New Bar Series";
```

Setting properties in batch

```
var mySeries = new EJSC.BarSeries(  
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),  
    { lineWidth: 1, title: "New Bar Series" }  
>;
```

5.4.3.1 Properties

5.4.3.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.3.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.3.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.3.1.4 defaultColors

Definition

array **defaultColors** = [EJSC.DefaultBarColors](#)

Description

Defines the pool of default colors available for bar series bars.

NOTE: To make use of individually colored bars, the [EJSC.BarSeries.useColorArray](#) property must be set to true.

5.4.3.1.5 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.3.1.6 groupedBars

Definition

boolean **groupedBars** = true

Description

Defines whether the bars from different bar series in a single chart are grouped or overlayed.

NOTE: Only the first bar series added to the chart may use this property to affect the grouped/overlay display. To change the style after the first bar series has been added, use the [EJSC.BarSeries.setGroupedBars](#) from any bar series in the chart. Currently you cannot mix both overlayed and grouped bars within the same chart.

Example

>> Make the bar series overlay

```
var chart = new EJSC.Chart("chart");
var bar1 = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        groupedBars: false,
    }
));
var bar2 = chart.addSeries(new EJSC.BarSeries(data));
```

5.4.3.1.7 `hint_string` (inherited)

Definition

string `hint_string` = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br /><strong>Y:</strong>[y]"
});
```

5.4.3.1.8 `intervalOffset`

Definition

float `intervalOffset` = 0.8

Description

Defines the spacing between the bars as a percentage of 1. 1 = bars take up the entire width available, with their sides touching.

Example

>> Make the bars take up 1/2 their available width. (i.e. more space between bars than by default)

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        intervalOffset: 0.5
    }
));
```

5.4.3.1.9 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.3.1.10 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.3.1.11 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.3.1.12 opacity (inherited)

Definition

```
integer opacity = 50
```

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.3.1.13 orientation

Definition

```
string orientation = "vertical"
```

Description

This property determines the orientation of the bar series. The supported property values are "vertical" and "horizontal".

Note: Currently this is a creation-time only property and should not be changed after the series has been created.

5.4.3.1.14 ranges

Definition

```
array ranges = new Array()
```

Description

This property is used to store the ranges for a given bar series. The range objects are used to draw bars in varying styles based on their Y value.

The range objects stored are defined as:

```
range = {
    min:          float, // >=
    max:          float, // <
    color:        string, // Defined as rgb(RED,GREEN,BLUE), ex: "rgb(255,0,0)"
    opacity:      integer, // Represents percent, i.e. 50 = 50%
    lineOpacity:  integer, // Represents percent, i.e. 50 = 50%
    lineWidth:    integer // Represents the line width in pixels
}
```

Example

>> Define ranges so that bars with a Y value from 0 to 10 and 90 to 100 are colored red, bars 10 - 90 are colored green

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
```

```
{
    ranges: [
        { 0, 10, "rgb(255,0,0)", 100, 100, 1 },
        { 90, 100, "rgb(255,0,0)", 100, 100, 1 },
        { 10, 90, "rgb(0,255,0)", 100, 100, 1 }
    ]
});
});
```

5.4.3.1.15 title (inherited)

Definition

string **title** = "Series <index>"

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.3.1.16 treeLegend

Definition

boolean **treeLegend** = false

Description

Defines whether to display each bar individually in the legend.

If the [useColorArray](#) property is true and treeLegend left at its default (not defined in options), the treeLegend property will automatically be set to true to enable tree-style legend display.

5.4.3.1.17 useColorArray

Definition

boolean **useColorArray** = false

Description

Defines whether to make use of the [EJSC.BarSeries.defaultColors](#) property

Example

>> Use the color array to make a chart of multi colored bars

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
{
```

```
        useColorArray: true
    }
) );
```

5.4.3.1.18 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.3.1.19 x_axis (inherited)

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.3.1.20 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.3.1.21 y_axis (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.3.1.22 y_axis_formatter (inherited)

Definition

```
string y_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.3.2 Methods

5.4.3.2.1 addRange

Definition

```
void addRange( float min, float max, string color, integer opacity, integer lineOpacity, integer lineWidth, boolean redraw )
```

Description

Adds a new range to the bar series and optionally triggers a redraw.

5.4.3.2.2 clearRanges

Definition

```
void clearRanges( boolean redraw )
```

Description

Clears all ranges defined for the series and optionally redraws the chart.

5.4.3.2.3 deleteRange

Definition

```
void deleteRange( float min, float max, boolean redraw )
```

Description

Deletes the matching range (min and max must exactly match an existing range) and optionally redraws the chart.

5.4.3.2.4 getBarSize

Definition

```
integer getBarSize()
```

Description

This method returns the size in pixels (width or height depending on orientation) of a single bar.

5.4.3.2.5 `getDataHandler` (inherited)

Definition

EJSC.DataHandler **`getDataHandler()`**

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.3.2.6 `getPoints`

Definition

array **`getPoints()`**

Description

This method returns an array of all [EJSC.BarPoint](#) objects in the series.

5.4.3.2.7 `getVisibility` (inherited)

Definition

boolean **`getVisibility()`**

Description

Returns a boolean indicating the series current visible state

5.4.3.2.8 `hide` (inherited)

Definition

void **`hide()`**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.3.2.9 `hideLegend` (inherited)

Definition

void **`hideLegend()`**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.3.2.10 `reload` (inherited)

Definition

`void reload()`

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base Series class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.3.2.11 `setColor` (inherited)

Definition

`void setColor(string color)`

Description

Changes the series color and causes the chart to redraw.

5.4.3.2.12 `setColoredLegend` (inherited)

Definition

`void setColoredLegend(boolean coloredLegend)`

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.3.2.13 `setDataHandler` (inherited)

Definition

`void setDataHandler(EJSC.DataHandler dataHandler, boolean reload)`

Description

Updates the series data handler and triggers a data reload if reload parameter is `true`. This method may not be implemented in all child classes.

5.4.3.2.14 setDefaultColors

Definition

```
void setDefaultColors( array colors, boolean reload )
```

Description

Set the array of default colors available for bar series bars.

If `reload = true` the bars (if loaded) will pull their colors from the given color array and the chart will be redrawn.

If [onBarNeedsColor](#) is assigned, this method will ignore that event and load the colors from the array.

Example

```
var colors = [
    "rgb('0,0,0')",           // black
    "rgb(255,0,0)",          // red
    "rgb("0,255,0)",         // green
    "rgb("0,0,255")",        // blue
    "rgb("255,255,255)"     // white
];
myBarSeries.setDefaultColors(colors, true);
```

5.4.3.2.15 setGroupedBars

Definition

```
void setGroupedBars( boolean grouped, boolean redraw )
```

Description

Changes the chart between grouped and overlayed bars and optionally triggers a redraw.

5.4.3.2.16 setIntervalOffset

Definition

```
void setIntervalOffset( float offset, boolean redraw )
```

Description

Updates the interval offset property (spacing between the bars) and optionally redraws the chart. See [EJSC.BarSeries.intervalOffset](#) for additional information.

5.4.3.2.17 setLineWidth (inherited)

Definition

void **setLineWidth**(integer width)

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.3.2.18 setOpacity (inherited)

Definition

void **setOpacity**(integer opacity)

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.3.2.19 setTitle (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.3.2.20 show (inherited)

Definition

void **show**()

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.3.2.21 showLegend (inherited)

Definition

void **showLegend**()

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.3.3 Events

5.4.3.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable**([EJSC.Chart](#) chart, [EJSC.Series](#) series)

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.3.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.3.3.3 onBarNeedsColor

Definition

string **onBarNeedsColor**([EJSC.BarPoint](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart)
object **onBarNeedsColor**([EJSC.BarPoint](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired when a bar needs a color. This event may return either a string (i.e. "rgb(0,255,0)") or an object with additional styling properties.

The object returned is expected to be formatted as:

```
{  
    color:      string,  
    opacity:    integer,  
    lineOpacity: integer,  
    lineWidth:  integer  
}
```

Example

>> Display bars with userdata of "bold" with thicker lines

```
var chart = new EJSC.Chart("chart");
```

```

var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        lineOpacity: 80,
        lineWidth: 1,
        onBarNeedsColor: function(point, series, chart) {

            if (point.userdata == "bold") {
                return {
                    color: "rgb(0,0,0)",
                    opacity: 100,
                    lineOpacity: 100,
                    lineWidth: 100
                };
            } else {
                return "rgb(128,128,128)";
            }
        }
    );
);

```

5.4.3.3.4 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.3.3.5 onShowHint (inherited)

Definition

string **onShowHint**([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.3.4 Data Formats

The x and y parameters are required, label and userdata are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

<graph>

```

    <plot>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
    </plot>
<graph>

```

Short:

```

<G>
    <L>
        <P x="number or string" y="number or string" label="string"
userdata="string"/>
        <P x="number or string" y="number or string" label="string"
userdata="string"/>
    </L>
</G>

```

Compact: The values parameter is formatted as CSV

```

<G>
    <L values="CSV string"/>
</G>

```

Array ([EJSC.ArrayDataHandler](#)):

```

[
    ["x", "y", "label", "userdata"],
    ["x", "y", "label", "userdata"]
]

```

Null should be used to skip unused parameters:

```

[
    ["x", "y", null, "userdata"],
    ["x", "y", null, "userdata"]
]

```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|y|label|userdata,x|y|label|userdata"

Null should be used to skip unused parameters

"x|y|null|userdata,x|y|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[  
    {"x":"number or string","y":"number or  
string","label":"string","userdata":"string"},  
    {"x":"number or string","y":"number or  
string","label":"string","userdata":"string"}  
]
```

5.4.3.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[label]	The label property of the current point

5.4.4 EJSC.CandlestickSeries

In order to use the CandlestickSeries, the file EJSChart_Stock.js must be included in the HTML page after the inclusion of the standard EJSChart.js file.

```
<head>  
    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>  
    <script type="text/javascript" src="/EJSChart/EJSChart_Stock.js"></script>  
</head>
```

CandlestickSeries renders its point data as vertical boxes with optional "wicks" to express open and close values.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.CandlestickSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.CandlestickSeries(  
    new EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,19]]),  
    { title: "New Candlestick Series" }  
);
```

Defining Properties and Events

CandlestickSeries properties may be set individually after the series has been created or in batch using

the options parameter during instantiation.


Setting properties individually

```
var mySeries = new EJSC.CandlestickSeries(new
    EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,19]]));
    mySeries.lineWidth = 1;
    mySeries.title = "New Candlestick Series";
```

Setting properties in batch

```
var mySeries = new EJSC.CandlestickSeries(
    new EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,9]]),
    { lineWidth: 1, title: "New Candlestick Series" }
);
```

Emprise JavaScript Charts



5.4.4.1 Properties

5.4.4.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.4.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.4.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.4.1.4 delayLoad (inherited)

EXPERIMENTAL**Definition**

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.4.1.5 gain

Definition

```
object gain = {
    lineColor: "rgb(151,183,247)",
    lineOpacity: 100,
    color: "rgb(151,183,247)",
    opacity: 50
}
```

Description

Defines the appearance of the points which represent a gain.

Example


```
var series = new EJSC.CandlestickSeries(new EJSC.DataHandler(),
{
    gain {
```

```

        lineColor: "#006600",
        lineOpacity: 50,
        color: "#000000",
        opacity: 0
    }
}
);

```

Emprise JavaScript Charts



5.4.4.1.6 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```

var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br /><strong>Y:</strong>[y]"
});

```

5.4.4.1.7 intervalOffset

Definition

float **intervalOffset** = 0.8


Description

Defines the spacing between the points as a percentage of 1. 1 = points take up the entire width available, with their sides touching.

Example

```
var chart = new EJSC.Chart("chart");
var series = chart.addSeries(new EJSC.CandlestickSeries(
    data,
    {
        intervalOffset: 1
    }
));
```

Emprise JavaScript Charts



5.4.4.1.8 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.4.1.9 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.4.1.10 lineWidth (inherited)

Definition

```
integer lineWidth = 1
```

Description

Defines the width of the line connecting series points.

5.4.4.1.11 loss

Definition

```
object loss = {
    lineColor: "rgb(249,95,95)",
    lineOpacity: 100,
    color: "rgb(249,95,95)",
    opacity: 50
}
```


Description

Defines the appearance of the points which represent a loss.

Example

```
var series = new EJSC.CandlestickSeries(new EJSC.DataHandler(),
{
    loss {
        lineColor: "#996600",
        lineOpacity: 50,
        color: "#000000",
        opacity: 0
    }
});
```

Emprise JavaScript Charts



5.4.4.1.12 opacity (inherited)

Definition

```
integer opacity = 50
```

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.4.1.13 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.4.1.14 visible (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.4.1.15 x_axis (inherited)

Definition

```
string x_axis = "bottom"
```

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.4.1.16 x_axis_formatter (inherited)

Definition

```
string x_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)
[EJSC.NumberFormatter](#)

5.4.4.1.17 `y_axis` (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.4.1.18 `y_axis_formatter` (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)
[EJSC.NumberFormatter](#)

5.4.4.2 Methods

5.4.4.2.1 `findClosestPoint` (inherited)

Definition

[EJSC.Point](#) **findClosestPoint**(integer pixel)

Description

Returns the point object closest to the pixel coordinate given or null if no points are found.

5.4.4.2.2 `getDataHandler` (inherited)

Definition

EJSC.DataHandler **getDataHandler**()

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.4.2.3 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.4.2.4 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.4.2.5 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.4.2.6 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base Series class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.4.2.7 setColor (inherited)

Definition

```
void setColor( string color )
```

Description

Changes the series color and causes the chart to redraw.

5.4.4.2.8 setColoredLegend (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.4.2.9 setDataHandler (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.4.2.10 setLineOpacity (inherited)

Definition

```
void setLineOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.lineOpacity](#) property and redraws the series to reflect the change.

5.4.4.2.11 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.4.2.12 setOpacity (inherited)

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.4.2.13 setTitle (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.4.2.14 show (inherited)

Definition

void **show**()

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.4.2.15 showLegend (inherited)

Definition

void **showLegend**()

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.4.3 Events

5.4.4.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable**([EJSC.Chart](#) chart, [EJSC.Series](#) series)

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.4.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.4.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.4.3.4 onShowHint (inherited)

Definition

string **onShowHint**([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.4.4 Data Formats

[XML](#) ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
    <plot>
        <point x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
```

```

        <point x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
    </plot>
<graph>
```

Short:

```

<G>
    <L>
        <P x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
            <P x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
        </L>
    </G>
```

Compact: The values parameter is formatted as CSV

```

<G>
    <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```

[
    ["x", "high", "low", "open", "close", "label", "userdata"],
    ["x", "high", "low", "open", "close", "label", "userdata"]
]
```

Null should be used to skip unused parameters:

```

[
    ["x", null, null, "open", "close", null, "userdata"],
    ["x", null, null, "open", "close", null, "userdata"]
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|high|low|open|close|label|userdata,x|high|low|open|close|label|userdata"

Null should be used to skip unused parameters

"x|null|null|open|close|null|userdata,x|null|null|open|close|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```

[ {
    "x": "number or string", "high": "number", "low": "number",
```

```

"open": "number", "close": "number", "label": "string", "userdata": "string" },
      {"x": "number or string", "high": "number", "low": "number",
"open": "number", "close": "number", "label": "string", "userdata": "string" }
]

```

5.4.4.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[high]	The preformatted high value of the point
[low]	The preformatted low value of the point
[open]	The preformatted open value of the point
[close]	The preformatted close value of the point
[label]	The label property of the current point

5.4.5 EJSC.FloatingBarSeries

FloatingBarSeries renders its points as vertical or horizontal bars which are not fixed to a baseline.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.FloatingBarSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.FloatingBarSeries(
  new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
  { title: "New Floating Bar Series" }
);
```

Defining Properties and Events

FloatingBarSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.FloatingBarSeries(new
EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]));
mySeries.lineWidth = 1;
mySeries.title = "New Floating Bar Series";
```

Setting properties in batch

```
var mySeries = new EJSC.FloatingBarSeries(
  new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
```

```
    { lineWidth: 1, title: "New Floating Bar Series" }  
);
```

5.4.5.1 Properties

5.4.5.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.5.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.5.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.5.1.4 defaultColors (inherited)

Definition

array **defaultColors** = [EJSC.DefaultBarColors](#)

Description

Defines the pool of default colors available for bar series bars.

NOTE: To make use of individually colored bars, the [EJSC.BarSeries.useColorArray](#) property must be set to true.

5.4.5.1.5 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.5.1.6 groupedBars (inherited)

Definition

boolean **groupedBars** = true

Description

Defines whether the bars from different bar series in a single chart are grouped or overlayed.

NOTE: Only the first bar series added to the chart may use this property to affect the grouped/overlay display. To change the style after the first bar series has been added, use the [EJSC.BarSeries.setGroupedBars](#) from any bar series in the chart. Currently you cannot mix both overlayed and grouped bars within the same chart.

Example

>> Make the bar series overlay

```
var chart = new EJSC.Chart("chart");
var bar1 = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        groupedBars: false,
    }
));
var bar2 = chart.addSeries(new EJSC.BarSeries(data));
```

5.4.5.1.7 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:
</strong>[y]"
}
);
```

5.4.5.1.8 intervalOffset (inherited)

Definition

float **intervalOffset** = 0.8

Description

Defines the spacing between the bars as a percentage of 1. 1 = bars take up the entire width available, with their sides touching.

Example

>> Make the bars take up 1/2 their available width. (i.e. more space between bars than by default)

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        intervalOffset: 0.5
    }
));
```

5.4.5.1.9 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.5.1.10 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.5.1.11 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.5.1.12 opacity (inherited)

Definition

integer **opacity** = 50

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.5.1.13 orientation (inherited)

Definition

string **orientation** = "vertical"

Description

This property determines the orientation of the bar series. The supported property values are "vertical" and "horizontal".

Note: Currently this is a creation-time only property and should not be changed after the series has been created.

5.4.5.1.14 ranges (inherited)

Definition

```
array ranges = new Array()
```

Description

This property is used to store the ranges for a given bar series. The range objects are used to draw bars in varying styles based on their Y value.

The range objects stored are defined as:

```
range = {
    min:      float, // >=
    max:      float, // <
    color:    string, // Defined as rgb(RED,GREEN,BLUE), ex: "rgb(255,0,0)"
    opacity:   integer, // Represents percent, i.e. 50 = 50%
    lineOpacity: integer, // Represents percent, i.e. 50 = 50%
    lineWidth: integer // Represents the line width in pixels
}
```

Example

>> Define ranges so that bars with a Y value from 0 to 10 and 90 to 100 are colored red, bars 10 - 90 are colored green

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        ranges: [
            { 0, 10, "rgb(255,0,0)", 100, 100, 1 },
            { 90, 100, "rgb(255,0,0)", 100, 100, 1 },
            { 10, 90, "rgb(0,255,0)", 100, 100, 1 }
        ]
    }
));
```

5.4.5.1.15 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.5.1.16 treeLegend (inherited)

Definition

boolean **treeLegend** = false

Description

Defines whether to display each bar individually in the legend.

If the [useColorArray](#) property is true and treeLegend left at its default (not defined in options), the treeLegend property will automatically be set to true to enable tree-style legend display.

5.4.5.1.17 useColorArray (inherited)

Definition

boolean **useColorArray** = false

Description

Defines whether to make use of the [EJSC.BarSeries.defaultColors](#) property

Example

>> Use the color array to make a chart of multi colored bars

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        useColorArray: true
    }
));
```

5.4.5.1.18 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.5.1.19 x_axis (inherited)

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.5.1.20 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.5.1.21 y_axis (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.5.1.22 y_axis_formatter (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.5.2 Methods

5.4.5.2.1 addRange (inherited)

Definition

void **addRange**(float min, float max, string color, integer opacity, integer lineOpacity, integer lineWidth, boolean redraw)

Description

Adds a new range to the bar series and optionally triggers a redraw.

5.4.5.2.2 clearRanges (inherited)

Definition

```
void clearRanges( boolean redraw )
```

Description

Clears all ranges defined for the series and optionally redraws the chart.

5.4.5.2.3 deleteRange (inherited)

Definition

```
void deleteRange( float min, float max, boolean redraw )
```

Description

Deletes the matching range (min and max must exactly match an existing range) and optionally redraws the chart.

5.4.5.2.4 getBarSize (inherited)

Definition

```
integer getBarSize()
```

Description

This method returns the size in pixels (width or height depending on orientation) of a single bar.

5.4.5.2.5 getDataHandler (inherited)

Definition

```
EJSC.DataHandler getDataHandler( )
```

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.5.2.6 getPoints (inherited)

Definition

```
array getPoints()
```

Description

This method returns an array of all [EJSC.BarPoint](#) objects in the series.

5.4.5.2.7 `getVisibility` (inherited)

Enter topic text here.

5.4.5.2.8 `hide` (inherited)**Definition**

```
void hide( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.5.2.9 `hideLegend` (inherited)**Definition**

```
void hideLegend( )
```

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.5.2.10 `reload` (inherited)**Definition**

```
void reload( )
```

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base Series class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.5.2.11 `setColor` (inherited)**Definition**

```
void setColor( string color )
```

Description

Changes the series color and causes the chart to redraw.

5.4.5.2.12 setColoredLegend (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.5.2.13 setDataHandler (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.5.2.14 setDefaultColors (inherited)

Definition

```
void setDefaultColors( array colors, boolean reload )
```

Description

Set the array of default colors available for bar series bars.

If reload = **true** the bars (if loaded) will pull their colors from the given color array and the chart will be redrawn.

If [onBarNeedsColor](#) is assigned, this method will ignore that event and load the colors from the array.

Example

```
var colors = [
    "rgb('0,0,0')",           // black
    "rgb(255,0,0)",           // red
    "rgb("0,255,0)",          // green
    "rgb("0,0,255)",          // blue
    "rgb("255,255,255)"      // white
];
myBarSeries.setDefaultColors(colors, true);
```

5.4.5.2.15 getGroupedBars (inherited)

Enter topic text here.

5.4.5.2.16 setIntervalOffset (inherited)

Definition

void **setIntervalOffset**(float offset, boolean redraw)

Description

Updates the interval offset property (spacing between the bars) and optionally redraws the chart. See [EJSC.BarSeries.intervalOffset](#) for additional information.

5.4.5.2.17 setLineWidth (inherited)

Definition

void **setLineWidth**(integer width)

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.5.2.18 setOpacity (inherited)

Definition

void **setOpacity**(integer opacity)

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.5.2.19 setTitle (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.5.2.20 show (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.5.2.21 showLegend (inherited)

Definition

```
void showLegend( )
```

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.5.3 Events

5.4.5.3.1 onAfterDataAvailable (inherited)

Definition

```
boolean onAfterDataAvailable( EJSC.Chart chart, EJSC.Series series )
```

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.5.3.2 onAfterVisibilityChange (inherited)

Definition

```
boolean onAfterVisibilityChange( EJSC.Series series, EJSC.Chart chart, boolean visible )
```

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.5.3.3 onBarNeedsColor (inherited)

Definition

```
string onBarNeedsColor( EJSC.BarPoint point, EJSC.Series series, EJSC.Chart chart )
object onBarNeedsColor( EJSC.BarPoint point, EJSC.Series series, EJSC.Chart chart )
```

Description

Fired when a bar needs a color. This event may return either a string (i.e. "rgb(0,255,0)") or an object with additional styling properties.

The object returned is expected to be formatted as:

```
{
    color:      string,
    opacity:    integer,
    lineOpacity: integer,
    lineWidth:  integer
}
```

Example

>> Display bars with userdata of "bold" with thicker lines

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        lineOpacity: 80,
        lineWidth: 1,
        onBarNeedsColor: function(point, series, chart) {

            if (point.userdata == "bold") {
                return {
                    color: "rgb(0,0,0)",
                    opacity: 100,
                    lineOpacity: 100,
                    lineWidth: 100
                };
            } else {
                return "rgb(128,128,128)";
            }
        }
    }
));
```

5.4.5.3.4 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.5.3.5 onShowHint (inherited)

Definition

```
string onShowHint( EJSC.Point point, EJSC.Series series, EJSC.Chart chart, string hint_string )
```

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.5.4 Data Formats

[XML](#) ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```

Orientation == "vertical"

<graph>
    <plot>
        <point x="number or string" min="number" max="number"
label="string" userdata="string"/>
        <point x="number or string" min="number" max="number"
label="string" userdata="string"/>
    </plot>
<graph>

Orientation == "horizontal"

<graph>
    <plot>
        <point y="number or string" min="number" max="number"
label="string" userdata="string"/>
        <point y="number or string" min="number" max="number"
label="string" userdata="string"/>
    </plot>
<graph>
```

Short:

```

Orientation == "vertical"

<G>
    <L>
        <P x="number or string" min="number" max="number"
label="string" userdata="string"/>
        <P x="number or string" min="number" max="number"
label="string" userdata="string"/>
    </L>
```

```

<G>

  Orientation == "horizontal"

  <G>
    <L>
      <P x="number or string" min="number" max="number"
label="string" userdata="string"/>
      <P x="number or string" min="number" max="number"
label="string" userdata="string"/>
    </L>
  <G>

```

Compact: The values parameter is formatted as CSV

```

<G>
  <L values="CSV string"/>
</G>

```

Array ([EJSC.ArrayDataHandler](#)):

```

[
  ["x or y", "min", "max", "label", "userdata"],
  ["x or y", "min", "max", "label", "userdata"]
]

```

Null should be used to skip unused parameters:

```

[
  ["x or y", min, max, null, "userdata"],
  ["x or y", min, max, null, "userdata"]
]

```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x or y|min|max|label|userdata,x or y|min|max||label|userdata"

Null should be used to skip unused parameters

"x or y|min|max|null|userdata,x or y|min|max|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

Orientation == "vertical"

```

[
  {"y":"number or string", "min":"number", "max":"number",
label:"string","userdata":"string"},
```

```

        {"y":"number or string", "min":"number", "max":"number",
label:"string", "userdata":"string"}
    ]
}

```

Orientation == "horizontal"

```

[
    {"x":"number or string", "min":"number", "max":"number",
label:"string", "userdata":"string"},
    {"x":"number or string", "min":"number", "max":"number",
label:"string", "userdata":"string"}
]
}

```

5.4.5.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[label]	The label property of the current point
[min]	The preformatted min value of the current point
[max]	The preformatted max value of the currnt point

5.4.6 EJSC.FunctionSeries

The FunctionSeries is rendered as a line based on the results of the function specified.

The constructor expects a function which can be called as `function(x)`, and an optional set of object properties.

Constructor

```
EJSC.FunctionSeries( function fn [, object options] )
```

Example

```
var mySeries = new EJSC.FunctionSeries(
    Math.cos,
    { title: "New Function Series" }
);
```

Defining Properties and Events

FunctionSeries properties may be set individually after the series has been created or in batch using the `options` parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.FunctionSeries(Math.cos);
```

```
mySeries.lineWidth = 2;  
mySeries.title = "New Function Series";
```

Setting properties in batch

```
var mySeries = new EJSC.FunctionSeries(  
    Math.cos,  
    { lineWidth: 2, title: "New Function Series" }  
)
```

5.4.6.1 Properties

5.4.6.1.1 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.6.1.2 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.6.1.3 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:
</strong>[y]"
});
);
```

5.4.6.1.4 legendIsVisible (inherited)

Definition

```
boolean legendIsVisible = true
```

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.6.1.5 lineOpacity (inherited)

Definition

```
integer lineOpacity = 100
```

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.6.1.6 lineWidth (inherited)

Definition

```
integer lineWidth = 1
```

Description

Defines the width of the line connecting series points.

5.4.6.1.7 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.6.1.8 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.6.1.9 x_axis (inherited)

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.6.1.10 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.6.1.11 y_axis (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.6.1.12 y_axis_formatter (inherited)

Definition

```
string y_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.6.2 Methods

5.4.6.2.1 `getVisibility` (inherited)

Definition

```
boolean getVisibility()
```

Description

Returns a boolean indicating the series current visible state

5.4.6.2.2 `hide` (inherited)

Definition

```
void hide()
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.6.2.3 `hideLegend` (inherited)

Definition

```
void hideLegend()
```

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.6.2.4 `reload` (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base `Series` class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.6.2.5 `setColor` (inherited)

Definition

void **setColor**(string color)

Description

Changes the series color and causes the chart to redraw.

5.4.6.2.6 `setColoredLegend` (inherited)

Definition

void **setColoredLegend**(boolean coloredLegend)

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.6.2.7 `setLineWidth` (inherited)

Definition

void **setLineWidth**(integer width)

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.6.2.8 `setTitle` (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.6.2.9 show (inherited)

Definition

void **show()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.6.2.10 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.6.3 Events

5.4.6.3.1 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.6.3.2 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart)**

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.6.3.3 onShowHint (inherited)

Definition

```
string onShowHint( EJSC.Point point, EJSC.Series series, EJSC.Chart chart, string hint_string )
```

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.6.4 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[label]	The label property of the current point

5.4.7 EJSC.LineSeries

LineSeries is rendered by drawing a line from point to point.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.LineSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.LineSeries(
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
    { title: "New Line Series" }
);
```

Defining Properties and Events

LineSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.LineSeries(new
EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]));
mySeries.lineWidth = 2;
```

```
mySeries.title = "New Line Series";
```

Setting properties in batch

```
var mySeries = new EJSC.LineSeries(  
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),  
    { lineWidth: 2, title: "New Line Series" }  
);
```

5.4.7.1 Properties

5.4.7.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.7.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.7.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.7.1.4 drawPoints

Definition

boolean **drawPoints** = false

Description

Determines whether the individual points in the series are visually indicated by round dots on the chart. The size and color of the fill and border are determined by the [pointColor](#), [pointSize](#), [pointBorderColor](#) and [pointBorderSize](#) properties.

Note: Setting this property to true for series which have a large number of points may impact performance as additional draws are required to render the points.

5.4.7.1.5 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:
</strong>[y]"
});
);
```

5.4.7.1.6 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.7.1.7 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.7.1.8 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.7.1.9 pointBorderColor

Definition

string **pointBorderColor** = "rgb(255,255,255)"

Description

Defines the color of the border drawn around the points. This property is only applicable when the series [drawPoints](#) property is set to true and [pointBorderSize](#) is greater than 0.

5.4.7.1.10 pointBorderSize

Definition

integer **pointBorderSize** = 0

Description

Defines the size in pixels of the border drawn around the points. This property is only applicable when the series [drawPoints](#) property is set to true.

To draw points without any border, leave pointBorderSize set to 0.

5.4.7.1.11 pointColor

Definition

string **pointColor** = undefined

Description

Defines the color of the point (circle) drawn at each data point in the series. If left undefined the point will

inherit the series color.

This property is only applicable when the series [drawPoints](#) property is set to true.

5.4.7.1.12 pointSize

Definition

integer **pointSize** = undefined

Description

Defines the size of the point (circle) drawn at each data point in the series. If left undefined the point diameter will be twice the line width of the series.

This property is only applicable when the series [drawPoints](#) property is set to true.

5.4.7.1.13 title (inherited)

Definition

string **title** = "Series <index>"

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.7.1.14 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.7.1.15 x_axis (inherited)

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.7.1.16 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.7.1.17 y_axis (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.7.1.18 y_axis_formatter (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.7.2 Methods

Enter topic text here.

5.4.7.2.1 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler()**

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.7.2.2 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.7.2.3 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.7.2.4 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.7.2.5 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.4.7.2.6 setColor (inherited)

Definition

```
void setColor( string color )
```

Description

Changes the series color and causes the chart to redraw.

5.4.7.2.7 setColoredLegend (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.7.2.8 setDataHandler (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.7.2.9 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.7.2.10 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.7.2.11 show (inherited)

Definition

void **show()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.7.2.12 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.7.3 Events

Enter topic text here.

5.4.7.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable(EJSC.Chart chart, EJSC.Series series)**

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.7.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange(EJSC.Series series, EJSC.Chart chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.7.3.3 onBeforeVisibilityChange (inherited)

Definition

```
boolean onBeforeVisibilityChange( EJSC.Series series, EJSC.Chart chart )
```

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.7.3.4 onShowHint (inherited)

Definition

```
string onShowHint( EJSC.Point point, EJSC.Series series, EJSC.Chart chart, string hint_string )
```

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.7.4 Data Formats

The x and y parameters are required, label and userdata are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
  <plot>
    <point x="number or string" y="number or string" label="string"
userdata="string"/>
    <point x="number or string" y="number or string" label="string"
userdata="string"/>
  </plot>
<graph>
```

Short:

```
<G>
  <L>
    <P x="number or string" y="number or string" label="string"
userdata="string"/>
    <P x="number or string" y="number or string" label="string"
userdata="string"/>
```

```
</L>
</G>
```

Compact: The values parameter is formatted as CSV

```
<G>
  <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```
[
  [
    ["x", "y", "label", "userdata"],
    ["x", "y", "label", "userdata"]
]
```

Null should be used to skip unused parameters:

```
[
  [
    ["x", "y", null, "userdata"],
    ["x", "y", null, "userdata"]
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|y|label|userdata,x|y|label|userdata"

Null should be used to skip unused parameters

"x|y|null|userdata,x|y|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[
  [
    {"x": "number or string", "y": "number or
string", "label": "string", "userdata": "string"},
    {"x": "number or string", "y": "number or
string", "label": "string", "userdata": "string"}
  ]
]
```

5.4.7.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point

[label]	The label property of the current point
---------	---

5.4.8 EJSC.OpenHighLowCloseSeries

In order to use the OpenHighLowCloseSeries, the file EJSChart_Stock.js must be included in the HTML page after the inclusion of the standard EJSChart.js file.

```
<head>
    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>
    <script type="text/javascript" src="/EJSChart/EJSChart_Stock.js"></script>
</head>
```

OpenHighLowCloseSeries renders its point data as vertical lines with optional horizontal "wicks" to express open and close values.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.OpenHighLowCloseSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.OpenHighLowCloseSeries(
    new EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,19]]),
    { title: "New OpenHighLowClose Series" }
);
```

Defining Properties and Events


OpenHighLowCloseSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.OpenHighLowCloseSeries(new
EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,19]]));
mySeries.lineWidth = 1;
mySeries.title = "New OpenHighLowClose Series";
```

Setting properties in batch

```
var mySeries = new EJSC.OpenHighLowCloseSeries(
    new EJSC.ArrayDataHandler([[1,10,1,2,9],[2,20,7,10,19]]),
    { lineWidth: 1, title: "New OpenHighLowClose Series" }
);
```



5.4.8.1 Properties

5.4.8.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.8.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.8.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.8.1.4 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.8.1.5 gain

Definition

```
object gain = {  
    lineColor: "rgb(151,183,247)",  
    lineOpacity: 100  
}
```

Description

Defines the appearance of the points which represent a gain.

Example

```
var series = new EJSC.OpenHighLowCloseSeries(new EJSC.DataHandler(),  
{  
    gain {  
        lineColor: "#006600",  
        lineOpacity: 50  
    }  
});
```



5.4.8.1.6 hint_string (inherited)

Definition

```
string hint_string = undefined
```

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:</strong>[y]"
});

```

5.4.8.1.7 intervalOffset

Definition

```
float intervalOffset = 0.8
```

Description


Defines the spacing between the points as a percentage of 1. 1 = points take up the entire width available, with their edges touching.

Example

```
var chart = new EJSC.Chart("chart");
var series = chart.addSeries(new EJSC.OpenHighLowCloseSeries(
    data,
```

```
{  
    intervalOffset: 1  
}  
});
```

Emprise JavaScript Charts



5.4.8.1.8 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.8.1.9 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.8.1.10 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.8.1.11 loss

Definition


```
object loss = {
    lineColor: "rgb(249,95,95)",
    lineOpacity: 100
}
```

Description

Defines the appearance of the points which represent a loss.

Example

```
var series = new EJSC.OpenHighLowCloseSeries(new EJSC.DataHandler(),
{
    loss {
        lineColor: "#996600",
        lineOpacity: 50
    }
});
```

Emprise JavaScript Charts

5.4.8.1.12 opacity (inherited)

Definition

```
integer opacity = 50
```

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.8.1.13 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.8.1.14 visible (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.8.1.15 x_axis (inherited)

Definition

```
string x_axis = "bottom"
```

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.8.1.16 x_axis_formatter (inherited)

Definition

```
string x_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.8.1.17 y_axis (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.8.1.18 y_axis_formatter (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.8.2 Methods

5.4.8.2.1 findClosestPoint (inherited)

Definition

[EJSC.Point](#) **findClosestPoint**(integer pixel)

Description

Returns the point object closest to the pixel coordinate given or null if no points are found.

5.4.8.2.2 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler**()

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.8.2.3 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.8.2.4 **hide** (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.8.2.5 **hideLegend** (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.8.2.6 **reload** (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.4.8.2.7 **setColor** (inherited)

Definition

void **setColor(string color)**

Description

Changes the series color and causes the chart to redraw.

5.4.8.2.8 setColoredLegend (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.8.2.9 setDataHandler (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.8.2.10 setLineOpacity (inherited)

Definition

```
void setLineOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.lineOpacity](#) property and redraws the series to reflect the change.

5.4.8.2.11 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.8.2.12 setOpacity (inherited)

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.8.2.13 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.8.2.14 show (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.8.2.15 showLegend (inherited)

Definition

```
void showLegend( )
```

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.8.3 Events

5.4.8.3.1 onAfterDataAvailable (inherited)

Definition

```
boolean onAfterDataAvailable( EJSC.Chart chart, EJSC.Series series )
```

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.8.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.8.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.8.3.4 onShowHint (inherited)

Definition

string **onShowHint**([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.8.4 Data Formats

[XML \(EJSC.XMLDataHandler, EJSC.XMLStringDataHandler\):](#)

Unused parameters may be omitted

Full:

```
<graph>
  <plot>
    <point x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
    <point x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
```

```
</plot>
<graph>
```

Short:

```
<G>
  <L>
    <P x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
    <P x="number or string" high="number" low="number"
open="number" close="number" label="string" userdata="string"/>
  </L>
</G>
```

Compact: The values parameter is formatted as CSV

```
<G>
  <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```
[  
  ["x", "high", "low", "open", "close", "label", "userdata"],  
  ["x", "high", "low", "open", "close", "label", "userdata"]  
]
```

Null should be used to skip unused parameters:

```
[  
  ["x", null, null, "open", "close", null, "userdata"],  
  ["x", null, null, "open", "close", null, "userdata"]  
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

```
"x|high|low|open|close|label|userdata,x|high|low|open|close|label|userdata"
```

Null should be used to skip unused parameters

```
"x|null|null|open|close|null|userdata,x|null|null|open|close|null|userdata"
```

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[  
  {"x":"number or string", "high":"number", "low":"number",
"open":"number", "close":"number", "label":"string","userdata":"string"},  
  {"x":"number or string", "high":"number", "low":"number",
```

```
"open": "number", "close": "number", "label": "string", "userdata": "string"}  
]
```

5.4.8.5 Text Replacement Options (COPY)

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[high]	The preformatted high value of the point
[low]	The preformatted low value of the point
[open]	The preformatted open value of the point
[close]	The preformatted close value of the point
[label]	The label property of the current point

5.4.9 EJSC.PieSeries

PieSeries is rendered by drawing slices to form an ellipse. Each slice represents a percentage of the total of the sum of all point values in the dataset.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.PieSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.PieSeries(  
    new EJSC.ArrayDataHandler([[10,"Label 1"],[20,"Label 2"],[120,"Label3"]]),  
    { title: "New Pie Series" }  
>;
```

Defining Properties and Events

PieSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.PieSeries(new EJSC.ArrayDataHandler([[10,"Label  
1"],[20,"Label 2"],[120,"Label 3"]]);  
mySeries.title = "New Pie Series";
```

Setting properties in batch

```
var mySeries = new EJSC.PieSeries(  
    ArrayDataHandler([[10,"Label 1"],[20,"Label 2"],[120,"Label 3"]]),  
    { title: "New Pie Series" }  
>;
```

5.4.9.1 Properties

5.4.9.1.1 defaultColors

Definition

array **defaultColors** = [EJSC.DefaultPieColors](#)

Description

Defines the pool of default colors available for pie pieces.

5.4.9.1.2 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.9.1.3 height

Definition

string **height** = "100%"

Description

Defines the total height of the pie series. This may be specified in percent of the chart as shown above as the default value, or in exact pixels by specifying a number (i.e. height = 150).

5.4.9.1.4 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:</strong>[y]"
}
);
```

5.4.9.1.5 **legendIsVisible** (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.9.1.6 **lineOpacity** (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.9.1.7 **lineWidth** (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.9.1.8 **opacity** (inherited)

Definition

integer **opacity** = 50

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.9.1.9 position

Definition

```
string position = "center"
```

Description

Defines the quadrant of the chart that the pie will appear in.

Quadrants:

- topLeft
- topCenter
- topRight
- leftCenter
- center
- rightCenter
- bottomLeft
- bottomCenter
- bottomRight

5.4.9.1.10 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.9.1.11 total_value

Definition

```
integer total_value = undefined
```

Description

Defines the total value (sum) of all pie pieces in the series. If left undefined, this value will be calculated automatically by adding all the piece values when the series data is loaded.

This property is only applicable during series creation. To determine or modify the total value once the series has been created use the [getTotalValue](#) and [setTotalValue](#) methods.

To force the chart to recalculate the total value based on actual series data, use the [resetTotalValue](#) method.

5.4.9.1.12 treeLegend

Definition

boolean **treeLegend** = true

Description

Defines whether to display each pie piece individually in the legend.

5.4.9.1.13 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.9.1.14 width

Definition

string **width** = "100%"

Description

Defines the total width of the pie series. This may be specified in percent of the chart as shown above as the default value, or in exact pixels by specifying a number (i.e. width = 150).

5.4.9.1.15 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.9.2 Methods

5.4.9.2.1 findCenter

Definition

object **findCenter**([EJSC.PiePoint](#) point)

The object returned is formatted as:

```
{  
    x: integer,  
    y: integer  
}
```

Description

This method takes a pie point (see [getPoints](#)) and returns an object containing the x and y screen coordinates of the piece's center.

5.4.9.2.2 findCenterOfCurve

Definition

object **findCenterOfCurve**([EJSC.PiePoint](#) point)

The object returned is formatted as:

```
{  
    x: integer,  
    y: integer  
}
```

Description

This method takes a pie point (see [getPoints](#)) and returns an object containing the x and y screen coordinates of the center of the piece's arc.

5.4.9.2.3 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler**()

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.9.2.4 getPoints

Definition

array **getPoints**()

Description

This method returns an array of all [EJSC.PiePoint](#) objects in the series.

5.4.9.2.5 getTotalValue

Definition

integer **getTotalValue()**

Description

Returns the current total value of the pie series. If the total_value property was set during creation or the setTotalValue has been called, the static value will be returned. If the series is set to calculate the total value based on the series data, the dynamic value will be returned.

5.4.9.2.6 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.9.2.7 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.9.2.8 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.9.2.9 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base `Series` class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.9.2.10 `resetTotalValue`

Definition

void **resetTotalValue**(boolean redraw)

Description

This method causes the series to recalculate its total value based on the actual series data and optionally redraws the series to reflect the change.

To retrieve the total value after this method is called, use [getTotalValue](#).

5.4.9.2.11 `setDataHandler` (inherited)

Definition

void **setDataHandler**([EJSC.DataHandler](#) dataHandler, boolean reload)

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.9.2.12 `setDefaultColors`

Definition

void **setDefaultColors**(array colors, boolean reload)

Description

Set the array of default colors available for pie pieces.

If `reload = true` the pie pieces (if loaded) will pull their colors from the given color array and the chart will be redrawn.

If [onPieceNeedsColor](#) is assigned, this method will ignore that event and load the colors from the array.

Example

```
var colors = [
    "rgb('0,0,0')",           // black
    "rgb(255,0,0)",          // red
```

```
    "rgb("0,255,0)",           // green
    "rgb("0,0,255)",           // blue
    "rgb("255,255,255)"       // white
];
myPieSeries.setDefaultColors(colors, true);
```

5.4.9.2.13 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.9.2.14 setOpacity (inherited)

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.9.2.15 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.9.2.16 setTotalValue

Definition

```
void setTotalValue( integer value, boolean redraw )
```

Description

Sets the total value of the pie series and optionally redraws the series to reflect the change.

To force the chart to calculate its total value based on the actual series data, call [resetTotalValue](#).

5.4.9.2.17 show (inherited)

Definition

void **show()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.9.2.18 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.9.3 Events

5.4.9.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable([EJSC.Chart](#) chart, [EJSC.Series](#) series)**

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.9.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.9.3.3 onBeforeVisibilityChange (inherited)

Definition

```
boolean onBeforeVisibilityChange( EJSC.Series series, EJSC.Chart chart )
```

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.9.3.4 onPieceNeedsColor

Definition

```
boolean onPieceNeedsColor( EJSC.PiePoint point, EJSC.PieSeries series, EJSC.Chart chart )
```

Description

If assigned, this event is triggered for each piece in a pie series immediately before it pulls a color from the default colors array. The event provides the [EJSC.PiePoint](#) object which represents the piece which needs a color, the [EJSC.PieSeries](#) which owns the piece and the [EJSC.Chart](#) which owns the series. Return a color string formatted as "rgb(<red value>, <green value>, <blue value>)", i.e. Orange would be "rgb(237,173,0)"

5.4.9.3.5 onShowHint (inherited)

Definition

```
string onShowHint( EJSC.Point point, EJSC.Series series, EJSC.Chart chart, string hint_string )
```

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.9.4 Data Formats

The x parameter is required, label and userdata are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
  <plot>
    <point x="number or string" label="string" userdata="string"/>
    <point x="number or string" label="string" userdata="string"/>
```

```
</plot>
<graph>
```

Short:

```
<G>
  <L>
    <P x="number or string" label="string" userdata="string"/>
    <P x="number or string" label="string" userdata="string"/>
  </L>
</G>
```

Compact: The values parameter is formatted as CSV

```
<G>
  <L values="CSV string"/>
</G>
```

Array ([EJSC.ArrayDataHandler](#)):

```
[  
  ["x", "label", "userdata"],  
  ["x", "label", "userdata"]  
]
```

Null should be used to skip unused parameters:

```
[  
  ["x", null, "userdata"],  
  ["x", null, "userdata"]  
]
```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|label|userdata,x|label|userdata"

Null should be used to skip unused parameters

"x|null|userdata,x|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```
[  
  {"x": "number or string", "label": "string", "userdata": "string"},  
  {"x": "number or string", "label": "string", "userdata": "string"}  
]
```

5.4.9.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[x]	The preformatted value of the point
[total]	The total value represented by the sum of all piece values
[percent]	The percent of the total value the current point represents
[label]	The label property of the current point

5.4.10 EJSC.ScatterSeries

ScatterSeries is rendered by drawing a styled point for each x,y coordinate in the dataset.

The constructor expects an instantiated [EJSC.DataHandler](#) descendant and an optional set of object properties.

Constructor

```
EJSC.ScatterSeries( EJSC.DataHandler dataHandler [, object options] )
```

Example

```
var mySeries = new EJSC.ScatterSeries(
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
    { title: "New Scatter Series" }
);
```

Defining Properties and Events

ScatterSeries properties may be set individually after the series has been created or in batch using the options parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.ScatterSeries(new
EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]));
mySeries.pointSize = 3;
mySeries.pointStyle = "diamond";
mySeries.title = "New Scatter Series";
```

Setting properties in batch

```
var mySeries = new EJSC.ScatterSeries(
    new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,3],[5,2],[6,4]]),
    { pointSize: 3, pointStyle: "diamond", title: "New Scatter Series" }
);
```

5.4.10.1 Properties

5.4.10.1.1 autosort (inherited)

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.4.10.1.2 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.10.1.3 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.10.1.4 delayLoad (inherited)

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a

chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.4.10.1.5 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> *Modify the default hint to include custom text.*

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:
</strong>[y]"
});
);
```

5.4.10.1.6 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.10.1.7 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.10.1.8 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.10.1.9 opacity (inherited)

Definition

integer **opacity** = 50

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.4.10.1.10 pointSize

Definition

integer **pointSize** = 4

Description

Defines the size of the point to be drawn. Point size has no effect on point selection. In order to increase the distance from the actual coordinate that a click will select or hover a point, see [EJSC.Chart.proximity_snap](#)

5.4.10.1.11 pointStyle

Definition

string **pointStyle** = "triangle"

Styles:

- triangle
- box
- circle
- diamond

Description

Defines the shape of the point to be drawn. Point shape has no effect on point selection. In order to increase the distance from the actual coordinate that a click will select or hover a point, see [EJSC.Chart.proximity_snap](#)

5.4.10.1.12 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.10.1.13 `visible` (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.10.1.14 `x_axis` (inherited)

Definition

```
string x_axis = "bottom"
```

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.10.1.15 `x_axis_formatter` (inherited)

Definition

```
string x_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.10.1.16 `y_axis` (inherited)

Definition

```
string y_axis = "left"
```

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.10.1.17 `y_axis_formatter` (inherited)

Definition

string `y_axis_formatter` = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.10.2 Methods

5.4.10.2.1 `getDataHandler` (inherited)

Definition

EJSC.DataHandler `getDataHandler()`

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.4.10.2.2 `getVisibility` (inherited)

Definition

boolean `getVisibility()`

Description

Returns a boolean indicating the series current visible state

5.4.10.2.3 `hide` (inherited)

Definition

void `hide()`

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.10.2.4 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.10.2.5 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.4.10.2.6 setColor (inherited)

Definition

void **setColor(string color)**

Description

Changes the series color and causes the chart to redraw.

5.4.10.2.7 setColoredLegend (inherited)

Definition

void **setColoredLegend(boolean coloredLegend)**

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.10.2.8 setDataHandler (inherited)

Definition

void **setDataHandler([EJSC.DataHandler](#) dataHandler, boolean reload)**

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.4.10.2.9 `setLineWidth` (inherited)

Definition

`void setLineWidth(integer width)`

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.10.2.10 `setOpacity` (inherited)

Definition

`void setOpacity(integer opacity)`

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.4.10.2.11 `setPointStyle`

Definition

`void setPointStyle(integer size, string style)`

Description

Updates the [pointSize](#) and/or [pointStyle](#) and redraws the chart. Size or style update may be avoided by sending undefined.

See [EJSC.ScatterSeries.pointStyle](#) for a list of available styles.

Example

>> Update the size and style of scatter series points

```
mySeries.setPointStyle( 5, "diamond" );
```

>> Update only the style of scatter series points

```
mySeries.setPointStyle( undefined, "box" );
```

5.4.10.2.12 `setTitle` (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.10.2.13 show (inherited)

Definition

void **show**()

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.10.2.14 showLegend (inherited)

Definition

void **showLegend**()

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.10.3 Events

5.4.10.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable**([EJSC.Chart](#) chart, [EJSC.Series](#) series)

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.4.10.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.10.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.10.3.4 onShowHint (inherited)

Definition

string **onShowHint**([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.10.4 Data Formats

The x and y parameters are required, label and userdata are both optional.

XML ([EJSC.XMLDataHandler](#), [EJSC.XMLStringDataHandler](#)):

Unused parameters may be omitted

Full:

```
<graph>
    <plot>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
        <point x="number or string" y="number or string" label="string"
userdata="string"/>
    </plot>
<graph>
```

Short:

```

<G>
  <L>
    <P x="number or string" y="number or string" label="string"
      userdata="string"/>
    <P x="number or string" y="number or string" label="string"
      userdata="string"/>
  </L>
</G>

```

Compact: The values parameter is formatted as CSV

```

<G>
  <L values="CSV string"/>
</G>

```

Array ([EJSC.ArrayDataHandler](#)):

```

[
  ["x", "y", "label", "userdata"],
  ["x", "y", "label", "userdata"]
]

```

Null should be used to skip unused parameters:

```

[
  ["x", "y", null, "userdata"],
  ["x", "y", null, "userdata"]
]

```

CSV ([EJSC.CSVFileDataHandler](#), [EJSC.CSVStringDataHandler](#)):

"x|y|label|userdata,x|y|label|userdata"

Null should be used to skip unused parameters

"x|y|null|userdata,x|y|null|userdata"

JSON ([EJSC.JSONFileDataHandler](#), [EJSC.JSONStringDataHandler](#)):

Unused parameters may be omitted.

```

[
  {"x": "number or string", "y": "number or
  string", "label": "string", "userdata": "string"},
  {"x": "number or string", "y": "number or
  string", "label": "string", "userdata": "string"}
]

```

5.4.10.5 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[[label]]	The label property of the current point

5.4.11 EJSC.StackedBarSeries

Enter topic text here.

5.4.11.1 Properties

5.4.11.1.1 groupedBars (inherited)

Definition

boolean **groupedBars** = true

Description

Defines whether the bars from different bar series in a single chart are grouped or overlaid.

NOTE: Only the first bar series added to the chart may use this property to affect the grouped/overlay display. To change the style after the first bar series has been added, use the [EJSC.BarSeries.setGroupedBars](#) from any bar series in the chart. Currently you cannot mix both overlaid and grouped bars within the same chart.

Example

>> Make the bar series overlay

```
var chart = new EJSC.Chart("chart");
var bar1 = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        groupedBars: false,
    }
));
var bar2 = chart.addSeries(new EJSC.BarSeries(data));
```

5.4.11.1.2 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br /><strong>Y:
</strong>[y]"
}
);
```

5.4.11.1.3 intervalOffset (inherited)

Definition

float **intervalOffset** = 0.8

Description

Defines the spacing between the bars as a percentage of 1. 1 = bars take up the entire width available, with their sides touching.

Example

>> Make the bars take up 1/2 their available width. (i.e. more space between bars than by default)

```
var chart = new EJSC.Chart("chart");
var bar = chart.addSeries(new EJSC.BarSeries(
    data,
    {
        intervalOffset: 0.5
    }
));
```

5.4.11.1.4 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.11.1.5 title (inherited)

Definition

```
string title = "Series <index>"
```

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.11.1.6 orientation (inherited)

Definition

```
string orientation = "vertical"
```

Description

This property determines the orientation of the bar series. The supported property values are "vertical" and "horizontal".

Note: Currently this is a creation-time only property and should not be changed after the series has been created.

5.4.11.1.7 visible (inherited)

Definition

```
boolean visible = true
```

Description

Defines whether the series is visible and can draw on the chart

5.4.11.1.8 x_axis (inherited)

Definition

```
string x_axis = "bottom"
```

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.11.1.9 y_axis (inherited)

Definition

```
string y_axis = "left"
```

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.11.2 Methods

5.4.11.2.1 getBarSize (inherited)

Definition

integer **getBarSize()**

Description

This method returns the size in pixels (width or height depending on orientation) of a single bar.

5.4.11.2.2 addSeries

Definition

[EJSC.BarSeries](#) **addSeries(** [EJSC.BarSeries](#) series, boolean redraw **)**

Description

Adds a new series to the stacked bar series and returns the newly added series (this is useful when creating series inline as shown in the example below). The series must be a [EJSC.BarSeries](#) and have the same orientation as the stacked bar series being added to..

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the series to draw. The default, if redraw is omitted is **true**.

Note: If the series has not defined a title (i.e. Series.title = "") at the time addSeries is called, a default title of "Series <index>" will be assigned (where <index> is the current series index in internal series storage).

Example

>> Add new bar series to an existing stacked bar series.

```
var myChart = new EJSC.Chart("chart");
var myStackedSeries = myChart.addSeries(new EJSC.StackedBarSeries(data, { }));

var myBarSeries1 = myStackedSeries.addSeries(new EJSC.BarSeries(...));
var myBarSeries2 = myStackedSeries.addSeries(new EJSC.BarSeries(...));
var myBarSeries3 = myStackedSeries.addSeries(new EJSC.BarSeries(...));
var myBarSeries4 = myStackedSeries.addSeries(new EJSC.BarSeries(...));
var myBarSeries5 = myStackedSeries.addSeries(new EJSC.BarSeries(...));
```

5.4.11.2.3 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.4.11.2.4 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.11.2.5 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.11.2.6 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.4.11.2.7 removeSeries

Definition

void **removeSeries(EJSC.BarSeries series, boolean redraw)**

Description

Removes the specified series from the stacked bar series and triggers an immediate rescaling and redraw. Send in redraw = false if performing multiple removes and want to delay redrawing until complete.

5.4.11.2.8 setGroupedBars (inherited)

Definition

```
void setGroupedBars( boolean grouped, boolean redraw )
```

Description

Changes the chart between grouped and overlayed bars and optionally triggers a redraw.

5.4.11.2.9 setIntervalOffset (inherited)

Definition

```
void setIntervalOffset( float offset, boolean redraw )
```

Description

Updates the interval offset property (spacing between the bars) and optionally redraws the chart. See [EJSC.BarSeries.intervalOffset](#) for additional information.

5.4.11.2.10 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.11.2.11 show (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.11.2.12 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.11.3 Events

5.4.11.3.1 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.11.3.2 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart)**

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.11.3.3 onShowHint (inherited)

Definition

string **onShowHint([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)**

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.11.4 Text Replacement Options (COPY)

Enter topic text here.

5.4.12 EJSC.TrendSeries

The TrendSeries is rendered as a line based on the results of a function applied to the related series' data points.

The constructor expects a reference series, a `trendType` and an optional set of object properties.

The trend series then "trends" the data in that `referenceSeries` according to the `trendType` into a function, and plots the function in the visible area of the chart.

Constructor

```
EJSC.TrendSeries( EJSC.Series referenceSeries, string trendType [, object options] )
```

Valid options for `trendType`:

- "linear"
- "power"
- "exponential"
- "logarithmic"

Example

```
var mySeries1 = new EJSC.ScatterSeries(...);  
var mySeries2 = new EJSC.TrendSeries(  
    mySeries1,  
    "linear",  
    { title: "New Trend Series" }  
)
```

Defining Properties and Events

TrendSeries properties may be set individually after the series has been created or in batch using the `options` parameter during instantiation.

Setting properties individually

```
var mySeries = new EJSC.TrendSeries(myDataSeries, "linear");  
mySeries.lineWidth = 2;  
mySeries.title = "New Trend Series";
```

Setting properties in batch

```
var mySeries = new EJSC.TrendSeries(  
    myDataSeries,  
    "linear",  
    { lineWidth: 2, title: "New Trend Series" }  
)
```

```
 );
```

5.4.12.1 Properties

5.4.12.1.1 color (inherited)

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.4.12.1.2 coloredLegend (inherited)

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.4.12.1.3 hint_string (inherited)

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),
{
    hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br /><strong>Y:
</strong>[y]"
});
);
```

5.4.12.1.4 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.4.12.1.5 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.4.12.1.6 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.4.12.1.7 title (inherited)

Definition

string **title** = "Series <index>"

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.4.12.1.8 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.4.12.1.9 **x_axis** (inherited)

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.4.12.1.10 **x_axis_formatter** (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.12.1.11 **y_axis** (inherited)

Definition

string **y_axis** = "left"

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.4.12.1.12 **y_axis_formatter** (inherited)

Definition

string **y_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.4.12.2 Methods

5.4.12.2.1 `getVisibility` (inherited)

Definition

`boolean getVisibility()`

Description

Returns a boolean indicating the series current visible state

5.4.12.2.2 `hide` (inherited)

Definition

`void hide()`

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.4.12.2.3 `hideLegend` (inherited)

Definition

`void hideLegend()`

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.4.12.2.4 `reload` (inherited)

Definition

`void reload()`

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the `reload()` method exists in the base Series class, implementation of the protected methods triggered by calling `reload()` is at the discretion of the child class.

5.4.12.2.5 setColor (inherited)

Definition

```
void setColor( string color )
```

Description

Changes the series color and causes the chart to redraw.

5.4.12.2.6 setColoredLegend (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.4.12.2.7 setLineWidth (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.4.12.2.8 setTitle (inherited)

Definition

```
void setTitle( string title )
```

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.4.12.2.9 show (inherited)

Definition

```
void show( )
```

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.4.12.2.10 showLegend (inherited)

Definition

void **showLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.4.12.3 Events

5.4.12.3.1 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)**

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.4.12.3.2 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange([EJSC.Series](#) series, [EJSC.Chart](#) chart)**

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.4.12.3.3 onShowHint (inherited)

Definition

string **onShowHint([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)**

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.4.12.4 Text Replacement Options

String	Replaced With
[chart_title]	The title of the chart
[series_title]	The title of the series the selected point resides in
[xaxis]	The caption of the series x axis
[yaxis]	The caption of the series y axis
[x]	The preformatted X value of the point
[y]	The preformatted Y value of the point
[label]	The label property of the current point

5.5 Data Handlers

5.5.1 EJSC.XMLDataHandler

XMLDataHandler loads the requested XML file, determines the format (Full, Short or Compact) and extracts the data points into a format that the Series classes can manipulate.

The constructor expects the URL to the XML data file and an optional set of object properties.

Constructor

```
EJSC.XMLDataHandler( string url [, object options] )
```

Example

```
var myDataHandler = new EJSC.XMLDataHandler(
    "http://www.ejschart.com/data.xml"
);
```

Formats:

The XMLDataHandler supports three formats:

- [Full](#)
- [Short](#)
- [Compact](#)

5.5.1.1 Properties

5.5.1.1.1 requestType (inherited)

Definition

```
string requestType = "GET"
```

Description

Defines the type of HTTP request to be made. Valid options are "GET" and "POST"

5.5.1.1.2 url (inherited)

Definition

string **url** = null

Description

Defines the url currently being used to retrieve data. Descendants of AjaxDataHandler generally allow this to be set in the constructor method. To modify this value after creation, call the [setUrl](#) method which allows the data to be reloaded immediately.

5.5.1.1.3 urlData (inherited)

Definition

string **urlData** = null

Description

Defines the data to be included for both POST and GET requests. When performing a GET request, this data (if defined) will be appended to the URL before the request is made. For POST requests, this data will be sent as the body of the request.

NOTE: For GET requests you must include the proper syntax for appending the url stored in the url property. Example:

```
url = "http://localhost/getData"  
urlData = "?param1=30"
```

or

```
url = "http://localhost/getData?param1=30"  
urlData = "&extra=1"
```

5.5.1.2 Methods

5.5.1.2.1 getUrl (inherited)

Definition

string **getUrl()**

Description

Returns the url string currently stored in the AjaxDataHandler descendant.

DEPRECATED, see [EJSC.AjaxDataHandler.url](#)

5.5.1.2.2 loadData (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.1.2.3 setRequestType (inherited)

Definition

```
void setRequestType( string requestType, boolean reload )
```

Description

Updates the requestType stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Valid options for requestType are "GET" and "POST"

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.1.2.4 setUrl (inherited)

Definition

```
void setUrl( string url, boolean reload )
```

Description

Updates the url string stored in the AjaxDataHandler descendant and optionally reloads the data immediately.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.1.2.5 setUrlData (inherited)

Definition

```
void setUrlData( string urlData, boolean reload )
```

Description

Updates the urlData stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.1.2.6 setXMLData (inherited)

Definition

```
void setXMLData( XMLHttpRequest request )
```

Description

This method allows passing of an already retrieved XMLHttpRequest object to an AjaxDataHandler descendant. When used in conjunction with the [onNeedsData](#) event, this method allows interaction with pre-existing 3rd party Ajax libraries instead of the request pool built into the chart library.

If the data handler is not currently in the loading state (i.e. [onNeedsData](#) was triggered), calling this method will have no effect.

5.5.1.3 Events

5.5.1.3.1 onDataAvailable (inherited)

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.1.3.2 onDataReady (inherited)

Definition

```
boolean onDataReady( XMLHttpRequest response, EJSC.AjaxDataHandler data_handler, EJSC.Series series, EJSC.Chart chart)
```

Description

This event is fired when data has arrived completely and is ready for processing by the data handler. Returning true from this event will cause the data handler to process its data normally, returning false will cause processing to be canceled.

5.5.1.3.3 onNeedsData (inherited)

Definition

```
boolean onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart )
XMLHttpRequest onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart
```

chart)

Description

This event allows for additional control over when and how data is retrieved by the data handler. If assigned, the event will be triggered whenever the its owner series has requested the data handler retrieve its data. The event passes a reference to the current data handler, its owner series and the owner chart.

The result of this event is expected to be either a boolean value or an XMLHttpRequest object which has already been retrieved (responseXML is a valid, well-formed chart xml document).

RESULT:

- **true:** The data handler will ignore other properties such as url and requestType and hold itself in a loading state and wait for its setXMLData method to be called and provided a valid XMLHttpRequest object. In this manner, a separate Ajax library may be used to retrieve data.
- **false:** The data handler will ignore other properties such as url and requestType and cancel its loading process.
- **XMLHttpRequest:** The data handler will ignore other properties such as url and requestType and immediately begin processing the data stored in responseXML.

5.5.2 EJSC.XMLStringDataHandler

XMLStringDataHandler processes the provided xml-formatted string, determines the format (Full, Short or Compact) and extracts the data points into a format that the Series classes can manipulate.

The constructor expects a properly formatted string containing XML data and an optional set of object properties.

Constructor

```
EJSC.XMLStringDataHandler( string xml [, object options] )
```

Example

```
var myDataHandler = new EJSC.XMLStringDataHandler(
    '<?xml version="1.0"?><graph><plot><point x="1" y="1" /><point x="2" y="2"
    /><point x="3" y="3" /></plot></graph>';
);
```

Formats:

The XMLStringDataHandler supports three formats:

- [Full](#)
- [Short](#)
- [Compact](#)

5.5.2.1 Methods

5.5.2.1.1 getXML

Definition

string **getXML()**

Description

Returns the xml string currently stored in the XMLStringDataHandler.

5.5.2.1.2 loadData (inherited)

Definition

void **loadData()**

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.2.1.3 setXML

Definition

void **setXML(string xml)**

Description

Updates the xml string stored in the XMLStringDataHandler.

Note: This will not cause the data to be refreshed, see [EJSC.Series.reload\(\)](#) for more information.

5.5.2.2 Events

5.5.2.2.1 onDataAvailable (inherited)

Definition

void **onDataAvailable()**

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.3 EJSC.ArrayDataHandler

ArrayDataHandler converts the JavaScript array of points into a format that the Series classes can manipulate.

The constructor expects a multi-dimensional array of data and an optional set of object properties.

Constructor

```
EJSC.ArrayDataHandler( array data [, object options] )
```

Example

```
var myDataHandler = new EJSC.ArrayDataHandler(  
    [ [1,1], [2,2], [3,3], [4,4] ]  
)
```

5.5.3.1 Methods

5.5.3.1.1 getArray

Definition

```
array getArray()
```

Description

Returns the data array currently stored in the ArrayDataHandler.

5.5.3.1.2 loadData (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.3.1.3 setArray

Definition

```
void setArray( array data )
```

Description

Updates the data array stored in the ArrayDataHandler.

Note: This will not cause the data to be refreshed, see [EJSC.Series.reload\(\)](#) for more

information.

5.5.3.2 Events

5.5.3.2.1 onDataAvailable (inherited)

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.4 EJSC.CSVFileDataHandler

CSVFileDataHandler loads the requested csv file and extracts the data points into a format that the Series classes can manipulate.

The constructor expects the URL to the csv data file and an optional set of object properties.

Constructor

```
EJSC.CSVFileDataHandler( string url [, object options] )
```

Example

```
var myDataHandler = new EJSC.CSVFileDataHandler(  
    "http://www.ejschart.com/data.csv"  
)
```

5.5.4.1 Properties

5.5.4.1.1 requestType (inherited)

Definition

```
string requestType = "GET"
```

Description

Defines the type of HTTP request to be made. Valid options are "GET" and "POST"

5.5.4.1.2 url (inherited)

Definition

```
string url = null
```

Description

Defines the url currently being used to retrieve data. Descendants of AjaxDataHandler generally allow this to be set in the constructor method. To modify this value after creation, call the [setUrl](#) method which allows the data to be reloaded immediately.

5.5.4.1.3 urlData (inherited)

Definition

```
string urlData = null
```

Description

Defines the data to be included for both POST and GET requests. When performing a GET request, this data (if defined) will be appended to the URL before the request is made. For POST requests, this data will be sent as the body of the request.

NOTE: For GET requests you must include the proper syntax for appending the url stored in the url property. Example:

```
url = "http://localhost/getData"  
urlData = "?param1=30"
```

or

```
url = "http://localhost/getData?param1=30"  
urlData = "&extra=1"
```

5.5.4.2 Methods

5.5.4.2.1 getUrl (inherited)

Definition

```
string getUrl()
```

Description

Returns the url string currently stored in the AjaxDataHandler descendant.

DEPRECATED, see [EJSC.AjaxDataHandler.url](#)

5.5.4.2.2 loadData (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.4.2.3 setRequestType (inherited)

Definition

```
void setRequestType( string requestType, boolean reload )
```

Description

Updates the requestType stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Valid options for requestType are "GET" and "POST"

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.4.2.4 setUrl (inherited)

Definition

```
void setUrl( string url, boolean reload )
```

Description

Updates the url string stored in the AjaxDataHandler descendant and optionally reloads the data immediately.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.4.2.5 setUrlData (inherited)

Definition

```
void setUrlData( string urlData, boolean reload )
```

Description

Updates the urlData stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.4.2.6 setXMLData (inherited)

Definition

```
void setXMLData( XMLHttpRequest request )
```

Description

This method allows passing of an already retrieved XMLHttpRequest object to an AjaxDataHandler descendant. When used in conjunction with the [onNeedsData](#) event, this method allows interaction with pre-existing 3rd party Ajax libraries instead of the request pool built into the chart library.

If the data handler is not currently in the loading state (i.e. [onNeedsData](#) was triggered), calling this method will have no effect.

5.5.4.3 Events

5.5.4.3.1 onDataAvailable (inherited)

Definition

void [onDataAvailable\(\)](#)

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.4.3.2 onDataReady (inherited)

Definition

boolean [onDataReady\(XMLHttpRequest response, EJSC.AjaxDataHandler data_handler, EJSC.Series series, EJSC.Chart chart \)](#)

Description

This event is fired when data has arrived completely and is ready for processing by the data handler. Returning true from this event will cause the data handler to process its data normally, returning false will cause processing to be canceled.

5.5.4.3.3 onNeedsData (inherited)

Definition

boolean [onNeedsData\(EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart \)](#)
XMLHttpRequest [onNeedsData\(EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart \)](#)

Description

This event allows for additional control over when and how data is retrieved by the data handler. If assigned, the event will be triggered whenever the its owner series has requested the data handler retrieve its data. The event passes a reference to the current data handler, its owner series and the owner chart.

The result of this event is expected to be either a boolean value or an XMLHttpRequest object which has already been retrieved (responseXML is a valid, well-formed chart xml document).

RESULT:

- **true:** The data handler will ignore other properties such as url and requestType and hold itself in a loading state and wait for its setXMLData method to be called and provided a valid XMLHttpRequest object. In this manner, a separate Ajax library may be used to retrieve data.
- **false:** The data handler will ignore other properties such as url and requestType and cancel its loading process.
- **XMLHttpRequest:** The data handler will ignore other properties such as url and requestType and immediately begin processing the data stored in responseXML.

5.5.5 EJSC.CSVStringDataHandler

CSVStringDataHandler converts the csv string provided into a format that the Series classes can manipulate.

The constructor expects a properly formatted string and an optional set of object properties.

Constructor

```
EJSC.CSVStringDataHandler( string data [, object options] )
```

Example

```
var myDataHandler = new EJSC.CSVStringDataHandler(  
    "1|1,2|2,3|3,4|4"  
)
```

5.5.5.1 Methods

5.5.5.1.1 getCSV

Definition

```
string getCSV()
```

Description

Returns the csv string currently stored in the CSVStringDataHandler.

5.5.5.1.2 loadData (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.5.1.3 setCSV

Definition

```
void setCSV( string csv )
```

Description

Updates the csv string stored in the CSVStringDataHandler.

Note: This will not cause the data to be refreshed, see [EJSC.Series.reload\(\)](#) for more information.

5.5.5.2 Events

5.5.5.2.1 onDataAvailable (inherited)

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.6 EJSC.JSONFileDataHandler

JSONFileDataHandler loads the requested JSON file and extracts the data points into a format that the Series classes can manipulate.

The constructor expects the URL to the JSON data file and an optional set of object properties.

Constructor

```
EJSC.JSONFileDataHandler( string url [, object options] )
```

Example

```
var myDataHandler = new EJSC.JSONDataHandler(  
    "http://www.ejchart.com/data.json"  
)
```

See [Data Formats](#) for additional information.

5.5.6.1 Properties

5.5.6.1.1 requestType (inherited)

Definition

```
string requestType = "GET"
```

Description

Defines the type of HTTP request to be made. Valid options are "GET" and "POST"

5.5.6.1.2 url (inherited)

Definition

```
string url = null
```

Description

Defines the url currently being used to retrieve data. Descendants of AjaxDataHandler generally allow this to be set in the constructor method. To modify this value after creation, call the [setUrl](#) method which allows the data to be reloaded immediately.

5.5.6.1.3 urlData (inherited)

Definition

```
string urlData = null
```

Description

Defines the data to be included for both POST and GET requests. When performing a GET request, this data (if defined) will be appended to the URL before the request is made. For POST requests, this data will be sent as the body of the request.

NOTE: For GET requests you must include the proper syntax for appending the url stored in the url property. Example:

```
url = "http://localhost/getData"  
urlData = "?param1=30"
```

or

```
url = "http://localhost/getData?param1=30"  
urlData = "&extra=1"
```

5.5.6.2 Methods

5.5.6.2.1 getUrl (inherited)

Definition

```
string getUrl( )
```

Description

Returns the url string currently stored in the AjaxDataHandler descendant.

DEPRECATED, see [EJSC.AjaxDataHandler.url](#)

5.5.6.2.2 loadData (inherited)

Definition

void **loadData()**

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.6.2.3 setRequestType (inherited)

Definition

void **setRequestType(string requestType, boolean reload)**

Description

Updates the requestType stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Valid options for requestType are "GET" and "POST"

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.6.2.4 setUrl (inherited)

Definition

void **setUrl(string url, boolean reload)**

Description

Updates the url string stored in the AjaxDataHandler descendant and optionally reloads the data immediately.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.6.2.5 setUrlData (inherited)

Definition

void **setUrlData(string urlData, boolean reload)**

Description

Updates the urlData stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.5.6.2.6 setXMLData (inherited)

Definition

void **setXMLData**(XMLHttpRequest request)

Description

This method allows passing of an already retrieved XMLHttpRequest object to an AjaxDataHandler descendant. When used in conjunction with the [onNeedsData](#) event, this method allows interaction with pre-existing 3rd party Ajax libraries instead of the request pool built into the chart library.

If the data handler is not currently in the loading state (i.e. [onNeedsData](#) was triggered), calling this method will have no effect.

5.5.6.3 Events

5.5.6.3.1 onDataAvailable (inherited)

Definition

void **onDataAvailable**()

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.5.6.3.2 onDataReady (inherited)

Definition

boolean **onDataReady**(XMLHttpRequest response, EJSC.AjaxDataHandler data_handler, EJSC.Series series, EJSC.Chart chart)

Description

This event is fired when data has arrived completely and is ready for processing by the data handler. Returning true from this event will cause the data handler to process its data normally, returning false will cause processing to be canceled.

5.5.6.3.3 onNeedsData (inherited)

Definition

```
boolean onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart )  
XMLHttpRequest onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart )
```

Description

This event allows for additional control over when and how data is retrieved by the data handler. If assigned, the event will be triggered whenever the its owner series has requested the data handler retrieve its data. The event passes a reference to the current data handler, its owner series and the owner chart.

The result of this event is expected to be either a boolean value or an XMLHttpRequest object which has already been retrieved (responseXML is a valid, well-formed chart xml document).

RESULT:

- **true:** The data handler will ignore other properties such as url and requestType and hold itself in a loading state and wait for its setXMLData method to be called and provided a valid XMLHttpRequest object. In this manner, a separate Ajax library may be used to retrieve data.
- **false:** The data handler will ignore other properties such as url and requestType and cancel its loading process.
- **XMLHttpRequest:** The data handler will ignore other properties such as url and requestType and immediately begin processing the data stored in responseXML.

5.5.7 EJSC.JSONStringDataHandler

JSONStringDataHandler converts the JSON string provided into a format that the Series classes can manipulate.

The constructor expects a properly formatted string and an optional set of object properties.

Constructor

```
EJSC.JSONStringDataHandler( string data [, object options] )
```

Example

```
var myDataHandler = new EJSC.JSONStringDataHandler(  
    '[{"x":1,"y":2},{"x":2,"y":4}']  
)
```

5.5.7.1 Methods

5.5.7.1.1 getJSON

Definition

```
string getJSON()
```

Description

Returns the JSON string currently stored in the JSONStringDataHandler.

5.5.7.1.2 **loadData** (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.5.7.1.3 **setJSON**

Definition

```
void setJSON( string JSON )
```

Description

Updates the JSON string stored in the JSONStringDataHandler.

Note: This will not cause the data to be refreshed, see [EJSC.Series.reload\(\)](#) for more information.

5.5.7.2 Events

5.5.7.2.1 **onDataAvailable** (inherited)

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.6 Label Formatters

5.6.1 EJSC.NumberFormatter

Use this formatter when you want more control over the display of numeric values in your charts. It can be applied to the chart axis as well as series hints.

Constructor

EJSC.NumberFormatter([options])

Example

```
var nf = new EJSC.NumberFormatter({  
    currency_symbol: "$",  
    currency_position: "inner",  
    negative_symbol: "()"  
});
```

5.6.1.1 Properties

5.6.1.1.1 currency_align

Definition

```
string currency_align = "left"
```

Description

Valid options are "left" and "right".

5.6.1.1.2 currency_position

Definition

```
string currency_position = "inner"
```

Description

Valid options are "inner" and "outer".

5.6.1.1.3 currency_symbol

Definition

```
string currency_symbol = ""
```

Description

Specifies the symbol used to indicate currency.

Note: If blank "" then no currency marker is used.

5.6.1.1.4 decimal_separator

Definition

```
string decimal_separator = ","
```

Description

Specifies the symbol used to separate the whole number part from the fractional part.

Common values are "." or ","

5.6.1.1.5 forced_decimals

Definition

integer **forced_decimals** = undefined

Description

Specifies the number of decimal places which MUST be displayed (0's are appended if necessary).

5.6.1.1.6 negative_symbol

Definition

string **negative_symbol** = "-"

Description

Specifies the formatting of negative numbers.

Valid options are "-" and "()"

5.6.1.1.7 thousand_separator

Definition

string **thousand_separator** = ","

Description

Specifies the symbol used to separate thousands groupings.

Common values are:

" , " renders as 1,000,000

" . " renders as 1.000.000

" " renders as 1000000

5.6.1.1.8 variable_decimals

Definition

string **variable_decimals** = undefined

Description

Specifies the number of decimal places which MAY be displayed (values are truncated to this length)

If left undefined, values are not truncated.

5.6.1.2 Methods

5.6.1.2.1 format (inherited)

Definition

```
string format( float value, integer precision )
```

Description

Format is called when a value needs to be formatted for display in the axis, hint, cursor position, etc.

The behavior of the format method is to round a numeric value to the precision specified. Descendants do not need to implement the precision parameter.

5.6.2 EJSC.DateFormatter

Use this formatter when you want to display date values in your charts. It can be applied to the chart axis, series hints and cursor position labels by assigning the appropriate formatter property.

Dates are supported in UTC format by specifying a JavaScript date (i.e. number of milliseconds since midnight January 01, 1970) for a point value.

See the [format_string](#) property for information on supported date formatting options.

Constructor

```
EJSC.DateFormatter([options])
```

Example

```
var df = new EJSC.DateFormatter({
    format_string: "YYYY-MM-DD"
});
```

5.6.2.1 Properties

5.6.2.1.1 format_string

Definition

```
string format_string = ""
```

Description

The following format options are available:

Format	Description
YYYY	Four (4) digit year (i.e. 2007)
YY	Two (2) digit year (i.e. 07)

MMMM	Full month name (i.e. January)
MMM	Short month name (i.e. Jan)
MM	Two (2) digit month of the year with leading zeros (i.e. 01)
M	Month of the year without leading zeros
DDDD	Full day of the week (i.e. Monday)
DDD	Short day of the week (i.e. Mon)
DD	Two (2) digit day of the month with leading zeros (i.e. 04)
D	Day of the month without leading zeros
HH	Hour of the day in 24-hour format with leading zeros
H	Hour of the day in 24-hour format without leading zeros
hh	Hour of the day in 12-hour format with leading zeros
h	Hour of the day in 12-hour format without leading zeros
NN	Minutes with leading zeros
N	Minutes without leading zeros
SS	Seconds with leading zeros
S	Seconds without leading zeros
ZZZ	Milliseconds (3 places) with leading zeros
ZZ	Milliseconds (2 places) with leading zeros
Z	Milliseconds without leading zeros
AA	AM/PM notation
A	A/P notation
aa	am/pm notation
a	a/p notation

5.6.2.1.2 timezoneOffset

Definition

integer **timezoneOffset** = undefined

Description

Used in conjunction with useUTC, this property may be used to display dates in the specified time zone. The timezoneOffset property is set by specifying the number of minutes (positive or negative) to offset the given time.

Example

>> Display times in Eastern Standard Time (EST)

```
var chart = new EJSC.Chart("myChart");
chart.axis_bottom.formatter = new EJSC.DateFormatter({
    format_string: "HH:NN:SS",
    useUTC: true,
    timezoneOffset: -300
});
```

5.6.2.1.3 useUTC

Definition

boolean **useUTC** = true

Description

Set this property to false to use the workstation local time to calculate dates. This may be useful when passing in dates generated by JavaScript on the client machine to indicate current time.

5.6.2.2 Methods

5.6.2.2.1 format (inherited)

Definition

string **format**(float value, integer precision)

Description

Format is called when a value needs to be formatted for display in the axis, hint, cursor position, etc.

The behavior of the format method is to round a numeric value to the precision specified. Descendants do not need to implement the precision parameter.

5.6.3 EJSC.StringFormatter

Use this formatter when you want to prefix or append data to the value being displayed in your charts. It can be applied to the chart axis, series hints and cursor position labels by assigning the appropriate formatter property.

Constructor

EJSC.StringFormatter([options])

Example

```
var sf = new EJSC.StringFormatter({
    prefix: "Before (" ,
    append: ") After"
});
```

5.6.3.1 Properties

5.6.3.1.1 append

Definition

string **append** = undefined

Description

The string stored in the append property will be applied to every value processed by the formatter.

5.6.3.1.2 prefix**Definition**

string **prefix** = undefined

Description

The string stored in the prefix property will be applied to every value processed by the formatter.

5.6.3.2 Methods**5.6.3.2.1 format (inherited)****Definition**

string **format**(float value, integer precision)

Description

Format is called when a value needs to be formatted for display in the axis, hint, cursor position, etc.

The behavior of the format method is to round a numeric value to the precision specified. Descendants do not need to implement the precision parameter.

5.6.3.3 Events**5.6.3.3.1 onNeedsFormat****Definition**

string **onNeedsFormat**(number value, EJSC.StringFormatter formatter)

Description

This event (when assigned) will fire every time the formatter needs to process a value. The string returned from this event will be displayed in place of the value in the chart.

Example

>> Adjust all values by 100

```
var chart = new EJSC.Chart("myChart");
chart.x_axis_formatter = new EJSC.StringFormatter({
    onNeedsFormat: function(value, formatter) {
        return value + 100;
    }
});
```

5.7 Base Classes

5.7.1 EJSC.Inheritable

Base class from which all EJSC classes descend. There are no public properties, methods or events for this class at this time.

Constructor

none

5.7.2 EJSC.AjaxDataHandler

Base data handler class for all Ajax data handlers (i.e. [EJSC.XMLDataHandler](#), [EJSC.CSVFileDataHandler](#), [EJSC.JSONFileDataHandler](#)). This base class defines common properties, methods and events but does not implement any data processing. This class should not be used directly.

Constructor

none

5.7.2.1 Properties

5.7.2.1.1 `requestType`

Definition

string `requestType` = "GET"

Description

Defines the type of HTTP request to be made. Valid options are "GET" and "POST"

5.7.2.1.2 `url`

Definition

string `url` = null

Description

Defines the url currently being used to retrieve data. Descendants of AjaxDataHandler generally allow this to be set in the constructor method. To modify this value after creation, call the [setUrl](#) method which allows the data to be reloaded immediately.

5.7.2.1.3 `urlData`

Definition

```
string urlData = null
```

Description

Defines the data to be included for both POST and GET requests. When performing a GET request, this data (if defined) will be appended to the URL before the request is made. For POST requests, this data will be sent as the body of the request.

NOTE: For GET requests you must include the proper syntax for appending the url stored in the url property. Example:

```
url = "http://localhost/getData"  
urlData = "?param1=30"
```

or

```
url = "http://localhost/getData?param1=30"  
urlData = "&extra=1"
```

5.7.2.2 Methods

5.7.2.2.1 getUrl

Definition

```
string getUrl()
```

Description

Returns the url string currently stored in the AjaxDataHandler descendant.

DEPRECATED, see [EJSC.AjaxDataHandler.url](#)

5.7.2.2.2 loadData (inherited)

Definition

```
void loadData()
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.7.2.2.3 setRequestType

Definition

```
void setRequestType( string requestType, boolean reload )
```

Description

Updates the requestType stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Valid options for requestType are "GET" and "POST"

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.7.2.2.4 setUrl

Definition

```
void setUrl( string url, boolean reload )
```

Description

Updates the url string stored in the AjaxDataHandler descendant and optionally reloads the data immediately.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.7.2.2.5 setUrlData

Definition

```
void setUrlData( string urlData, boolean reload )
```

Description

Updates the urlData stored in the AjaxDataHandler descendant and optionally reloads / reprocesses the data source and updates the series.

Note: If the reload parameter is omitted or false, the data will not reload automatically and must be done manually via [EJSC.Series.reload\(\)](#)

5.7.2.2.6 setXMLData

Definition

```
void setXMLData( XMLHttpRequest request )
```

Description

This method allows passing of an already retrieved XMLHttpRequest object to an AjaxDataHandler descendant. When used in conjunction with the [onNeedsData](#) event, this method allows interaction with pre-existing 3rd party Ajax libraries instead of the request pool built into the chart library.

If the data handler is not currently in the loading state (i.e. [onNeedsData](#) was triggered), calling this method will have no effect.

5.7.2.3 Events

5.7.2.3.1 onDataAvailable (inherited)

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.7.2.3.2 onDataReady

Definition

```
boolean onDataReady( XMLHttpRequest response, EJSC.AjaxDataHandler data_handler, EJSC.Series series, EJSC.Chart chart )
```

Description

This event is fired when data has arrived completely and is ready for processing by the data handler. Returning true from this event will cause the data handler to process its data normally, returning false will cause processing to be canceled.

5.7.2.3.3 onNeedsData

Definition

```
boolean onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart )  
XMLHttpRequest onNeedsData( EJSC.AjaxDataHandler dataHandler, EJSC.Series series, EJSC.Chart chart )
```

Description

This event allows for additional control over when and how data is retrieved by the data handler. If assigned, the event will be triggered whenever the its owner series has requested the data handler retrieve its data. The event passes a reference to the current data handler, its owner series and the owner chart.

The result of this event is expected to be either a boolean value or an XMLHttpRequest object which has already been retrieved (responseXML is a valid, well-formed chart xml document).

RESULT:

- **true:** The data handler will ignore other properties such as url and requestType and hold itself in a loading state and wait for its setXMLData method to be called and provided a valid XMLHttpRequest object. In this manner, a separate Ajax library may be used to retrieve data.
- **false:** The data handler will ignore other properties such as url and requestType and cancel its

loading process.

- **XMLHttpRequest:** The data handler will ignore other properties such as url and requestType and immediately begin processing the data stored in responseXML.

5.7.3 EJSC.Axis

Base class for all Axis classes (i.e. [EJSC.LinearAxis](#), [EJSC.LogarithmicAxis](#)). This base class defines common properties, methods and events but does not implement any drawing or calculation routines. This class should not be used directly.

Constructor

none

5.7.3.1 Properties

5.7.3.1.1 background

Definition

```
object background = {  
    color: "#fff",  
    opacity: 0,  
    includeTitle: false  
};
```

Description

Defines the color and opacity of the axis area background. Setting the includeTitle property to true will fill the axis caption area as well as the ticks. If opacity is set to 0, no fill will occur.

5.7.3.1.2 border

Definition

```
object border = {  
    thickness: 1,  
    color: undefined,  
    opacity: 100,  
    show: true  
}
```

Description

Defines the appearance of the axis side bordering the chart area. By default the border color inherits the axis color property ([EJSC.Axis.color](#))

Example

>> Provide a 2 pixel tall green border on the bottom axis.

```
var chart = new EJSC.Chart()
```

```

    "chart",
    {
        axis_bottom:
            border: { thickness: 2, color: "#0F0" }
    }
);

```

5.7.3.1.3 caption

Definition

string **caption** = "Axis"

Description

Defines the text to be displayed below or beside the axis.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Customize the bottom axis caption.

```

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption: "Year" }
    }
);

```

5.7.3.1.4 caption_class

Definition

string **caption_class** = ""

Description

Defines the CSS className to assign to the axis caption.

For styling the tick labels, see [EJSC.Axis.label_class](#)

Example

>> Style the axis caption bold.

```

<style> .AxisCaption { font-style: bold; } </style>

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { caption_class: "AxisCaption" }
    }
);

```

5.7.3.1.5 color

Definition

```
string color = "#FFF"
```

Description

Defines the default color of the axis border and tick marks. If the sub properties such as minor_ticks.color, major_ticks.color, border.color are left undefined, they inherit the value set here.

Example

>> Color the axis border and tick marks red

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { color: "#F00" }
    }
);
```

5.7.3.1.6 crosshair

Definition

```
object crosshair = {
    show: false,
    color: "#F00"
}
```

Description

Defines if crosshair should be shown on the chart at the current mouse coordinates as they relate to the given axis. May be enabled and disabled for each axis independently. This is automatically disabled for all axes if [EJSC.Chart.allow_interactivity](#) is set to false.

Example

>> Show crosshair based on the bottom axis mouse position.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            crosshair: { show: true }
        }
    }
);
```

5.7.3.1.7 cursor_position

Definition

```
object cursor_position = {
    show: false,
    color: "#F00",
    textColor: "#FFF",
    formatter: undefined,
    caption: undefined,
    className: undefined
}
```

Description

Defines the display properties of the cursor position feature for an axis. These properties may be used to turn the cursor position indicator on and off as well as configure the styling and color.

show: determines whether or not to display the cursor position while the mouse is within the chart area

color: sets the background and line color

textColor: sets the text color

formatter: defines a formatter to use when displaying coordinates, if left undefined it will use the axis formatter

caption: defines text to use as a prefix to the current coordinate

className: a CSS class name to be used for additional styling

Example

>> Turn on cursor position for the bottom axis and configure to display a related label

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            cursor_position: {
                show: true,
                caption: "Sales"
            }
        }
    }
);
```

5.7.3.1.8 extremes_ticks

Definition

```
boolean extremes_ticks = false
```

Description

Defines if the min and max values should be forced to land on the next tick mark.

Example

>> Force tick marks at the min and max coordinates of the bottom axis (left and right sides of the chart)

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { extremes_ticks: true }
    }
);
```

5.7.3.1.9 force_static_points

Definition

boolean **force_static_points** = false

Description

Defines if the chart should force ticks to match up to every point by converting the data to strings.

Example

>> Display every bottom axis data point, essentially disable auto axis scaling.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { force_static_points: true }
    }
);
```

5.7.3.1.10 formatter

Definition

EJSC.Formatter **formatter** = EJSC.Formatter

Description

Defines the formatter that will be used to format the tick marks on the axis before displaying them.

Types:

EJSC.DateFormatter
EJSC.NumberFormatter
EJSC.StringFormatter

Example

>> Display bottom axis tick labels as \$0.00

```
var chart = new EJSC.Chart(
```

```

    "chart",
    {
        axis_bottom:  {
            formatter: new EJSC.NumberFormatter( { currency_symbol: "$" ,
forced_decimals: 2, variable_decimals: 2 } )
        }
    }
);

```

5.7.3.1.11 grid

Definition

```
object grid = {
    thickness: 1,
    color: "rgb(230,230,230)",
    opacity: 100,
    show: true
}
```

Description

Defines the appearance and visibility of the grid drawn in the background.

Example

>> Do not draw the background grid for the top and right axes.

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_top:  {
            grid: { show: false }
        },
        axis_right: {
            grid: { show: false }
        }
    }
);
```

5.7.3.1.12 hint_caption

Definition

```
string hint_caption = "Value:"
```

Description

Defines the text to display in front of the axis-related value in the hint (leave blank to hide the value when displaying the hint).

Example

>> Customize the value label in the hint window

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            hint_caption: "Month:"
        }
    }
);
```

5.7.3.1.13 label_class

Definition

```
string label_class = ""
```

Description

Defines the CSS className to assign to the axis tick labels. Used in conjunction with [EJSC.Axis.stagger_ticks](#) and [EJSC.Axis.size](#), this property allows for greater control over the size and staggering of tick labels on the top and bottom axes.

For styling the caption, see [EJSC.Axis.caption_class](#)

Example

>> Style the axis tick labels grey, make them 24 pixels high to enable text wrapping and enable two levels of tick staggering.

```
<style> .AxisTickLabels { color: #999; height: 24px; } </style>

var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            label_class: "AxisTickLabels",
            size: 48
        }
    }
);
```

5.7.3.1.14 major_ticks

Definition

```
object major_ticks = {
    thickness: 1,
    size: 4,
    color: undefined,
    opacity: 100,
    show: true,
    count: undefined,
    offset: 0,
    min_interval: undefined,
    max_interval: undefined
```

}

Description

This set of properties defines the characteristics of the major ticks for a given axis.

thickness: the height or width (depending on axis orientation) of the tick mark

size: the amount the tick mark extends from the axis border, may be specified as a number or a string containing % for a percentage

color: the color of the tick marks, if left undefined this property inherits its value from [EJSC.Axis.color](#)

opacity: the opacity of the tick marks

show: specifies whether to draw the tick marks

count: the number of tick marks to draw, if left undefined the axis will determine the proper amount of ticks to draw automatically based on the range of data available to the axis

Note: This property is not compatible with text labels (i.e. x axis values are "Gizmos", "Widgets", instead of numbers)

offset: distance in pixels or percent from the axis border to begin drawing the tick marks,

min_interval: Defines the minimum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

max_interval: Defines the maximum interval between major tick marks / labels. This will override the auto generation of ticks to cap the interval to the value when defined.

5.7.3.1.15 max_extreme

Definition

float **max_extreme** = undefined

Description

Defines the maximum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            max_extreme: 500.00
        }
    }
);
```

5.7.3.1.16 minor_ticks

Definition

```
object minor_ticks = {
    show: false,
    color: "rgb(0,0,0)",
    opacity: 20
    thickness: 1,
    count: 7,
    size: 4,
    offset: 0
}
```

Description

Defines the properties of the minor tick marks to be drawn on the axis. The color, opacity and thickness (width of ticks in pixels) properties define the style of the tick marks. The count property defines the number of tick marks to be drawn between each major tick mark. The size property defines the height of the ticks (in pixels or percent). The offset property defines the distance away from the axis the minor tick marks begin drawing.

Example

>> Display red minor tick marks on the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            minor_ticks: { show: true, color: "#FF0000" }
        }
    }
);
```

5.7.3.1.17 min_extreme

Definition

float **min** = undefined

Description

Defines the minimum value of the the axis. This will only affect the axis when set during chart creation and may be used to extend or truncate the value range displayed. To retrieve and set this value after the chart has been created, see [EJSC.Axis.getExtremes](#) and [EJSC.Axis.setExtremes](#)

Example

>> Force the axis range to extend beyond the data it contains

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: {
            min_extreme: -500.00
        }
    }
);
```

```
) ;
```

5.7.3.1.18 size

Definition

```
integer size = 20
```

Description

Defines the height of horizontal axes or width of vertical axes (in pixels) of the tick area. To fully enable staggered ticks on horizontal axes, set this property to a multiple of 20 (or axis tick height), i.e. two levels = 40, three levels = 60.

For additional control over the format of the labels, see the [EJSC.Axis.label_class](#) property.

Example

>> Make axis tick area twice as tall, enabling staggered ticks (default tick label height is 20 pixels)

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { size: 40 }
    }
);
```

5.7.3.1.19 stagger_ticks

Definition

```
boolean stagger_ticks = true
```

Description

Determines whether the axis tick labels are staggered.

NOTE: This property is only applicable to horizontal axes (i.e. [EJSC.Chart.axis_top](#) and [EJSC.Chart.axis_bottom](#))

Example

>> Disable tick staggering for the bottom axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { stagger_ticks: false }
    }
);
```

5.7.3.1.20 visible

Definition

```
boolean visible = true
```

Description

Defines if the axis (containing axis caption and tick labels) should be displayed.

Example

>> Remove the bottom axis from the chart to allow additional room for data

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_bottom: { visible: false }
    }
);
```

5.7.3.1.21 zero_plane

Definition

```
object zero_plane = {
    color: "rgb(0,0,0)",
    show: false,
    opacity: 100,
    thickness: 1,
    coordinate: 0
}
```

Description

Defines the properties of the zero plane line to be drawn at 0 (or whatever the coordinate property is set to). It is used to specify if the line should be shown as well as its color, thickness and opacity. The coordinate property allows the base of [EJSC.BarSeries](#), [EJSC.StackedBarSeries](#) and [EJSC.AreaSeries](#) changed.

Example

>> Display a 2 pixel thick dark green line on the zero plane of the left axis

```
var chart = new EJSC.Chart(
    "chart",
    {
        axis_left: {
            zero_plane: { show: true, color: "rgb(7,89,5)", thickness: 2 }
        }
    }
);
```

5.7.3.2 Methods

5.7.3.2.1 addBin

Definition

```
void addBin( String label, boolean redraw )
```

Description

Adds a new static label to the axis and sets the appropriate flags if necessary to force the chart to draw using static labels (as opposed to a dynamic range based on series data).

This method is useful if there is a need to include bins which may not be part of any series added (i.e. chart labels should be "Apples", "Oranges", "Pears" but the series data only contains data pertaining to Apples and Pears).

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger the chart to draw. The default, if redraw is omitted is **true**.

Note:

Manually added bins may only be removed if there are no series currently utilizing them.

Example

>> Add bins in a specific order to ensure they appear the same each time the chart is loaded, regardless of the order in which they appear in the data.

```
var myChart = new EJSC.Chart("chart");
myChart.axis_bottom.addBin("Salesman 1");
myChart.axis_bottom.addBin("Salesman 2");
myChart.axis_bottom.addBin("Salesman 3");

var mySeries = myChart.addSeries(
    new EJSC.BarSeries(...)
);
```

5.7.3.2.2 getExtremes

Definition

```
object getExtremes()
```

RETURNS:

```
{ min: float, max: float }
```

Description

Returns the current axis extreme values.

To set the extreme values, see [EJSC.Axis.setExtremes](#)

5.7.3.2.3 getZoom

Definition

object **getZoom()**

RETURNS:

{ min: float, max: float }

Description

Returns the current zoom coordinates for a given axis in chart units.

To set the zoom coordinates, see [EJSC.Axis.setZoom](#)

5.7.3.2.4 getZoomBoxCoordinates

Definition

void **getZoomBoxCoordinates()**

RETURNS:

{ min: float, max: float }

Description

Returns the min and max values for a given axis of the current zoom box. These values are in chart coordinates, not pixels.

5.7.3.2.5 hide

Definition

void **hide()**

Description

Hides the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already hidden.

5.7.3.2.6 hideGrid

Definition

void **hideGrid(boolean redraw)**

Description

Hides the background grid for a given axis and if redraw is omitted or true, redraws the chart

No effect if the grid is already hidden.

5.7.3.2.7 resetZoom

Definition

void **resetZoom()**

Description

Resets the zoom for a given axis to use its extreme values for min and max (as if a user had double-clicked the chart or drawn the zoom rectangle anywhere but down and right)

5.7.3.2.8 pixelToPoint

Definition

float **pixelToPoint(integer Pixel)**

Description

Converts the pixel coordinate into chart units based on an axis. The result will be undefined if the pixel location is outside of the chart area.

5.7.3.2.9 pointToPixel

Definition

integer **pointToPixel(number coordinate)**

Description

Converts the chart coordinates based on axis data into the appropriate pixel position for that point (x or y depending on the orientation of the axis)

The result will be undefined if the coordinate provided is outside the currently displayed range.

5.7.3.2.10 removeBin

Definition

void **removeBin(String label, boolean redraw)**

Description

Removes a bin (static text label) from the axis.

If redraw is false, drawing will not occur immediately but will not be entirely prevented. Certain actions such as adding an additional series with redraw = true, or chart dimensions changing may still trigger

the chart to draw. The default, if redraw is omitted is **true**.

Note:

Bins may only be removed using this method if they were added using [EJSC.Axis.addBin](#) and no series are currently utilizing them.

5.7.3.2.11 setCaption

Definition

```
void setCaption( string caption )
```

Description

Updates the axis caption. This method must be used to change the caption once the chart has been rendered. To set a default caption on creation, see [EJSC.Axis.caption](#).

5.7.3.2.12 setCrosshair

Definition

```
void setCrosshair( boolean visible, float coordinate, boolean fireEvent )
```

Description

This method may be used to hide, show and position the cursor position indicator. If the fireEvent parameter is set to true or left undefined the [EJSC.Axis.onShowCrosshair](#) or [EJSC.Axis.onHideCrosshair](#) events will fire.

5.7.3.2.13 setExtremes

Definition

```
void setExtremes( float min, float max )
```

Description

Updates the manual extremes for the axis. Use this method if the series data does not span the range to be displayed on the chart or to limit 100% zoom to a range smaller than the series data.

Example

>> Series data only spans 18 hours on the bottom axis but the chart needs to display an entire day

```
var myChart = new EJSC.Chart( "chart" );
myChart.axis_bottom.setExtremes( 0, 86400000 );
```

5.7.3.2.14 setZoom

Definition:

void **setZoom**(float min, float max)

Description

Sets the current zoom of the axis to the specified coordinates.

5.7.3.2.15 show

Definition

void **show**()

Description

Shows the axis, resizes the chart area and redraws all visible series.

No effect if the axis is already visible.

5.7.3.2.16 showGrid

Definition

void **showGrid**(boolean redraw)

Description

Shows the background grid for the axis and if redraw is omitted or true, redraws the chart.

No effect if the grid is already visible.

5.7.3.3 Events

5.7.3.3.1 onHideCrosshair

Definition

void **onHideCrosshair**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

Called when the axis crosshair is hidden by the chart. This can occur when the user moves their mouse outside of the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending false for the visible parameter and true for the fireEvent parameter.

5.7.3.3.2 onHideCursorPosition

Definition

void **onHideCursorPosition**([EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is fired when the cursor position indicator for an axis is hidden. This will occur when the user's mouse leaves the chart area.

5.7.3.3.3 onNeedsTicks

Definition

array **onNeedsTicks**(float min, float max, [EJSC.Axis](#) axis, [EJSC.Chart](#) chart)

Description

This event is triggered whenever the axis ticks need to be redrawn / recalculated. It expects an array of [float y, string label] to be returned which defines exactly where to put the tick marks and labels. In addition, null may be returned in order to skip custom ticks for the current draw and use the chart's build in tick controls.

min: The current minimum value visible on the chart for the axis.

max: The current maximum y value visible on the chart for the axis.

axis: The axis which needs ticks.

chart: The chart that triggered the event.

Notes

- To use the label formatter already assigned to the axis, set label to null (i.e. [min, null])
- To use on an axis with bins (text instead of numbers), simply send in the bin (i.e. ["First Bin", null])

Example

A typical event handler may look like the following:

```
function doBottomAxisNeedsTicks(min, max, axis, chart) {
    // Display 3 tick marks, one at min, one at max and one directly in between
    var result = new Array();

    result.push( [min, null] );
    result.push( [min + ((max - min) / 2), null] );
    result.push( [max, null] );

    // Given a chart with a min and max of 0 and 100, the resulting array looks like:
    // [
    //   [0, null],
    //   [50, null],
    //   [100, null]
    // ]
    return result;
}
```

5.7.3.3.4 onShowCrosshair

Definition

```
void onShowCrosshair( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the axis crosshair is shown by the chart. This can occur when the user moves their mouse into the chart area or when [EJSC.Axis.setCrosshair](#) is called, sending true for the visible parameter and true for the fireEvent parameter.

5.7.3.3.5 onShowCursorPosition

Definition

```
void onShowCursorPosition( float coordinate, EJSC.Axis axis, EJSC.Chart chart )
```

Description

Called when the cursor position indicator becomes visible or changes position on a given axis. This will occur when the user enters the chart area or moves their mouse within the chart area.

5.7.4 **EJSC.DataHandler**

Base data handler class that defines properties, methods and events common to all data handler descendants. This class does not implement any actual data loading and should not be instantiated. All data handlers should descend from DataHandler or one of its descendants in order to function properly with the [EJSC.Series](#) descendants.

Constructor

none

5.7.4.1 Methods

5.7.4.1.1 loadData

Definition

```
void loadData( )
```

Description

Placeholder method which should be used to clear (if stored) and reload data. This method must be overridden in all descendant classes.

5.7.4.2 Events

5.7.4.2.1 onDataAvailable

Definition

```
void onDataAvailable()
```

Description

Placeholder for storing an event to fire after the a descendant class has loaded and processed its data.

Important: This event should be assigned by the EJSC.Series object.

5.7.5 EJSC.GaugeSeries

Base series class that holds all the generic information for each gauge series that is being created. All gauge type series should descend from this class or one of its descendants in order to function properly with the [EJSC.Chart](#) class.

Constructor

```
none
```

5.7.5.1 Properties

5.7.5.1.1 color (inherited)

Definition

```
string color = undefined
```

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.7.5.1.2 coloredLegend (inherited)

Definition

```
boolean coloredLegend = true
```

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.7.5.1.3 delayLoad (inherited)

EXPERIMENTAL

Definition

```
boolean delayLoad = true
```

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.7.5.1.4 legendIsVisible (inherited)

Definition

boolean **legendIsVisible** = true

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.7.5.1.5 lineOpacity (inherited)

Definition

integer **lineOpacity** = 100

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.7.5.1.6 lineWidth (inherited)

Definition

integer **lineWidth** = 1

Description

Defines the width of the line connecting series points.

5.7.5.1.7 opacity (inherited)

Definition

integer **opacity** = 50

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.7.5.1.8 title (inherited)

Definition

string **title** = "Series <index>"

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.7.5.1.9 visible (inherited)

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.7.5.1.10 x_axis_formatter (inherited)

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.7.5.2 Methods

5.7.5.2.1 getDataHandler (inherited)

Definition

EJSC.DataHandler **getDataHandler()**

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.7.5.2.2 getVisibility (inherited)

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.7.5.2.3 hide (inherited)

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.7.5.2.4 hideLegend (inherited)

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.7.5.2.5 reload (inherited)

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.7.5.2.6 setColor (inherited)

Definition

```
void setColor( string color )
```

Description

Changes the series color and causes the chart to redraw.

5.7.5.2.7 `setColoredLegend` (inherited)

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.7.5.2.8 `setDataHandler` (inherited)

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.7.5.2.9 `setLineOpacity` (inherited)

Definition

```
void setLineOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.lineOpacity](#) property and redraws the series to reflect the change.

5.7.5.2.10 `setLineWidth` (inherited)

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.7.5.2.11 `setOpacity` (inherited)

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.7.5.2.12 setTitle (inherited)

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.7.5.2.13 show (inherited)

Definition

void **show**()

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.7.5.2.14 showLegend (inherited)

Definition

void **showLegend**()

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.7.5.3 Events

5.7.5.3.1 onAfterDataAvailable (inherited)

Definition

boolean **onAfterDataAvailable**([EJSC.Chart](#) chart, [EJSC.Series](#) series)

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.7.5.3.2 onAfterVisibilityChange (inherited)

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.7.5.3.3 onBeforeVisibilityChange (inherited)

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.7.6 EJSC.Formatter

The top level Formatter class is used as a base for all label formatters. It defines a `format_string` property as a guide for descendants. The `format` method is required to be overridden in all descendant classes in order to function properly when used with the chart classes.

Constructor

`EJSC.Formatter()`

5.7.6.1 Properties

5.7.6.1.1 format_string

Definition

string **format_string** = undefined

Description

Defines the format string. Classes that descend from EJSC.Formatter may use this property to store their custom format strings.

5.7.6.2 Methods

5.7.6.2.1 format

Definition

```
string format( float value, integer precision )
```

Description

Format is called when a value needs to be formatted for display in the axis, hint, cursor position, etc.

The behavior of the format method is to round a numeric value to the precision specified. Descendants do not need to implement the precision parameter.

5.7.7 EJSC.Point

Base point class that holds all the generic information for each point that is being created. All points should descend from this class or one of its descendants in order to function properly with the [EJSC.Chart](#) and [EJSC.Series](#) (and descendant) classes.

Constructor

```
none
```

5.7.7.1 Properties

5.7.7.1.1 label

Definition

```
string label = null
```

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.7.7.1.2 userdata

Definition

```
string userdata = null
```

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.7.7.1.3 x

Definition

float **x** = null

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.7.7.1.4 y

Definition

float **y** = null

Description

Defines point Y value.

5.7.8 EJSC.Series

Base series class that holds all the generic information for each series that is being created. All series should descend from this class or one of its descendants in order to function properly with the [EJSC.Chart](#) class.

Constructor

none

5.7.8.1 Properties

5.7.8.1.1 autosort

Definition

boolean **autosort** = true

Description

Defines whether the series applies the appropriate sort to points prior to drawing. Drawing routines are generally optimized to accept data in a certain order and this property eliminates the need for the developer to worry about that order prior to sending data to the series. If set to false, the data must be properly ordered beforehand in order to ensure the series renders correctly.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#), [EJSC.AnalogGaugeSeries](#))

5.7.8.1.2 color

Definition

string **color** = undefined

Description

Defines the series color. If left undefined, the color is pulled from the array of default colors stored in the chart.

Note: May not be applicable to all series (i.e. [EJSC.PieSeries](#))

5.7.8.1.3 coloredLegend

Definition

boolean **coloredLegend** = true

Description

Determines whether the legend text inherits the series color. Setting to false will allow the legend text to inherit its normal cascaded color. To modify this property after series creation see [EJSC.Series.setColoredLegend\(\)](#)

5.7.8.1.4 delayLoad

EXPERIMENTAL

Definition

boolean **delayLoad** = true

Description

This property allows a series to force its data handler to begin data retrieval as soon as it is added to a chart. When set to false, the series will initiate data retrieval as soon as it is added to a chart. When true, the data retrieval is initialized when the series first needs to draw.

5.7.8.1.5 hint_string

Definition

string **hint_string** = undefined

Description

This property may be used to define a series specific string to be used when displaying point hints. This string may contain replacement indicators (see [Text Replacement Options](#)). When left undefined, a default hint defined by the series type will be displayed.

Example

>> Modify the default hint to include custom text.

```
var series = new EJSC.LineSeries(new EJSC.ArrayDataHandler(),  
{
```

```
        hint_string: "My Custom Hint<br /><strong>X: </strong>[x]<br/><strong>Y:</strong>[y]"  
    }  
);
```

5.7.8.1.6 legendIsVisible

Definition

```
boolean legendIsVisible = true
```

Description

Determines whether the legend item associated with the series appears in the legend window. Use the Series.showLegend and Series.hideLegend methods to control legend item visibility after series creation.

5.7.8.1.7 lineOpacity

Definition

```
integer lineOpacity = 100
```

Description

Determines the line opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setLineOpacity\(\)](#)

5.7.8.1.8 lineWidth

Definition

```
integer lineWidth = 1
```

Description

Defines the width of the line connecting series points.

5.7.8.1.9 opacity

Definition

```
integer opacity = 50
```

Description

Determines the fill opacity (if applicable) of the series. The range is a percentage and should be specified as an integer between 0 and 100. To modify this property after series creation see [EJSC.Series.setOpacity\(\)](#)

5.7.8.1.10 title

Definition

string **title** = "Series <index>"

Description

Defines the series title used in hints and legend display.

Note: The default title of Series <index> (where <index> equals the current position in the series array for its owner chart) is assigned when a series is added to a chart using [addSeries](#). This default title is only applied if the title is blank (i.e. "") at the time the addSeries method is called.

5.7.8.1.11 visible

Definition

boolean **visible** = true

Description

Defines whether the series is visible and can draw on the chart

5.7.8.1.12 x_axis

Definition

string **x_axis** = "bottom"

Description

Defines the horizontal axis to use for X values. Valid options are "top" or "bottom".

5.7.8.1.13 x_axis_formatter

Definition

string **x_axis_formatter** = undefined

Description

Defines the formatter that will be used to format hints for the X values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.7.8.1.14 y_axis

Definition

```
string y_axis = "left"
```

Description

Defines the vertical axis to use for Y values. Valid options are "left" or "right".

5.7.8.1.15 y_axis_formatter

Definition

```
string y_axis_formatter = undefined
```

Description

Defines the formatter that will be used to format hints for the Y values before displaying them. If left undefined, the series will inherit the axis formatter of its parent chart.

Types:

[EJSC.DateFormatter](#)

[EJSC.NumberFormatter](#)

5.7.8.2 Methods

5.7.8.2.1 findClosestPoint

Definition

[EJSC.Point](#) **findClosestPoint**(integer pixel)

Description

Returns the point object closest to the pixel coordinate given or null if no points are found.

5.7.8.2.2 getDataHandler

Definition

EJSC.DataHandler **getDataHandler**()

Description

Returns the EJSC.DataHandler descendant currently assigned to the series. This is not applicable to all series and will return null if a data handler has not been defined or is not used.

5.7.8.2.3 getVisibility

Definition

boolean **getVisibility()**

Description

Returns a boolean indicating the series current visible state

5.7.8.2.4 **hide**

Definition

void **hide()**

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already hidden.

5.7.8.2.5 **hideLegend**

Definition

void **hideLegend()**

Description

Changes the series legend item visible state.

No effect if the series legend item is already hidden.

5.7.8.2.6 **reload**

Definition

void **reload()**

Description

Triggers a series reload if the functionality is defined in a child class. This may involve retrieving data again or simply recalculating. While the reload() method exists in the base Series class, implementation of the protected methods triggered by calling reload() is at the discretion of the child class.

5.7.8.2.7 **setColor**

Definition

void **setColor(string color)**

Description

Changes the series color and causes the chart to redraw.

5.7.8.2.8 setColoredLegend

Definition

```
void setColoredLegend( boolean coloredLegend )
```

Description

Sets the [EJSC.Series.coloredLegend](#) property and updates the legend to reflect the change.

5.7.8.2.9 setDataHandler

Definition

```
void setDataHandler( EJSC.DataHandler dataHandler, boolean reload )
```

Description

Updates the series data handler and triggers a data reload if reload parameter is **true**. This method may not be implemented in all child classes.

5.7.8.2.10 setLineOpacity

Definition

```
void setLineOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.lineOpacity](#) property and redraws the series to reflect the change.

5.7.8.2.11 setLineWidth

Definition

```
void setLineWidth( integer width )
```

Description

Updates the [lineWidth](#) property and redraws the chart.

5.7.8.2.12 setOpacity

Definition

```
void setOpacity( integer opacity )
```

Description

Sets the [EJSC.Series.opacity](#) property and redraws the series to reflect the change.

5.7.8.2.13 setTitle

Definition

void **setTitle**(string title)

Description

Changes the series title and update the legend caption (if applicable).

Note: this will not cause updates to a hint which is visible at the time it is called, though the next time a hint is rendered it will show the new property value.

5.7.8.2.14 show

Definition

void **show**()

Description

Changes the series visible state, updates the legend (if applicable) and redraws the owner chart

No effect if the series is already visible.

5.7.8.2.15 showLegend

Definition

void **showLegend**()

Description

Changes the series legend item visible state.

No effect if the series legend item is already visible.

5.7.8.3 Events

5.7.8.3.1 onAfterDataAvailable

Definition

boolean **onAfterDataAvailable**(EJSC.Chart chart, EJSC.Series series)

Description

Fired after the series has processed its data and before the chart is told to redraw. Returning **false** from this event handler will cancel redrawing the chart.

5.7.8.3.2 onAfterVisibilityChange

Definition

boolean **onAfterVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart, boolean visible)

Description

Fired when the series visibility changes. Sends series which changed, its owner chart and its new visible property value.

Returning **false** from this event handler will cancel redrawing the chart.

5.7.8.3.3 onBeforeVisibilityChange

Definition

boolean **onBeforeVisibilityChange**([EJSC.Series](#) series, [EJSC.Chart](#) chart)

Description

Fired before the series visibility is about to change. Sends series which changed, its owner chart. The current visible state of the series may be checked using the series.visible property.

Returning **false** from this event handler will cancel the change in visibility.

5.7.8.3.4 onShowHint

Definition

string **onShowHint**([EJSC.Point](#) point, [EJSC.Series](#) series, [EJSC.Chart](#) chart, string hint_string)

Description

Fired before the displaying the hint, this event allows the current hint string to be overridden. See [Text Replacement Options](#) for a list of the automatic substitutions available.

5.8 Other Classes

5.8.1 EJSC.BarPoint

BarPoint is used to store an X,Y point value (and optionally a label and/or user defined data). This is used in the [EJSC.BarSeries](#) class to store data for each bar to be drawn on the chart. This object is created automatically once data is made available via a [EJSC.DataHandler](#) descendant. BarPoint objects should generally not be created manually.

The constructor expects the X and Y value as well as the [EJSC.BarSeries](#) which owns the point and optionally (leave null if not used) a label and a userdata string value.

Constructor

```
EJSC.BarPoint( float x, float y, string label, string userdata, EJSC.BarSeries
owner )
```

5.8.1.1 Properties

5.8.1.1.1 label (inherited)

Definition

string **label** = null

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.1.1.2 userdata (inherited)

Definition

string **userdata** = null

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.1.1.3 x (inherited)

Definition

float **x** = null

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.1.1.4 y (inherited)

Definition

float **y** = null

Description

Defines point Y value.

5.8.2 EJSC.FloatingBarPoint

FloatingBarPoint is used to store X and min and max Y, or Y and min and max X values for use with a

[EJSC.FloatingBarSeries](#). This information is used by the [EJSC.FloatingBarSeries](#) class to store data for each bar to be drawn on the chart. This object is created automatically once data is made available via a [EJSC.DataHandler](#) descendant. FloatingBarPoint objects should generally not be created manually.

The constructor expects the X, Y, min and max values as well as the [EJSC.BarSeries](#) which owns the point and optionally (leave null if not used) a label and a userdata string value.

Constructor

```
EJSC.FloatingBarPoint( float x, float y, float min, float max, string label,
string userdata, EJSC.FloatingBarSeries owner )
```

5.8.2.1 Properties

5.8.2.1.1 label (inherited)

Definition

string **label** = null

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.2.1.2 max

Definition

float **max** = null

Description

Defines point max value (x or y depending on the series orientation).

5.8.2.1.3 min

Definition

float **min** = null

Description

Defines point min value (x or y depending on the series orientation).

5.8.2.1.4 userdata (inherited)

Definition

string **userdata** = null

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.2.1.5 x (inherited)

Definition

float **x** = null

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.2.1.6 y (inherited)

Definition

float **y** = null

Description

Defines point Y value.

5.8.3 EJSC.GaugePoint

GaugePoint is used to store an X point value (and optionally a label). This is used in the [EJSC.GaugeSeries](#) class to store data the gauge indicator. This object is created automatically once data is made available via a [EJSC.DataHandler](#) descendant. GaugePoint objects should generally not be created manually.

The constructor expects the X value as well as the [EJSC.GaugeSeries](#) which owns the point and optionally (leave null if not used) a label string value.

Constructor

```
EJSC.GaugePoint( float x, string label, EJSC.GaugeSeries owner )
```

5.8.3.1 Properties

5.8.3.1.1 label (inherited)

Definition

string **label** = null

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.3.1.2 userdata (inherited)

Definition

```
string userdata = null
```

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.3.1.3 x (inherited)

Definition

```
float x = null
```

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.4 EJSC.PiePoint

PiePoint is used to store an X point value (and optionally a label value). This is used in the [EJSC.PieSeries](#) class store data for each pie piece to be drawn on the chart. This object is created automatically by once data is made available via a [EJSC.DataHandler](#) descendant. PiePoint objects should generally not be created manually.

The constructor expects the X value as well as the [EJSC.PieSeries](#) which owns the point and optionally (leave null if not used) label and userdata string values.

Constructor

```
EJSC.PiePoint( number x, string label, string userdata, EJSC.PieSeries owner )
```

5.8.4.1 Properties

5.8.4.1.1 label (inherited)

Definition

```
string label = null
```

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.4.1.2 userdata (inherited)

Definition

```
string userdata = null
```

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.4.1.3 x (inherited)

Definition

```
float x = null
```

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.5 EJSC.StockPoint

StockPoint is used to store the data necessary to display stock-related series such as [EJSC.CandlestickSeries](#) and [EJSC.OpenHighLowCloseseries](#). The standard properties are an X point value which defines where along the horizontal axis the point will appear, and the open, close, high and low values used to render the series in the chart. In addition to the standard properties, each point can also store a label and user defined data which may be utilized later during user interaction with the series. StockPoint objects should generally not be created manually.

The constructor expects the X value as well as the open, close, high, and low values, a series which owns the point and optionally (leave null if not used) a label and a userdata string value.

Constructor

```
EJSC.StockPoint( float x, float high, float low, float open, float close,  
string label, string userdata, EJSC.Series owner )
```

5.8.5.1 Properties

5.8.5.1.1 close

Enter topic text here.

5.8.5.1.2 high

Enter topic text here.

5.8.5.1.3 label (inherited)

Definition

string **label** = null

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.5.1.4 low

Enter topic text here.

5.8.5.1.5 open

Enter topic text here.

5.8.5.1.6 userdata (inherited)

Definition

string **userdata** = null

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.5.1.7 x (inherited)

Definition

float **x** = null

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.6 EJSC.XYPoint

XYPoint is used to store a X,Y point value. This is used in series such as [EJSC.LineSeries](#), [EJSC.AreaSeries](#), [EJSC.ScatterSeries](#) and [EJSC.BarSeries](#) to store each point to be drawn on the chart. This object is created automatically by each series once data is made available via a [EJSC.DataHandler](#) descendant. XYPoint objects should generally not be created manually.

The constructor expects the X and Y values as well as the [EJSC.Series](#) which owns the point and an optional (leave null if not used) userdata string value.

Constructor

```
EJSC.XYPoint( number x, number y, string userdata, EJSC.Series owner )
```

5.8.6.1 Properties

5.8.6.1.1 label (inherited)

Definition

string **label** = null

Description

Defines the point label. Currently this is only implemented in [EJSC.PieSeries](#) [EJSC.PiePoint](#) objects.

5.8.6.1.2 userdata (inherited)

Definition

string **userdata** = null

Description

Stores a user-defined string related to the point. This may be used to hold information such as database id values, drill down urls or any other related data. Currently only supported by the [EJSC.XMLDataHandler](#) (full and short formats).

5.8.6.1.3 x (inherited)

Definition

float **x** = null

Description

Defines the point X value. This may be mapped to a text label automatically by the data handler in instances where the point data is not numeric.

5.8.6.1.4 y (inherited)

Definition

float **y** = null

Description

Defines point Y value.

5.9 Using Colors

Using Colors

Colors may be specified in any of the following formats:

RGB: "rgb(<red>, <green>, <blue>)"

example: "rgb(255,0,0)"

RGBA: "rgba(<red>, <green>, <blue>, <opacity>)"

example: "rgba(255,0,0,50)"

HEX: "#<red><green><blue>"

example: "#FF0000"

SHORT HEX: "#<red><green><blue>"

example "#F00"

5.10 Text Replacement Options

Each series has its own set of text replacement options.

5.11 Exporting To SVG

Including SVG Export Functionality

To add the SVG Export functionality to your current implementation, simply include the file immediately after the EJSChart.js

```
<head>
    <script type="text/javascript" src="/EJSChart/EJSChart.js"></script>
    <script type="text/javascript" src="/EJSChart/EJSChart_SVGExport.js"></script>
</head>
```

Exporting SVG

Exporting SVG from your chart is as simple as making a single JavaScript call. The following example shows how to call the [exportSVG](#) method and obtain the resulting SVG. The default configuration will produce complete SVG including headers and sized to match the dimensions of source chart. If additional customization is needed, the options parameter allows for settings to be changed at the time of export.

```
<script type="text/javascript">

    var chart = new EJSC.Chart("myChart", {});
    var series = new EJSC.LineSeries(
        new EJSC.ArrayDataHandler([[1,1],[2,2],[3,3],[4,2],[5,1]]),
        {}
    );
    chart.addSeries(series);

    function buttonClick() {
        alert(chart.exportSVG());
    }
}
```

```
</script>
<button onclick="buttonClick();">Export SVG</button>
```

6 Getting Support

There are a wide variety of technical support options available for Emprise software products. For users who have purchased the Developer or Enterprise editions, and customers with maintenance plans, support options may include Priority E-mail Support and our Technical Support Hotline. Technical support documents, help files and access to our support forums are available to all users of Emprise software products.

Documentation

Emprise JavaScript Charts documentation is available in several formats:

- [Online Web Documentation \(Searchable\)](#)

Downloadable Formats:

- [PDF Manual](#)
- [Windows HTML Help \(.chm\)](#)
- [Classic Windows Help \(.hlp\)](#)

Example Charts

Our website contains a wide variety of example charts to assist you in creating and customizing your own. All examples include full JavaScript and data descriptions as well as links to the relevant help files for each property used.

- [Line Chart](#)
- [Area Chart](#)
- [Bar Chart](#)
- [Pie Chart](#)
- [More...](#)

Support Forums

Share questions, suggestions, and information about your Emprise software products with other

users and the Emprise support and development staff in our [Support Forums](#).

Contact Us

If you cannot find an answer to your question from the resources listed above, send our support department a message and we will get back to you as soon as we can.

General Information & Questions

info@ejschart.com

Sales Related Inquiries

sales@ejschart.com

Technical Support

support@ejschart.com

Phone

Sales: +1 (860) 464-8555

Support: (See support contract)

Mailing Address:

PO Box 129

Ledyard, CT 06339

USA